


BAHRIA CLASSIFICATION SOCIETY



RULES FOR CLASSIFICATION OF NAVAL SHIPS

Chapter 102 Hull Structure & Ship Equipment

July 2022

This latest edition incorporates all rule changes. The latest revisions are shown with a vertical line. The section title is framed if the section is revised completely. Changes after the publication of the rule are written in red color.

Unless otherwise specified, these rules apply to ships for which the date of contract for construction is on or after July 2022.

This publication is available in print and electronic pdf versions. Once downloaded, this document will become uncontrolled. Please check the website below for the valid version.

<https://www.bahriaclassificationsociety.org/>

All rights are reserved by Bahria Classification Society, and content may not be reproduced , disseminated , published , or transferred in any form or by any means , except with the prior written permissions of Bahria Classification Society.

BAHRIA CLASSIFICATION SOCIETY

Head Office

Third Floor, Bahria Complex II, M.T Khan Road, Karachi

Tel : +92 21 35640738-Ext 603,605

Email : riazuddin@bahriafoundation.com

Website : <https://www.bahriaclassificationsociety.org/>

Chapter 102 – Hull Structures and Ship Equipment

Section 1	General	Page
A.	General	1- 2
B.	Definitions.....	1- 3
C.	General Aspect On Design	1- 7
D.	Documents	1- 9
E.	Workmanship	1- 10
Section 2	Subdivision and Stability	
A.	General.....	2- 2
B.	Intact Stability	2- 2
C.	Subdivision and Damage Stability	2- 10
D.	Tests.....	2- 14
E.	Guidelines for Computation	2- 15
F.	Stability Information	2- 16
G.	Marking of Maximum Draught.....	2- 16
H.	Draught Readings	2- 16
Section 3	Materials and Corrosion Protection	
A.	General.....	3- 2
B.	Hull Structural Steel.....	3- 2
C.	Forged Steel and Cast steel	3- 3
D.	Aluminium Alloys	3- 3
E.	Reduction of the Corrosion Risk by Special Measures in Design and Construction	3- 7
F.	Corrosion Protection.....	3- 7
Section 4	Design Principles	
A.	General.....	4- 3
B.	Design of Plates	4- 4
C.	Scantlings of Secondary Stiffening Members, Primary Supporting Members and Pillars	4- 7
D.	End Attachments	4- 13
E.	Effective Width of Plating.....	4- 18
F.	Proof of Buckling Strength	4- 18
G.	Structural Details	4- 30
H.	Evaluation of Notch Stress	4- 32
Section 5	Design Loads	

Contents

A.	General, Definitions	5- 2
B.	Design Values of Acceleration Components.....	5- 3
C.	External Sea Loads	5- 4
D.	Loads on Watertight and Non-Watertight Partitions.....	5- 7
E.	Loads on Decks.....	5- 7
F.	Loads on Tank Structures	5- 9
G.	Loads due to Military Equipment	5- 10
H.	Deadweight of Structures	5- 13
I.	Wind Loads.....	5- 13

Section 6 Longitudinal Strength

A.	General.....	6- 2
B.	Definition of Load Cases	6- 4
C.	Hull Girder Loads	6- 4
D.	Structural Resistance	6- 9

Section 7 Bottom and Shell Structures

A.	General, Definitions	7- 2
B.	Plating	7- 2
C.	Secondary Stiffeners	7- 4
D.	Primary Members	7- 5
E.	Appendages and Internals.....	7- 7
F.	Special Strengthening	7- 8

Section 8 Decks and Longitudinal Walls

A.	General.....	8- 2
B.	Plating	8- 2
C.	Secondary Stiffeners	8- 2
D.	Primary Members	8- 2
E.	Elastic Mounting of Deckhouses.....	8- 3
F.	Helicopter Deck	8- 5

Section 9 Watertight and Non-watertight Bulkheads

A.	General.....	9- 2
B.	Scantlings of Single Plate Bulkheads	9- 4
C.	Corrugated Bulkheads.....	9- 5
D.	Shaft Tunnels	9- 5

Section 10 Tank Structures

A.	General.....	10- 2

Contents

B.	Scantlings.....	10- 3
C.	Detached Tanks	10- 3
D.	Testing for Tightness	10- 4

Section 11 Stem and Sternframe Structures

A.	Plate Stem and Bulbous Bow	11- 2
B.	Stern frame.....	11- 2
C.	Propeller Brackets.....	11- 2

Section 12 Rudder and Manoeuvring Arrangement

A.	General, Definitions	12- 2
B.	Rudder Force and Torque	12- 3
C.	Scantlings of the Rudder Stock	12- 5
D.	Rudder Horn of Semi Spade Rudders	12- 8
E.	Rudder Couplings.....	12- 10
F.	Rudder Body, Rudder Bearings	12- 13
G.	Design Yield Moment of Rudder Stock	12- 16
H.	Stopper, Locking Device.....	12- 16
I.	Fin Stabilizers	12- 16

Section 13 Strengthening for Navigation in Ice

A.	General.....	13- 2

Section 14 Foundations, Hatchways and Hatchcovers

A.	General.....	14- 2
B.	Foundations.....	14- 2
C.	Hatchways.....	14- 7
D.	Hatch Covers.....	14- 8
E.	Strength and Securing of Small Hatches on the Exposed Fore Deck.....	14- 9
F.	Engine Room Hatchways	14-12
G.	Miscellaneous Openings in Freeboard and Superstructure Decks	14-12

Section 15 Welded Joints

A.	General.....	15- 2
B.	Design	15- 3
C.	Stress Analysis.....	15- 13

Section 16 Noise, Vibration and Shock Considerations

A.	General.....	16- 2

Contents

B.	Acoustics	16- 3
C.	Vibration	16- 15
D.	Shock Strength	16- 20

Section 17 Fatigue Strength

A.	General.....	17- 2
B.	Fatigue Strength Analysis for Free Plate Edges and for Welded Joints Using Detail Classification.....	17- 4
C.	Fatigue Strength Analysis for Welded Joints Based on Local Stresses	17- 9

Section 18 Equipment

A.	General.....	18- 2
B.	Equipment Numeral.....	18- 2
C.	Anchors	18- 3
D.	Chain Cables	18- 4
E.	Chain Locker	18- 5
F.	Mooring and Towing Equipment.....	18- 6
G.	Shipboard Fittings and Supporting Hull Structures Associated With Mooring and Towing	18- 6

Section 19 Hull Outfit

A.	Partition Bulkheads	19- 2
B.	Breakwater	19- 2
C.	Sheathings and Ceilings.....	19- 2
D.	Openings in Hull and Superstructures	19- 3
E.	Scuppers, Sanitary Discharges and Freeing Ports	19- 6
F.	Air Pipes, Overflow Pipes, Sounding Pipes	19- 7
G.	Ventilators	19- 8
H.	Stowage of Containers	19- 8
I.	Lashing Arrangements	19- 9
J.	Life Saving Appliances	19- 9
K.	Signal, Radar and Sensor Masts	19- 9
L.	Loading and Lifting Gear	19- 11
M.	Guard Rails	19- 12
N.	Ammunition Rooms	19- 15
O.	Access to Ships.....	19- 15
P.	Bottom Plugs.....	19- 16

Section 20 Structural Fire Protection

A.	General.....	20- 2
B.	Basic Requirements for all Ships	20- 4
C.	Additional Requirements for Ships with Class Notation SFP	20- 7

Section 21 Residual Strength

A.	General.....	21- 2
B.	Requirements for Residual Strength.....	21- 2
C.	Measures to Improve Residual Strength.....	21- 4

Section 22 Amphibious Warfare Ships

A.	General.....	22- 2
B.	Bow Doors and Inner Doors.....	22- 2
C.	Side Shell Doors and Stern Doors.....	22- 8
D.	Well Dock.....	22- 10
E.	References to Further Requirements for Amphibious Warfare	22- 12

Section 23 Provisions for Flight Operations

A.	General.....	23- 2
B.	Flight Decks.....	23- 3
C.	Hangars.....	23- 8
D.	Provisions for Drones (UAV)	23- 9
E.	References to Further Requirements for Flight Operations	23- 10

SECTION 1

GENERAL

	Page
A. General	1-2
1. Application	
2. Equivalence	
3. Notations	
4. Ambient conditions	
B. Definitions	1-3
1. General	
2. Co-ordinate system	
3. Principal dimensions	
4. Frame spacing a	
5. Displacement Δ	
6. Block coefficient C_B	
7. Ship speed	
8. Rated driving power P	
9. Auxiliary electrical power	
10. Definition of decks	
11. International conventions and codes	
12. Position for the arrangements of hatches, doors, manholes:	
13. Standard height of superstructure	
14. Material properties	
C. General Aspects on Design	1-8
1. Accessibility	
2. Stability	
3. Survivability	
D. Documents	1-11
1. Documents for approval	
2. Documents on board	
3. Operating and maintenance instructions	
E. Workmanship	1-12
1. General	
2. Structural details	
3. Corrosion protection	

A. General

1. Application

These Rules apply to naval surface ships classed **1Np**. For Characters of Classification and Class Notations, see Chapter 101 - Classification and Surveys (Naval Ship Technology).

1.1 The requirements apply to hull structures and equipment of monohull, displacement type of naval ships. They may also be applied to other types of naval surface ships and complete (parts of) auxiliary naval ships with Notation **AUX-N** according to mutual agreement.

1.2 For design and dimensioning of special hull structures, e.g. catamarans, SWATH, hydrofoil craft, surface effect ships, air-cushion vehicles the **BCS** Rules Part C, Chapter 7 - High Speed Craft, Section 3 may be applied, see also Chapter 101 - Classification Surveys, Section 2, C.

1.3 The right of interpretation of their technical Rules rests with **BCS** alone.

2. Equivalence

2.1 Naval ships deviating from the **BCS** Rules in their type, equipment or in some of their parts may be classed, provided that their structures or equipment are found to be equivalent to the **BCS** requirements for respective Class.

2.2 In this respect, **BCS** can accept alternative design, arrangements and calculation/analyses (FE, FMEA etc.) which are suitable to satisfy the intent of respective **BCS** requirements and to achieve equivalent safety level.

3. Notations

3.1 Service range

Ships complying with the rule requirements for a restricted range of service will have a corresponding Notations **Y**, **K50/20**, **K6** affixed to the Character of Classification. The Notation will indicate the relevant kind of restriction, e.g.:

- Geographical designation (name) of the opera-

tion range

- Distance from defined ports and coast line
- Restrictions related to weather conditions (wave height, etc.), possibly combined with speed limitations

The applicable range of service will be agreed between the Naval Authority and **BCS**.

3.2 Class Notation IWS

For ships suitable for in-water survey which will be assigned the Class Notation **IWS**, the requirements of Section 3, F.5.1 are to be observed.

3.3 Class Notations RSD and ERS

Naval ships, for which special analysis procedures have been carried out, will be assigned the Notation **RSD** ("Rational Ship Design").

If the data developed for **RSD** are made available in a database to provide assistance during operation, the Class Notation **ERS** will be assigned. See also Chapter 101 - Classification and Surveys, Section 2, C.

3.4 Further notations

Additional details regarding the definition of ship types, structural assessment, machinery and electrical installations and special equipment are given in Chapter 101 - Classification and Surveys, Section 2.

4. Ambient conditions

4.1 General operating conditions

4.1.1 The selection, layout and arrangement of the ship's structure and all shipboard machinery shall be such as to ensure faultless continuous operation under defined standard ambient conditions.

More stringent requirements must be observed for Class Notation **AC1** (see Chapter 101 - Classification and Surveys, Section 2, C).

For the Class Notation **ACS** variable requirements for unusual types and/or tasks of naval ships can be discussed case by case, but shall not be less than the standard requirements.

Components in the machinery spaces or in other spaces which comply with the conditions for Notations **AC1** or **ACS** must be approved by **BCS**.

4.1.2 Inclinations and movements of the ship

The design conditions for static and dynamic inclinations of a naval ship have to be assumed independently from each other. The standard requirements and the requirements for Class Notation **AC1** are defined in Table 1.1.

The effects of elastic deformation of the ship's hull on the machinery installation have to be considered.

4.1.3 Environmental conditions

The design environmental conditions for a naval ship are contained in Table 1.2. In addition to the standard requirements also the requirements for Class Notation **AC1** are specified.

4.2 Vibration

Design, construction and installation must take account of stresses caused by vibration.

Criteria regarding vibration are described in Section 16, C. and Chapter 104 - Propulsion Plants, Section 1, D.2.

4.3 Shock

For consideration of shock loads, see Section 16, D.

B. Definitions

1. General

In the following definitions only SI-units are used. Unless otherwise mentioned, the dimensions according to 2., 3. and 4. are to be inserted [m] into the formulae stated in the following Sections.

2. Co-ordinate system

For the use of these Rules the fixed, right-handed co-ordinate system 0, x, y, z as defined in Fig. 1.1 is

introduced. The origin of the system is situated at the aft end of the length **L**, at centerline and on the moulded baseline at the ship's keel. The x-axis points in longitudinal direction of the ship positive forward, the y-axis positive to port and the z-axis positive upwards. Angular motions are considered positive in a clockwise direction about the three axes.

3. Principal dimensions

3.1 Length **L**

The length **L** of the ship is the distance from the moulded side of the plate stem to the fore side of the stern or transom measured on the design waterline at the draught **T**. Other forms of stem are to be specially considered.

3.2 Length **L_c** (according to ICLL, MARPOL)

The length **L_c** is to be taken as 96% of the total length on a waterline at 85% of the least moulded depth **H_c** measured from the top of the keel, or as the length from the fore side of the stem to the axis of the rudder stock on that waterline, if that be greater. In ships with a rake of keel the waterline on which this length is measured shall be parallel to the designed waterline..

3.3 Length **L_{OA}**

The length over all **L_{OA}** is the distance between the most forward and most aft element of the ship, permanent outfit included, measured parallel to the design water line.

3.4 Forward perpendicular **FP**

The forward perpendicular coincides with the moulded side of the plate stem on the waterline on which the length **L** is measured.

3.5 Breadth **B**

The breadth **B** is the maximum moulded breadth of the design waterline at draught **T**.

3.6 Breadth **B_{Max}**

The breadth **B_{Max}** is the greatest moulded breadth of the

ship. For ships with unusual cross section the breadth will be specially considered.

3.7 Depth H

The depth **H** is the vertical distance, at the middle of the length **L**, from the base line to top of the deck beam at side on the uppermost continuous deck.

3.8 Draught T

The draught **T** is the vertical distance, at the middle of

the length **L**, from base line to the deepest design waterline, as estimated for the lifetime of the ship

3.9 Draught T_{MAX}

The draught **T_{MAX}** is the vertical distance between the lowest point of the immersed hull including appendages (e.g. domes, rudders, propellers, thrusters, etc.) and the design waterline, movable parts, like fins, rudder propellers, sonars, etc. considered retracted.

Table 1.1 Design limit for ship inclinations and movements

Type of movement	Type of inclination	Design limit conditions	
		Standard requirements	Notation AC1
Static condition	Inclination athwartships: (1) Main and auxiliary machinery	15°	25°
	Other installations (2)	22,5°	25°
	Ship's structure	acc. to stability requirements	acc. to stability requirements
	Inclinations fore and aft: (1) Main and auxiliary machinery	5°	5°
	Other installations (2)	10°	10°
	Ships structure	acc. to stability requirements	acc. to stability requirements
Dynamic condition	Rolling: Main and auxiliary machinery	22,5°	30°
	Other installations (2)	22,5°	30°
	Pitching: Main and auxiliary machinery	7,5°	10°
	Other installations (2)	10°	10°
	Accelerations: Vertical (pitch and heave)	a_z [g] (3)	32 °/s ² (pitch) 1,0 g (heave)
	Transverse (roll, yaw and sway)	a_y [g] (3)	48 °/s ² (roll) 2 °/s ² (yaw) a_y [g] (3) (sway)
	Longitudinal (surge)	a_x [g] (3)	a_x [g] (4)
	Combined acceleration	acceleration ellipse (3)	direct calculation
(1) Thwart ships and fore and aft inclinations may occur simultaneously			
(2) Ship's safety equipment, e.g. emergency power installations, emergency fire pump and their device switch gear and electric/electronic equipment			
(3) Defined in Section 5, B. (g = acceleration of gravity)			
(4) To be defined by direct calculation			

Table 1.2 Design environmental conditions

Environmental area	Parameters	Design conditions	
		Standard	Notation AC1
Outside the ship/air	Temperature at atmospheric pressure at relative humidity of	- 25 to + 45 °C 1000 mbar 60 % (2)	- 30 to + 55 °C (1) 900 to 1100 mbar 100 %
	Temperature for partially open spaces at the same conditions	-	- 10 to + 50 °C (1)
	Salt content	1 mg/m ³	1 mg/m ³
		withstand salt-laden	withstand salt-laden spray
	Dust/sand	to be considered	filters to be provided
	Wind velocity (systems in operation)	43 kn (3)	90 kn
	Wind velocity (systems out of operation)	86 kn (3)	100 kn
Outside the ship/seawater	Temperature (4)	- 2 to + 32 °C	- 2 to + 35 °C
	Density acc. to salt content	1,025 t/m ³	1,025 t/m ³
	Flooding	withstand temporarily	withstand temporarily
Outside the ship/icing of surface	Icing on ship's surfaces up to 20 m above waterline	see Section 2, B.3.4	see Section 2, B.3.4
Outside the ship/navigation in ice	Ice Class B	Drift ice in mouth of rivers and coastal	Drift ice in mouth of rivers and coastal regions
Entrance to the ship/for design of heating/cooling systems	Air temperature	-15 to + 35°C	-15 to + 35°C
	Max. heat content of the air	100 kJ/kg	100 kJ/kg
	Sea water temperature	- 2 to + 32 °C	- 2 to + 32 °C
Inside the ship/all spaces (5)	Air temperature at atmospheric pressure at relative humidity of	0 to + 45 °C 1000 mbar up to 100% (+45°)	0 to + 45 °C 1000 mbar 100 %
	Salt content	1 mg/m ³	1 mg/m ³
	Oil vapour	withstand	withstand
	Condensation	to be considered	to be considered
Inside the ship/air- conditioned areas	Air temperature	0 to + 40 °C	0 to + 45 °C
	Max. relative humidity	80%	100 %
	Recommended ideal climate for manned computer spaces	-	Air temperature + 20 to + 22 °C at 60 % rel. humidity
Inside the ship/in electrical devices with higher degree of heat dissipation	Air temperature	0 to + 55 °C	0 to + 55°C
	Max. relative humidity	100 %	100 %
(1) Higher temperatures due to radiation and absorption heat have to be considered (2) 100% for layout of electrical installations (3) For lifting devices according to BCS Rules - Guidelines for the Construction Survey of Lifting Appliances, Section 2 (4) BCSS may approve lower limit water temperatures for ships operating only in special geographical areas (5) For recommended climatic conditions in the ship's spaces see also Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 11, F.			




Fig. 1.1 Coordinate system and angles of motion

4. Frame spacing a

The frame spacing a will be measured from moulding edge to moulding edge of frame.

5. Displacement Δ

The displacement Δ represents the mass of the ship in metric tons at the draught T .

6. Block coefficient C_B

Moulded block coefficient at design draught T , based on the length L .

$$C_B = \frac{\text{moulded displacement volume [m}^3\text{] at } T}{L \cdot B \cdot T}$$

7. Ship speed**7.1 Rated speed v_0**

Expected maximum, continuous ahead speed v_0 [kn] of the ship in calm water at the draught T , when the total available rated driving power is exclusively used for propulsion devices.

7.2 Maximum speed $v_{\max}$

Expected maximum ahead speed $v_{\max}$ [kn] of the ship in calm water, at the draught T , when the total available maximum driving power is exclusively used for propulsion devices. The speed is related to an overload condition, permissible only for a defined, relatively short time period.

7.3 Cruising speed v_M

Expected economic, continuous ahead cruising speed v_M [kn] of the ship, which provides the maximum radius of action.

7.4 Astern speed v_a

Maximum intended astern speed v_a [kn] of the ship.

8. Rated driving power P

The rated driving power [kW] is defined as continuous power to be delivered by the propulsion machinery for running at rated speed v_0 .

9. Auxiliary electrical power

The auxiliary electrical power [kVA] is defined as the

continuous electrical power at continuous speed v_0 , which is not directly used for propulsion of the ship, but for driving all kinds of auxiliary devices and equipment. The degree of redundancy shall be defined in the building specification.

10. Definition of decks

10.1 Bulkhead deck

Bulkhead deck is the deck up to which the watertight bulkheads are extended to.

10.2 Freeboard deck

The freeboard deck is normally the uppermost complete deck exposed to weather and sea, which has permanent means of closing all openings in the weather part thereof, and below which all openings in the sides of the ship are fitted with permanent means of watertight closing.

10.3 Strength deck

Strength deck is the deck or the parts of a deck which form the upper flange of the effective longitudinal structure.

10.4 Weather deck

All free decks and parts of decks exposed to the sea are defined as weather deck.

10.5 Internal decks

Internal decks are decks inside closed structures.

11. International conventions and codes

From legal point of view the international conventions and codes are not valid for naval ships. But there is a tendency that Naval Authorities request more and more the application of such Regulations.

11.1 MARPOL

International convention for the prevention of pollution from ships, 1973 including 1978 Protocol as amended.

11.2 ICLL

International convention on Load Lines, 1966 as amended.

11.3 SOLAS

International convention for the Safety of Life at Sea, 1974, as amended.

12. Position for the arrangements of hatches, doors, manholes:

Pos. 1- on exposed freeboard decks

- on exposed superstructure decks within the forward quarter of L
- on the first exposed superstructure deck above the freeboard deck within the forward quarter of L_c

Pos. 2- on exposed superstructure decks aft of the forward quarter of L_c located at least one standard height of superstructure above the freeboard deck

- on exposed superstructure decks within the forward quarter of L_c located at least two standard heights of superstructure above the freeboard deck

13. Standard height of superstructure

The standard height of superstructures can be defined as follows:

- 1.8 m for ships with a length L less than 75 m
- 2.3 m for ships with a length L of 125 m or more

The standard heights at intermediate length of the ship shall be obtained by linear interpolation

14. Material properties

14.1 Yield stress R_{eH}

The yield stress R_{eH} of the material is defined as the

nominal upper yield point R_{eH} or, for materials where this point is not existing, the nominal 0.2% proof stress $R_{p0.2}$ measured in N/mm².

14.2 Tensile strength R_m

The tensile strength R_m of the minimum guaranteed tensile strength of the material as defined in the Rules, Chapter 103, Materials.

14.3 Modulus of Elasticity E

The modulus of Elasticity E is to be set to 206000 N/mm² for mild and higher strength structural steels. For other materials like aluminum alloys, high strength and austenitic steels E is defined in the BCS Rules Materials.

14.4 Poisson ratio ν

The Poisson ratio ν , if not otherwise stated, is defined as:

- 0,3 for steel
- 0,33 for aluminum alloys

C. General Aspects on Design

1. Accessibility

All parts of the hull are to be accessible for survey and maintenance. For small spaces not intended to be accessible, the corrosion protection requirements according to Section 3, F.3. have to be observed.

2. Stability

2.1 Intact stability

Ships will be assigned Class only after it has been proven and demonstrated, that their intact stability is adequate for the service intended.

Adequate intact stability means compliance with the standards laid down by the Naval Authority in the building specification and agreed by **BCS**.

2.2 Damage stability

Criteria for damage stability are specified in Section 2, C. The subdivision status of the ship is defined by a five digit code.

3. Survivability

3.1 Definition

Survivability comprises the following three aspects:

- Susceptibility
- Vulnerability
- Recoverability

3.2 Susceptibility

3.2.1 Susceptibility is the ability of the naval ship to respond to threats, including practicing of a low signature, evasion and defeat before impact.

3.2.2 The effectiveness of an active defeat of a threat is a matter of the available military sensors and weapons of the naval ship and is therefore not subject of these Rules.

3.2.3 Aspects regarding signature

3.2.3.1 General

A successful signature control will be able to contribute to susceptibility and is influenced very much by the design of a naval ship. It demands special consideration for the hull structures' design and the equipment to be used. The relative importance of the different aspects of the ship's signature and the intended extent of compensation has to be defined by the Naval Authority according to the Concept of Operations and summarized in a Signature Concept

The main types of such signatures are listed in 3.2.3.2 to 3.2.3.8 and relevant requirements, if applicable, are specified.

3.2.3.2 Visibility

Visibility is still a design aspect in not open sea areas, like littoral waters and between islands, where it is not possible to make full use of electronic sensors. Visibility may be influenced by low and flat superstructures of the ship and by camouflage paint.

3.2.3.3 Infra-red signature (IR)

A naval ship may create a characteristic temperature level above environmental temperature which can lead to its detection. As the output of the hot exhaust gases from the main propulsion plant (internal combustion engines, gas turbines) show in general the highest temperature level, a careful design and positioning of these exhaust outlets will be necessary. The outlets may be water-cooled, may penetrate the ship's shell below the design waterline or very near above it, or even may be switched to the expected enemy-free side of the ship. The requirements for such a piping system are defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8, M.

In addition it may become necessary to reduce and/or equalize the temperature of the different parts of the ship's surface structure including the hull. This can be achieved by a seawater cooling system for which the requirements are given in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, P.

3.2.3.4 Radar cross section (RCS)

The radar reflection of the ship's body and equipment is the most important signature at large distances. Favourable stealth characteristics of the ship aim to achieve a relatively late and dim identification of the naval ship. This can be achieved by a flat ship silhouette, inclined side shell (flare) and superstructure walls (tumblehome), by providing large, flat surfaces with sharp edges which may cover also the ship's equipment, and by avoiding "corner effects".

3.2.3.5 Electromagnetic emissions

Naval ships disturb the natural magnetic field while moving at sea. This effect can be used for detection or immediate weapon action. These unintentional

electromagnetic emissions may be reduced by the consequent use of non-ferrous and/or non-magnetizable materials for hull, machinery and equipment. The types of non-magnetizable austenitic steels suitable for the hull structure of naval ships are defined in Section 3, B.

4. Further details and the application of non-magnetizable materials for forged or cast steel components, anchor chains, etc. are given in the **BCS** Chapter 103 - Special Materials for Naval Ships.

Further methods may be a kind of Faraday cage around devices with strong electromagnetic emissions or a degaussing system. The magnetic field induced by a degaussing system shall be capable of a real-time compensation of the permanent, the induced and the eddy-current-generated magnetizations of the ship's hull. If the ship is equipped such a system the Class Notation **DEG** may be assigned.

4.1.1.1 Radiated-noise

It must be a design target to "hide" the underwater noise of the ship within the natural noise of the sea as far as possible and to avoid noise spectra, which are specific for a certain type of naval ship.

The acoustic signature, like airborne noise, underwater noise and sonar self noise as well as the requirements for the acoustic verification by measurements are given in Section 16, B.

4.1.1.2 Hydrodynamic pressure

Hydrodynamic pressures can cause an activating of underwater weapons. This influence can be reduced by hydro mechanical optimization of the propulsion elements and also of the appendages to the underwater hull.

The requirements for naval propellers and for other propulsion systems, like cycloidal propellers, azimuthing propulsors, dynamic positioning systems are given in Chapter 104 - Propulsion Plants, Section 7.

4.1.1.3 Solid and liquid waste

Detection of the position of the naval ship may also be possible due to liquid and/or solid wastes. Treatment

and/or storage of these wastes on board lead to considerable space requirements, which constitute a not negligible design criterion.

The requirement for waste treatment are given in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 10 and special aspects for fire fighting in case of waste incineration are defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, L.

4.2 Vulnerability

4.2.1 Vulnerability is the ability of a naval ship is to be to withstand a defined impact of military weapons and to maintain at least a basic degree of safety and operability to carry out its mission or a major part thereof.

Vulnerability is threatened by:

- Loss of global strength of the hull structure
- Loss of buoyancy and/or stability
- Loss of maneuverability
- Fire in the ship and ineffective fire protection or fire fighting capability
- Direct destruction of machinery, equipment or control systems
- Direct destruction of weapons and sensors
- Threat to the crew

4.2.2 Measures for improved survivability of the ship's structure

The design of a ship which is classed as naval ship has to consider a series of possible measures to improve vulnerability. The **BCS** Rules for naval surface ships offer various measures and Class Notations to achieve improved vulnerability. The degree of including such measures in an actual project has to be defined by the Naval Authority.

4.2.2.1 Residual strength

Residual strength after structural damage caused by military action has to be considered and calculated. Degree and character of the damage and any other basic assumptions for these calculations have to be defined by the Naval Authority in the building specification. The relevant calculations and their results have to be submitted to **BCS** if the Class Notation **RSM** shall assigned, for further details see Section 21.

4.2.2.2 Shock strength and protection

The assessment of shock effects, recommendations to improve the shock strength of the hull, measures for the protection of equipment and crew against shock, etc. are given in Section 16, D.

4.2.2.3 Structural fire protection

The basic requirements for structural fire protection and the more stringent requirements for Class Notation **SFP** are defined in Section 20.

4.2.2.4 Protection by armour

Naval ships may be exposed to high performance projectiles from even relatively small arms and to splinters from external and internal blasts. The actual threat and its level of protection by lightweight compound armour or other adequate measures have to be defined by the Naval Authority in the building specification.

Special attention has to be given to the connection of the armour components with the structural elements of the ship. Forces from loads on the ship's structure should not be transferred to armour components. But deadweight of armour and ballistic forces are to be considered for the design loads of the ship's structure.

According to the type and capacity of such armour, it has to be agreed between Naval Authority, Shipyard and **BCS** which elements of the ship remain intact for defined military threat.

If a noteworthy application of armour is applied in a professional manner, the Class Notation **ARM PLT** may be assigned.

4.2.3 Measures for improved vulnerability of the ship's machinery and systems

In Sections 1 of Chapters 104 and 107 of these **BCS** Naval Rules additional aspects to improve vulnerability applying machinery and systems are specified.

4.2.4 Vulnerability analysis

The aspects described above and additional other ones depending on the actual project should be considered already in an early stage of ship design. But even during the Classification procedure it might be reasonable to make a final check if all possibilities are realized and the different measures are harmonized.

3.4 Recoverability

Recoverability occurs after initial damage and focuses on the ability of ship and crew to restore functionality. Besides the measures described under vulnerability, recoverability depends very much on the organization, number and skills of the crew and is therefore not subject of these Rules.

D. Documents

1. Documents for approval

1.1 The scope of documents to be submitted for approval is defined in Chapter 101, Section 4, Table 4.1. All documents have to be submitted to **BCS** English language.

1.2 The drawings must contain all data necessary for assessment and approval. Where deemed necessary, calculations and descriptions of the ship's elements are also to be submitted. Any non-standard symbols used are to be explained in a key list. All documents must show the number of the project and the name of the Naval Authority and/or Shipyard.

1.3 The supporting calculations shall contain all necessary information concerning reference documents (parts of the specification, drawings, and global computations, computations for elements, following calculations). Literature used for the calculations has to be cited, important but not commonly known sources shall be added as copy.

The choice of computer programs according to the "State of the Art" is free. The programs may be checked by **BCS** through comparative calculations with test examples. A generally valid approval for program is, however, not given by **BCS**.

The calculations have to be compiled in a way which allows identifying and checking all steps of the calculations with regard to input and output in an easy way. Handwritten, easily readable documents are acceptable.

Comprehensive quantities of output data shall be presented in graphic form. A written comment to the main conclusions resulting from the calculations has to be provided.

1.4 **BCS** reserve the right to require additional documentation if the submitted one is insufficient for an assessment of the ship or essential parts thereof. This may especially be the case for plants and equipment related to new developments and/or which are not tested on board to a sufficient extent.

1.5 The drawings are to be submitted in triplicate, all calculations and supporting documentation in one copy for examination at a sufficiently early date to ensure that they are approved and available to the Surveyor at the beginning of the manufacture or installation of the ship or of important components.

1.6 The survey of the ship's construction will be carried out on the basis of approved documents. Once the documents submitted have been approved by they are binding for the execution of the work .
quent modifications and extensions require the of **BCS** fore becoming effective.

2. Documents on board

To allow quick action in case of surveys, special

operation and especially in case of damage, the following documentation must be kept on board and shall be made available to the BCS Surveyor on request

- Class Certificates
- Reports on surveys performed previously
- Final Loading Manual and Stability Handbook
- Description of corrosion control system
- Approved drawings and other documentation handed out to the Naval Authority and containing particulars or instructions of significance in respect of the Classification requirements (e.g. use of special steel, etc.)
- List of important testing/monitoring procedures to be followed in connection with validity of Class

3. Operating and maintenance instructions

The operating and maintenance instructions, warning signs, etc. have to be prepared in English and in the user's language.

E. Workmanship

1. General

1.1 Requirements to be complied with by the Shipyard and the manufacturers

1.1.1 Every manufacturing plant must be provided with completion of such checks and corrections by the suitable equipment and facilities to enable proper handling plant. of the materials, manufacturing processes, structural components, etc. **BCS** reserves the right to inspect the plant accordingly or to restrict the scope of manufacture to the potential available at the plant.

The manufacturing plant must have at its disposal sufficiently qualified personnel **BCS** must be advised of the names and areas of responsibility of all supervisory and control personnel. **BCS** reserves the right to require proof of qualification.

1.1.2 The shipyard or manufacturing plant and its subcontractors must get approval from **BCS** for the type of work they provide for the manufacture and installation of naval ships. Approval can only be given if the conditions defined in detail in the **BCS** Rules Part A, Chapter 2 Materials and 3 - Welding are complied with.

1.1.3 The fabrication sites, stores and their operational equipment shall also comply with the requirements of the relevant Safety Authorities and Professional Associations. The shipyard or manufacturing plant is alone responsible for compliance.

1.2 Quality control

1.2.1 The Shipyard shall operate a quality assurance system, such as ISO 9001 or equivalent.

1.2.2 As far as required and expedient, the manufacturer's personnel has to examine all structural components both during the manufacture and on completion, to ensure that they are complete, that the dimensions are correct and that workmanship is satisfactory and meets the standard of good shipbuilding practice.

1.2.3 Upon inspection and corrections by the manufacturing plant, the structural components are to be shown to the **BCS** Surveyor for inspection, in suitable sections, normally in unpainted condition and enabling proper access for inspection.

1.2.4 The Surveyor may reject components that have not been adequately checked by the plant and may demand their re-submission upon successful

2. Structural details

2.1 Details in manufacturing documents

2.1.1 All significant details concerning quality and functional ability of the components concerned shall be entered in the manufacturing documents, workshop drawings, etc. This includes not only scantlings but, where relevant, such items as surface conditions (e.g. finishing of flame cutting edges and weld seams), and

special methods of manufacture involved as well as inspection and acceptance requirements and, where relevant, permissible tolerances.

A production standard which considers the special requirements for the manufacturing of naval ships has to be defined by the Shipyard or manufacturing plant and approved by **BCS**

For details of welded joints see Section 15 and Rules - Chapter 3 - Welding, Section 12 –Welding Hull Structure.

2.1.2 If, due to missing or insufficient details in the manufacturing documents, the quality or functional ability of the component cannot be guaranteed or is doubtful, **BCS** may require appropriate improvements. This includes the provision of supplementary or additional parts, e.g. reinforcements, even if these were not required at the time of plan approval.

2.2 Cut-outs, plate edges

2.2.1 The free edges (cut surfaces) of cut-outs, hatch corners, etc. are to be properly prepared and are to be free from notches. As a general rule, cutting drag lines, etc. must not be welded out, but are to be smoothly ground. All edges should be broken or in cases of highly stressed parts, should be rounded off.

2.2.2 Free edges on flame or machine cut plates or flanges are not to be sharp cornered and are to be finished off as laid down in 2.2.1. This also applies to cutting drag lines, etc., in particular to the upper edge of shear strake and analogously to weld joints, changes in sectional areas or similar discontinuities.

2.3 Cold forming

2.3.1 For cold forming, like bending, flanging, beading of plates the minimum average bending radius should not be less than 3 times the plate thickness t and must be at least $2t$. Regarding the welding of cold formed areas, see Section 15, B.2.6.

2.3.2 In order to prevent cracking, flame cutting flash or sheering burrs must be removed before cold forming. After cold forming all structural components and, in particular, the ends of bends (plate edges) are to be examined for cracks. Except in cases where edge cracks are negligible, all cracked components are to be rejected. Repair welding is not permissible.

2.4 Assembly, alignment

2.4.1 The use of excessive force is to be avoided during the assembly of individual structural components or during the erection of sub-assemblies. As far as possible, major distortions of individual structural components should be corrected before further assembly.

2.4.2 Girders, beams, stiffeners, frames, etc. that are interrupted by bulkheads, decks, etc. must be accurately aligned. In the case of critical components, control drillings are to be made where necessary. After completion the control drillings are to be closed by welding.

2.4.3 After completion of welding, straightening and aligning must be carried out in such a manner that the material properties will not be significantly influenced. In case of doubt, **BCS** may require procedure test or a working test to be carried out.

3. Corrosion protection

The requirements of Section 3, E. and F. apply.

Table 1.3 Documentation to be submitted for Classification

Serial No.	Description
	General Information
1	General arrangement plan
2	Deck plan
3	Technical specification
4	Lines plan
5	Material specification (for steel or aluminium hull)
6	List of submitted drawings
	Hull Structures and Ship Equipment
7	Midship section
8	Other typical sections
9	Bottom structure
10	Engine room structure (including engine foundations)
11	Shell expansion plan
12	Ice strengthening
13	Decks
14	Superstructures and deckhouses
15	Bulkheads
16	Tank arrangement plan
17	Rudder body
18	Rudder stock
19	Rudder bearings, pintles and couplings etc.
20	Large openings
21	Special foundations
22	Welded joints for steel or aluminium
23	Coating plan
24	NDT-plan (Non-Destructive-Testing)
25	Equipment number and anchoring equipment
26	Mooring equipment
	Supporting Calculations (Structure)
27	Design loads summarized in a load plan
28	Distribution of still water shear forces and bending moments
29	Longitudinal strength calculation
30	Geometry properties of significant hull girder cross sections
31	Local stress calculations, if applicable
32	Finite element analysis, if applicable
33	Fatigue stress calculations, if applicable
34	Shock calculations, if applicable
35	Residual strength , if applicable
	Safety Requirements for the Hull
36	Closing appliances
37	Information to calculation of freeboard, if applicable
38	Bulwarks and guard-rails
39	Arrangement and details of shell doors
40	Watertight integrity plan
41	General stability information
42	Intact stability calculations
43	Damage stability calculations
44	Damage control plan
45	Inclining test, report and evaluation
46	Structural fire protection
47	Documentation on storage rooms and transport lines for explosives (ammunition, missiles, etc.)
48	Rigging plan
49	Masts
50	Specification of standing rigging
51	Specification of further equipment

SECTION 2

SUBDIVISION AND STABILITY

		Page
A.	General	2-2
	1. Application	
	2. Classification	
	3. Documents to be submitted	
	4. Definitions	
	5. Anti-heeling devices	
B.	Intact Stability	2-2
	1. Buoyancy	
	2. Load cases for stability considerations	
	3. Assumptions for computation	
	4. Righting lever	
	5. Heeling levers	
	6. Criteria for intact stability	
	7. Intact stability of special ship types	
C.	Subdivision and Damage Stability	2-10
	1. Definition of subdivision status	
	2. Design principles	
	3. Extent of damage	
	4. Permeability of compartments	
	5. Righting lever	
	6. Heeling levers	
	7. Criteria for damage stability	
D.	Tests	2-14
	1. General	
	2. Inclining test	
E.	Guidelines for Computation	2-15
	1. Computation of the cross curves	
	2. Evaluation of an equivalent safety level	
F.	Stability Information	2-15
	1. Stability manual	
	2. Damage control plan	
	3. Stability computer	
G.	Marking of Maximum Draught	2-16
H.	Draught Readings.....	2-16

A. General**1. Application**

The requirements of this Section apply to monohull naval surface ships.

High Speed Craft and Hydrofoil Craft are covered by the **BCS** Rules, Part C, Chapter 7 - High Speed Craft.

For other types of ships special requirements will be agreed with **BCS** case by case.

For application details which are not specified in this Section, refer to Part A, Chapter 1, Section 26 or IMO Requirements or Guidelines.

2. Classification

2.1 Naval ships will be assigned Class only after it has been demonstrated that their intact stability is adequate for the service intended. The level of intact stability for naval ships shall generally meet the standard defined in the following, unless special operational restrictions reflected in the Class Notation allow a smaller level.

The Naval Authority may require compliance with other existing standards, regarding intact stability. **BCS** the right to accept such standards as

2.2 Naval ships with proven subdivision and damage stability will be assigned the relevant symbol. This symbol will be supplemented by a damage stability marking, kind of stability assessment and regulations applied, see C. and also Chapter 101 - Classification and Surveys (Naval Ship Technology), Section 2, B.3. and C.2.2

3. Documents to be submitted

The drawings and documents necessary for approval are defined in Section 1, D.

4. Definitions

For the purpose of this and other Sections the following definitions apply unless explicitly defined otherwise.

4.1 Down flooding point

Down flooding point means any opening through which flooding of the spaces which comprise the reserve buoyancy could take place while the ship is in the intact or damaged condition, and heels to an angle past the angle of equilibrium.

4.2 Permeability μ .

Permeability μ of a space means the percentage of the immersed volume of that space which in case of flooding can be occupied by water.

4.3 Watertight

Watertight, in relation to a structure, means capable of preventing the passage of water through the structure in any direction under the head of water likely to occur in the intact or damaged condition.

4.4 Weathertight

Weathertight means that water will not penetrate into the ship in any sea condition.

5. Anti-heeling devices

5.1 If tanks are used as anti-heeling devices, effects of maximum possible tank moments on intact stability are to be checked. A respective proof has to be carried out for several draughts and taking maximum allowable centres of gravity resulting from the stability limit curve as a basis.

5.2 If a ship is equipped with anti-heeling arrangements which may counteract heeling angles of more than 10°, the requirements defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8, Q. have to be observed.

5.3 All devices have to comply with Chapter 105 Electrical Installations, Section 7, G.

B. Intact Stability**1. Buoyancy**

1.1 All naval ships shall have a sufficient

reserve of buoyancy at the design waterline to meet the intact stability requirements of this Section. This buoyancy reserve shall be calculated by including only those compartments which are:

1.1.1 Watertight

1.1.2 Accepted as having scantlings and arrangements adequate to maintain their watertight integrity

1.1.3 Situated in locations below a boundary, which may be a watertight deck or equivalent structure of a non-watertight deck covered by a weathertight structure as defined in A.4.4.

1.2 Arrangements shall be provided for checking the watertight integrity of those compartments taken into account in 1.1.1.

1.3 Where entry of water into spaces above the boundary as defined in 1.1.3 would significantly influence the stability and buoyancy of the ship, such structure shall be:

- Of adequate strength to maintain the weather tight integrity and fitted with weathertight closing appliances; or
- Provided with adequate drainage arrangements; or
- An equivalent combination of both measures.

1.4 The means of closing openings in the boundaries of weathertight structures shall be such as to maintain weathertight integrity in all operational conditions.

2. Load cases for stability considerations

2.1 General

For naval ships the investigation of the basic load cases **0**, **1**, **1A**, **2**, **2A**, **5**, **5A** and **6** defined in the following written in bold and italics is mandatory, all other load cases defined herein are not mandatory, but can be regarded as a guideline for further investigations.

For ships with unusual mass distribution and considerably differing heeling moments other or additional load cases should be agreed with the Naval Authority.

A summary of the different load cases is given in Table 2.1.

For naval ships with important supply functions, the special load distribution of the supply goods or liquids requires a loading and unloading manual, considering stability as well as structural strength.

2.2 Load case 0: Light Ship Displacement

The condition **0 "Light Ship Displacement"** means a displacement according to the heeling test, including a design and construction margin, including fillings of liquids in all machinery systems, weapons and sensors, filling of sonar domes and fixed ballast, if applicable.

This load case considers in addition the specified crew and their personal belongings, but does not include any provisions, aircraft, etc., see Table 2.1.

2.3 Load case 0V: Warping Displacement

The condition 0V "Warping Displacement" is based on the **"Light Ship Displacement"**, but includes fillings of ballast water and fuels in tanks as far as they are necessary for stability and trim during warping or docking operations.

2.4 Load case 1: Limit Displacement

The condition **1 "Limit Displacement"** is an unfavourable loading condition, where stability must be sufficient for the maximum wind forces acting on the ship. It is based on load case **0**, but ballast water tanks are filled as far as necessary and different provisions are fully or partially on board as defined in Table 2.1. Supply goods and liquids are only aboard in an extent as it is relevant for the most unfavourable load case.

2.5 Load case 1A: Limit Displacement End of Life

The condition **1A "Limit Displacement End of Life"**

is identical to load case **1**, but includes life cycle margins for maintenance, later conversions and equipment improvements and additions.

2.6 Load case 1B: Limit Displacement with Icing

The condition 1B "Limit Displacement with Icing" is based on the load case **1**, but includes icing of the ship's superstructures, see 3.4.

2.7 Load case 1AB: Limit Displacement End of Life with Icing

The condition 1AB "Limit Displacement End of Life with Icing" is identical to load case **1A**, but includes icing of the ship's superstructure according to 3.4.

2.8 Load case 2: Combat Displacement

The condition **2 "Combat Displacement"** is equivalent to the design displacement. It is based on load case **0**, but includes loading of all provisions at 100 % and does not provide for waste water or ballast water aboard, see Table 2.1.

2.9 Load case 2A: Combat Displacement End of Life

The condition **2A "Combat Displacement End of Life"** is identical to load case **2**, but includes life cycle margins for maintenance, later conversions and equipment improvements and additions.

2.10 Load case 2B: Combat Displacement with Icing

The condition 2B "Combat Displacement with Icing" is based on load case **2**, but includes icing of the ship's superstructures according to 3.4.

2.11 Load case 2AB: Combat Displacement End of Life with Icing

The condition 2AB "Combat Displacement End of Life with Icing" is identical to load case **2A**, but includes icing of the ship's structure according to 3.4.

2.12 Load case 3: Medium Displacement

The condition 3 "Medium Displacement" is mostly relevant for boats and auxiliary units. It is based on load condition **0**, but includes life cycle margins for maintenance, later conversions and equipment improvements and additions as well as a partial content of provisions as defined in Table 2.1. Ballast water is only aboard as far as necessary for stability.

2.13 Load case 4: Special Limit Displacement

The condition 4 "Special Limit Displacement" is based on load case **1**, but includes additional loading which may become necessary for carrying out exceptional tasks, e.g.

- Transport of troops
- Transport of goods for humanitarian assistance

For such special loading conditions the requirements defined herein are still applicable.

It is within the responsibility of the Naval Authority to make allowance for extreme loading scenarios in case of severe situations (crisis /wartime). **BCS**

2.14 Load case 4A: Special Limit Displacement End of Life

The condition 4A "Special Limit Displacement End of Life" is identical to load case **4**, but includes life cycle margins for maintenance, later conversions, equipment improvements and additions.

2.15 Load case 4AB: Special Limit Displacement End of Life with Icing

The condition 4AB "Special Limit Displacement End of Life with Icing" is identical to load case **4A**, but includes icing of the ship's superstructure according to 3.4.

2.16 Load case 5A: Special Combat Displacement

The condition 5 **"Special Combat Displacement"** is based on load case 2, but includes fuels as far as necessary for stability and at least 10 % filling, see Table 2.1. The additional special loads have the same characteristics as for load case 4, but in percentage of loading as to be agreed with the Naval Authority.

2.17 Load case 5A: Special Combat Displacement End of Life

The condition 5A **"Special Combat Displacement End of Life"** is identical to load case 5, but including life cycle margins for maintenance, later conversions, equipment improvements and additions.

2.18 Load case 5AB: Special Combat Displacement End of Life with Icing

The condition 5AB "Special Limit Displacement End of Life with Icing" is identical to load case 5A, but includes icing of the ship's superstructure according to 3.4.

2.19 Load case 6: Maximum Displacement

For auxiliary naval vessels, this loading condition may be omitted.

The condition 6 **"Maximum Displacement"** is identical to load case 2A with an increase of displacement of 2%. This increase is to be applied from the centre of gravity of Load Case 2A.

2.20 Load case 6B: Maximum Displacement with Icing

The condition 6B **"Maximum Displacement with Icing"** is identical to load case 6, but includes icing of the ship's superstructure according to 3.4.

3. Assumptions for computation

3.1 Displacement

The displacement shall be computed in metric tons [t] (1 000 kg). The density of the seawater shall be assumed as 1,025 t/m³.

3.2 Load assumptions

The assumptions for loads such as

- Weight of crew including the personal effects
 - Provisions
 - Density of fuels, lubricants, waste water, etc.
 - Special heeling influences
- have to be agreed with the Naval Authority.

Note:

If no other information is available, the following densities of liquids may be used:

- freshwater	1,000	t/m ³
- bilge water	1,005	t/m ³
- waste water	1,050	t/m ³
- ship's fuel (diesel)	0,83	t/m ³
- aircraft fuel	0,81	t/m ³
- lubricants	0,90	t/m ³
- fire extinguishing foams	1,15	t/m ³

3.3 Displacement margins

The following margins for the determination of the final displacement and the centres of gravity have to be considered carefully within the ranges to be defined by the shipyard and the Naval Authority:

- Design margin for uncertainties in true weights during design phase
- Construction margin for tolerances of the construction material and because of detail design changes
- Maintenance margin for continued corrosion protection, (additional coatings), etc.
- Margin for later conversions and equipment improvements/additions, if applicable

3.4 Icing

For the load cases which include icing, icing has to be assumed up to a height of 20 m above waterline.

Note:

The additional weight may be estimated for:

- *free deck areas and front areas of superstructure and deckhouse:* 0,5 kN/m²
 - *projected front areas of weapons, sensors, boats, masts and rigging, etc.:* 1,0 kN/m²
 - *free standing top masts, stays and antennas with a diameter below 0,1 m:*
- 0,1 kN/m
- For the estimation of the lateral wind attack area icing can be neglected. For the evaluation of the centre of gravity sheer and camber of the deck beams shall be considered approximately.

Table 2.1 Summary of load cases (basic load cases are written in italics)

Load cases →	0	OV	1/1A/1B/1AB	2/2A/2B/2AB	3	4/4A/ 4AB	5/5A/ 5AB	6/6B
	Light Ship Displ.	Warping Displace- ment	Limit Displacement	Combat Displacement	Medium Displace- ment	Special Limit Displ.	Special Combat Displ.	Maximum Displ.
Loads ↓	All values are percentages of the specific max. possible load [%]							
Empty Ship with mach. systems filled	100	100	100	100	100	100	100	100
Crew with personal effects	100	100	100	100	100	100	100	100
Consumables / provisions	-	-	50/33	100	50	50/33	100	100
Fresh water	-	-	10/50 (1)	100	50	10/50 (1)	100	100
Waste water	-	-	50	-	50	50	-	-
Ship fuel	-	(2)	10	100	50	≥ 10	100	100
Aircraft fuel	-	-	10	100	-	≥10	100	100
Lubrications	-	-	50	100	100	50	100	100
Fire exting. foams	-	-	100	100	100	100	100	100
Ammunition	-	-	33	100	-	33	100	100
Aircraft (stowed)	-	-	100	100	-	100	100	100
Special loads	-	-	-	-	-	100	100	100
Supplies / transports	-	-		100	(3)	(3)	100	100
Ballast water	-	(2)	(2)	(3)	(2)	(2)	(2)	(2)
(1) 50 % of freshwater if 30 l/day/crew member can be produced (2) as far as necessary for stability (3) supply goods and liquids according to the most unfavorable load condition								

4. Righting lever

4.1 The levers of the righting moments have to be calculated for ship spaces which are closed watertight. Such spaces are the ship's hull up to the bulkhead deck and the superstructures and deckhouses, which can be closed watertight at sea. If the spaces above bulkhead deck do not exceed a length of 0,05 L, they shall not be included in this volume.

4.2 A righting lever h is defined as follows:

h = Righting moment [mt]/displacement [t] [m]

The righting levers have to be evaluated for the following conditions:

- h_{SW} for the ship in still water
- h_C for the ship in the wave crest condition
- h_T for the ship in the wave trough condition
- h_{WV} for the ship in the seaway, average value of wave crest and wave trough conditions

and for the basic load cases defined above. For these load cases the righting levers and other form parameters have to be determined for the ship at even keel condition. The computation of the cross-curves of stability shall be done under the assumption that the total watertight space including superstructures and deckhouses is kept constant. For further information, see E.

5. Heeling levers

5.1 The heeling lever is defined as follows:

k = heeling moment [mt] / displacement [t] [m]

The heeling levers are to be determined for heeling angles φ of 10°, 20°, 30°, 45°, 60° and 75°. The different heeling influences are summarized in the following. If these influences occur at the same time the actual lever values are to be added.

5.2 Free liquid surfaces

The contribution of free liquid surfaces to the heeling moment results in the following heeling lever k_F :

$$k_F = \frac{1}{\Delta} \cdot \sum (p_i \cdot b_{\varphi i}) \quad [\text{m}]$$

p_i = Mass of liquids in slack tank i with free liquid surfaces [t]

$b_{\varphi i}$ = Change of the centre of gravity in relation to the upright ship, measured parallel to the design water line [m]

5.3 Turning circle

The heeling lever k_D is to be determined as follows: With known radius of the turning circle:

$$k_D = v_D^2 \frac{KG - 0,5 \cdot T}{g \cdot R_D} \cdot \cos \varphi \quad [\text{m}]$$

With unknown radius of turning circle:

$$k_D = \frac{c_D \cdot v_{\max}^2 (KG - 0,5 \cdot T)}{g \cdot L} \cdot \cos \varphi \quad [\text{m}]$$

v_D = Average speed in the tactical turning circle (180°), but not less than 0,8 v_0 [m/s]

$v_{\max}$ = See Section 1, B.7.2

KG = Centre of gravity above baseline [m]

R_D = Radius of tactical turning circle (180°)

C_D = Coefficient for computation of turning circle

= 0,3, final value to be determined from sea trials

φ = Heeling angle [°]

g = Acceleration of gravity

= 9,81 [m/s²]

5.4 Wind

The heeling lever k_W caused by lateral wind pressure is

to be determined as follows:

$$k_w = \frac{A_w (A_{w\Theta H} - 0,5 \cdot T)}{\Delta \cdot g \cdot p_w \cdot (0,25 + 0,75 \cdot \cos \varphi)} [\text{m}]$$

A_w = Lateral area of the ship exposed to wind forces, including all superstructures, deckhouses, masts, weapons, sensors, etc. but without consideration of an icing layer, [m²]

$A_{w\Theta H}$ = Vertical distance of the centre of the area A_w above baseline [m]

p_w = Wind pressure [kN/m²]

$$= C_w \cdot v_w^2 \cdot \frac{\rho}{2}$$

= 0,30 for load cases 0 and 0V

C_w = Drag coefficient

= 0,60 for cylinders

= 1,00 for flat areas

= 1,70 for flat grid elements

= 1,30 for cylindrical grid elements

v_w = Wind speed [m/s]

ρ = Density of air [t/m³]

The direction of this heeling force shall be the most unfavourable direction in combination with the other heeling forces.

A proposal for the wind speeds to be used for computation of the heeling levers for the different load cases and unrestricted range of service is given in Table 2.3. The values used for this range and restricted service ranges will be decided finally after discussion with the Naval Authority.

Table 2.2 Wind pressure for different wind speeds based on $c_w = 1,20$

Wind speed		Wind pressure
[kn]	[m/s]	[kN/m ²]
90	46	1,50
80	41	1,25
70	36	1,00
60	31	0,75
50	26	0,50
40	21	0,30
30	15	0,20
20	10	0,10
Intermediate values can be found by linear interpolation.		

5.5 Replenishment at sea

Heeling levers caused by lateral forces due to replenishment at sea have to be considered if

$$\frac{\sum Z_i \cdot a_i}{\Delta \cdot g} > 0,05 \text{ m}$$

The heeling lever k_Q is to be determined as follows:

$$k_Q = \frac{\sum Z_i (a_i \cdot \cos \varphi - b_i \cdot \sin \varphi)}{\Delta \cdot g} [\text{m}]$$

Z_i = 3x nominal towing force at the transfer winch for the track rope [kN]

a_i = vertical distance of the track rope fixing point above $0,5 \cdot T$ [m]

b_i = horizontal distance between the centreline and the track rope fixing point [m]

φ = angle of heel [°]

The summation is to be carried out for all replenishment systems working at one ship's side at the same time.

5.6 Towing forces

If the naval surface ship can also be used for towing and warping duties the heeling lever k_T created by the pulling force on the towing line has to be considered.

5.7 Other heeling influences

In exceptional situations additional significant heeling influence with a lever k_P may occur, e.g. caused by crane operations or accumulation of persons at one ship side, etc. Such influence has to be considered in the overall balance. Attention has to be paid to the fact that not all heeling components may occur at the same time.

6. Criteria for intact stability

6.1 Proof of stability

The proof of sufficient stability for a naval ship fulfilling its operational tasks at the conditions defined by the Naval Authority shall be done by comparison of the righting levers with the heeling levers. Possible combinations are summarized in Table 2.4. Decisive are the size of the remaining righting lever and of the static angle of heel, see Fig. 2.1




Fig. 2.1 Lever arm curves

6.2 Required righting levers

The minimum righting lever is related to a certain angle of heel and will be measured at the relevant angle of reference. The reference angle of heel is to be defined as follows:

$$\varphi_{\text{ref}} = 2 \cdot \varphi_{\text{stat}} + 5 [^{\circ}]$$

The remaining righting lever h_{rem} is the difference

between the sum of the righting levers h and the heeling levers k , see Fig. 2.1. This relation has to be investigated for the load cases defined above as well as for any special load cases defined by the Naval Authority and the angles of heel defined in 6.3.

For all load cases the following values of the remaining righting levers h_{rem} have to be complied with:

- angle of heel $\varphi_{\text{stat}} \leq 15^{\circ}$,
remaining righting lever
 $h_{\text{rem}} \geq 0,1 \text{ m}$ at $\varphi_{\text{ref}} = 35^{\circ}$
- angle of heel $\varphi_{\text{stat}} > 15^{\circ}$,
 $h_{\text{rem}} \geq 0,01 \cdot (\varphi_{\text{stat}} - 5^{\circ}) [\text{m}]$ at φ_{ref}

For the load cases 1B, 1AB, 2B, 4AB, 5AB and 6B the maximum wind speed where the requirement of h_{rem} is complied with has to be evaluated. In general the evaluated wind speed shall not be less than 60 kn for unrestricted service and 40 kn for restricted service. The evaluated values have to be included in the stability documentation.

6.3 Maximum angles of heel

The static angle of heel φ_{stat} shall not exceed the values defined in Table 2.3.

Tablo 2.3 Static angle of heel for different wind speeds

Wind speed [kn]	40	70	90
Angle of heel $\varphi_{\text{stat}} [^{\circ}]$	15	20	25

The maximum permissible speed of entrance into the turning circle under consideration of wind speeds up to 40 kn has to be stated in the stability documentation.

For load cases with icing the static angle of heel shall not exceed 25° .

If these limit values cannot be achieved, necessary measures have to be discussed and agreed with **BCS** the Naval Authority.

6.4 Maximum draught

The maximum draught **T** is the draught permissible with regard to strength and stability requirements. It refers to the load case **2A "Combat Displacement End of Life"** plus a certain percentage of this displacement to be defined by the Naval Authority.

This maximum draught shall be clearly marked on both hull sides of the naval ship at **L/2**, see G.

7. Intact stability of special ship types

For special ship types the standard defined above may not be sufficiently applicable. In such cases the Naval Authority shall decide about the stability requirements to be applied. **BCS** may assist in the stability based on such requirements.

C. Subdivision and Damage Stability

1. Definition of subdivision status

Ships which meet the requirements of this Section will be assigned the symbol for complying with damage stability criteria, see Chapter 101 - Classification and Surveys (Naval Ship Technology), Section 2, C.3.

2. Design principles

To improve survivability of the naval ship in case of damage, the following design principles shall be applied:

2.1 Bulkhead decks

2.1.1 All penetrations through the bulkhead deck have to be designed to maintain the watertight integrity of the bulkhead deck.

2.1.2 Progressive flooding of intact watertight compartments over the bulkhead deck has to be prevented by dam up water in watertight areas on the bulkhead deck.

Watertight wing bulkheads in combination with sills are forming the boundaries of these watertight areas.

These areas have to be defined according to the final floating position of the ship and must fulfill the condition, that the lower edge of the watertight area must be located 0,5 m above the final floating position of the ship considering heel and trim, see Fig. 2.2. The heeling levers k_F and k_W (40 kn) have to be considered.

2.2 External watertightness

2.2.1 The external water tightness of the naval ship is limited up to the flooding line at the heeling angle $\phi = \pm 60^\circ$ considering the actual trim.

2.2.2 Openings in the hull, superstructure and deck houses as well as in decks forming the outer boundary of the buoyant body up to the flooding line as defined in 2.2.1 are to be provided with watertight closing appliances.

Watertight doors and openings for penetration of cables, piping, ventilation ducts, etc. located below the bulkhead deck are to be designed for a pressure of 70 kN/m². If they are located above the bulkhead deck the design pressure is 40 kN/ m². The design of the closing appliances has to be approved by **BCS**

2.2.3 The damage stability calculation is to be based only on the compartments of the hull, the superstructures and deckhouses which are enclosed watertight.

2.3 Watertight subdivision

2.3.1 Transverse bulkheads

2.3.1.1 The ship has to be divided up to the bulkhead deck by transverse bulkheads in a way that the requirements for sufficient damage stability are fulfilled. The watertight bulkheads must be able to withstand the loads from the water pressure in a case of damage.

2.3.1.2 A collision bulkhead shall be located at a distance of at least 5 % **L** from the forward perpendicular. No openings are permitted in the collision bulkhead. Deviations due to special operational requirements have to be approved by

Table 2.4 Summary of righting and heeling levers to be calculated

Load cases		Ship in still water		Ship in the seaway	
		Righting lever	Heeling lever	Righting lever	Heeling lever
0 0V	Light ship Warping	h_{sw}	$k_F + k_w(40) \text{ (1)}$	-	-
1, 1A, 1B, 1AB 2, 2A, 2B, 2AB 4, 4A, 4AB, 5, 5A, 5AB 6, 6B	Limit Combat Special limit Special combat Maximum	h_{sw}	$k_F + k_w(40) \text{ (1)} + k_D$	-	-
1, 1A, 1B, 1AB 2, 2A, 2B, 2AB 4, 4A, 4AB 5, 5A, 5AB 6, 6B	Limit Combat Special limit Special combat Maximum	-	-	$h_{ww}(2)$	$k_F + k_w(90) \text{ (1)}$ $k_F + k_w(70) \text{ (1)}$ $k_F + k_w(40) \text{ (1)}$
3	Medium	h_{sw}	$k_F + k_w(20) \text{ (1)} + k_D$ $k_F + k_w(20) \text{ (1)} + k_P$	-	-
All load cases except 0, 0V	Turning circle	h_{sw}	$k_F + k_w(40) \text{ (1)} + k_D$ $k_F + k_w(20) \text{ (3)} + k_D$	-	-
All load cases except 0, 0V	Towing forces	h_{sw}	$k_F + k_w(40) \text{ (1)} + k_T$	-	-
All load cases except 0, 0V	Replenishment at sea	h_{sw}	$k_F + k_w(40) \text{ (1)} + k_Q(4)$	-	-
(1) the value in brackets represents the proposed wind speed [kn] for naval ships with unrestricted range of service (for requirements for maximum static heeling see Table 2.3) (2) the more unfavourable value of "ship in wave condition" (mean value of h_T and h_C) has to be used. (3) only for boats with restricted service range (4) heeling during this operation shall not exceed 6°					




Fig. 2.2 Cross section at a watertight bulkhead

2.3.1.3 The number of openings in watertight bulkheads shall be reduced to the minimum compatible with the design and proper working of the ship. For the necessary openings hydraulic or electric closing systems are to be provided, which have to be approved by **BCS**.

2.3.1.4 Openings for doors and other purposes have to be located in the midship area, and in no case shall the outboard edge of such openings be situated at a distance from the shell plating which is less than 0,2 **B** measured at right angles to the centreline at the level of the maximum draught.

2.3.1.5 Bulkhead doors have to comply with Section 9,B.

2.3.2 Longitudinal bulkheads

2.3.2.1 To avoid extreme heeling angles due to asymmetrical flooding in case of damage the number and extent of longitudinal bulkheads has to be restricted to a minimum.

2.3.2.2 Cross-flooding arrangements

Where the damage stability calculation requires the installation of cross-flooding arrangements to minimize asymmetrical flooding, these arrangements shall be self-acting as far as possible. Non-automatic controls for cross flooding fittings are to be capable of being operated from the bridge or another central location. The position of each closing device has to be indicated on the bridge or the central operating location.

Particular attention has to be paid to cross-flooding arrangements upon the stability in intermediate stages of flooding.

The sectional area of the cross flooding pipes is to be determined in such a way that the time for complete equalization does not exceed 15 minutes:

$$A = \frac{Q}{c \cdot v \cdot t} \quad [\text{m}^2]$$

A = Cross section of pipes [m²]

Q = Volume of the space (tank) to be flooded [m³]

c = Friction coefficient

≈ 0,6

v = Flow velocity [m/s]

$$= \sqrt{2 \cdot g \cdot h}$$

h = Pressure head between the highest point of cross flooding pipe and the floating water-line [m]

t = Flooding time [s]

= ≤900s

When determining the bulkhead scantlings of tanks

connected by cross flooding arrangements, the increase in pressure head at the immersed side that may occur at maximum heeling in the damaged condition must be taken into account.

2.3.3 Progressive flooding between compartments through damaged pipes with diameters > 50 mm has to be prevented.

2.3.4 Ammunition storage and refrigerating rooms as well as missile shafts have to be closed watertight.

3. Extent of damage

3.1 Compartment length

The minimum distance between adjacent watertight bulkheads forming a compartment shall be 1,8 m. Otherwise the compartment shall be combined with the adjacent compartment for stability considerations.

3.2 Longitudinal extent of damage

3.2.1 Load cases 1 and 2

For the load cases **1** and **2** the longitudinal extent of damage ℓ is defined as follows:

- For ships with a length $L < 30$ m only one compartment shall be assumed as flooded
- For ships with a length $L \geq 30$ m the longitudinal extent of damage is

$$\ell = 0,18 \cdot L - 3,6 \text{ or } 18 \text{ m whichever is less}$$
- The longitudinal extent of damage is related to the moulded side of plane bulkheads. Between corrugated bulkheads or bulkheads with steps or recesses the minimum distance in between is decisive.

3.2.2 Load cases 4 and 5

For the load cases **4**, **4A**, **5** and **5A** the number of flooded compartments can be reduced by one, but the minimum will be one compartment flooded. Further

details have to be agreed between the Naval Authority and **BCS**.

3.3 Penetration depth

It is assumed that the depth of damage reaches the centreline of the ship. A central longitudinal bulkhead is to be considered always as undamaged. Longitudinal bulkheads are to be assumed undamaged only if this would lead to a more unfavourable stability situation.

For ships with double hulls the assumptions have to be agreed case by case with the Naval Authority and **BCS**.

3.4 Vertical extent of damage

The vertical extent of damage is to be assumed from keel upwards without any upper limit. Damages of lesser extent are to be assumed only if this would lead to a more unfavourable stability situation.

3.5 General aspects

If a longitudinal extent of damage less than defined above leads to a more unfavourable stability situation, the reduced length has to be used. If the damage requirements defined above endanger the main tasks of a naval ship, other damage assumptions may be agreed with the Naval Authority and **BCS**.

4. Permeability of compartments

4.1 For the purpose of stability calculations the permeability μ for flooding of the different compartments is defined in Table 2.5.

Deviations from the values defined in Table 2.5 have to be demonstrated to **BCS**. For holds partially filled with military cargo the permeability is to be modified in proportion to the height of flooding of the space.

4.2 For naval craft built from wood or composite material, the volume of the construction elements has to be calculated and the permeability values of Table 2.5 have to be reduced accordingly.

4.3 The surface permeability of tanks bunkers and cells have to be assumed 98 %. For other spaces the values for the surface permeability are equivalent to the volume permeability of Table 2.5.

5. Righting lever

The stability calculation for the damaged ship has to determine the remaining righting lever according to the method of "loss of buoyancy" for still water conditions.

6. Heeling levers

For the damaged ship the following heeling levers have to be considered.

6.1 Free liquid surfaces

The heeling lever k_F has to be calculated for the free surfaces in the undamaged part of the ship.

Table 2.5 Values of volume permeability

Definition of spaces	Permeability μ [%]
Combat information center, control stations, accommodation rooms, kitchens, pantries, workshops	95
Ammunition rooms, missile silos	80
Provision rooms, refrigerating holds Full/half full/empty	50/65/80
Spare part storages	80
Machinery and ventilation rooms	85
Tanks, bunkers, cells	98
Void spaces	98
Supply storages, cargo holds for military goods to be transported	To be determined case by case

6.2 Wind

The wind speed has to be assumed at 40 kn (for unrestricted range of service). For the calculation of the lateral area above waterline and its centre of gravity the average of fore and aft draught has to be used.

7. Criteria for damage stability

7.1 General

To maintain a minimum level of safety the naval ship shall withstand the defined damages. This has to be proven by investigation of all damage cases according to 5 and 6 in combination with the load cases **1A "Limit Displacement End of Life"** and **2A "Combat Displacement End of Life"**. In a first step the righting lever in still water h_{SW} has to be compared with the heeling lever for free surfaces k_F . Then the heeling lever k_W for a wind speed of 40 kn has to be added to the heeling lever k_F . For the load cases **4, 4A, 5, 5A** and **6** sufficient damage stability has to be demonstrated for the most unfavourable case of damage and a longitudinal extent of damage according to 3.2.

Damage stability will be considered sufficient if the conditions according to 7.2 to 7.3 are fulfilled.

7.2 Criteria in damage condition without wind

In the damage condition without wind the following criteria have to be met:

- If flooding is symmetrical the ship must float upright in the final floating position, that means that GM must not be negative
- In the final floating position the bulkhead deck must not immerse considering heel and trim as well as symmetrical or asymmetrical flooding
- For the intermediate stages of flooding a maximum heeling angle of $\varphi = 25^\circ$ is permitted; a remaining righting lever h_{rem} of at least 0,05 m has to be achieved in the range up to $\varphi = 40^\circ$

7.3 Criteria in damage condition with wind

In the damage condition with wind the following criteria have to be met:

- Openings connected to intact compartments must not immerse
- The angle of heel must not be greater than 25°

in the final floating condition; in this condition a remaining righting lever $h_{rem} \geq 0,05$ m must be ensured

- at least at the situation of immersing of non-watertight openings a remaining righting lever $h_{rem} \geq 0,05$ m must be ensured
- the remaining righting lever curve shall have a minimum range of 15° beyond the point of intersection of the h_{SW}/k_W (40 kn) curves up to the immersion of non-watertight openings

D. Tests

1. General

1.1 A practical test with the empty naval ship ready for operation (according to load case **0** in B.2.) has to be executed for newbuildings as well as for naval ships which have passed a major conversion.

1.2 If an identical series of naval ships is built at one shipyard, the tests have to be executed only with the first ship. If the identical ships are built at different shipyards, the tests have to be performed with the first ship at each shipyard.

1.3 The tests have to be executed in presence of a **BCS** Surveyor.

2. Inclining test

2.1 Purpose of test

The inclining test has to be executed to determine the centre of gravity of the empty ship ready for operation (load case **0**) and provides therefore a basis for the stability considerations described above.

2.2 Test conditions and procedure

For inclining test conditions and procedure, refer to Chapter 1, Hull, Section 26 and IMO Intact Stability Code, MSC 267 (85) as amended.

E. Guidelines for Computation

1. Computation of the cross curves

1.1 The hydrostatic data for the ship's form in untrimmed condition have to be evaluated using a well proven computer program. The reference values for the computation, like basis, L , etc. have to be defined. The output has to be presented in form of lists and graphs.

1.2 Ship in still water

For the calculation of the still water cross curves all spaces which can be closed watertight may be considered. Cross curves (KN) have to be calculated with free trim and sinkage at the angles of heel $\varphi = 10^\circ, 20^\circ, 30^\circ, 45^\circ, 60^\circ$ and 75° . At least the range of displacement from "*Empty Ship*" to "*Special Combat*" has to be included in the computation. General definitions, see Section 1, Fig.1.1, a sketch showing which superstructures and deckhouses are included, as well as the information "deck edge immersion" have to be added.

1.3 Ship in seaway

For the same watertight spaces of the ship the seaway cross curves of stability, considering the angles of heel and range of displacement as defined in 1.2, have to be evaluated.

The ship has to be assumed as stationary laying in a sinusoidal wave with a length λ equal to L and a height of

$$H = \frac{\lambda}{(10 + 0,05 \cdot \lambda)}$$

The wave crest/trough shall be located at the cross section with the maximum area.

For the computation of the cross curves the ship has to be assumed untrimmed. The cross curves have to be evaluated for:

- Wave crest situation (h_c)
- Wave trough situation (h_T)

- Mean righting lever curve determined from h_c and h_T

The length λ and height H of the wave as well as a sketch showing which superstructures and deckhouses are included, have to be documented.

2. Evaluation of an equivalent safety level

If a single criterion for stability cannot be met, it is possible to discuss the situation with **BCS** and Naval Authority concerning the use of methods an equivalent safety level.

F. Stability Information

1. Stability manual

For each naval ship a stability manual has to be provided. This book shall contain:

- Results of the intact stability and a summary of damage stability investigations
- Righting and heeling lever values for each load case in tabular form and graphs
- Comment to stability behaviour of the ship
- Measures to maintain sufficient stability for the intact as well as the damaged ship
- Basic requirements concerning freeboard

2. Damage control plan

2.1 The damage control plan shall be permanently exhibited or readily available on the navigating bridge and/or ship control centre, for the guidance of the officers in control of the naval ship. This plan shall show clearly:

- For each deck and compartment the boundaries of the watertight compartments, the openings therein with the means of closure and position of any controls thereof

- For doors, a description of degree of tightness, operating mode, normal position, operating circumstances (opened while at sea, not normally used while at sea, not used while at sea)
- Arrangements for the correction of any list due to flooding

2.2 General information shall be given by listing operational procedures in order to maintain the watertight integrity under any condition.

3. Stability computer

If a stability computer is installed aboard, a stability manual and a damage control plan have also to be provided.

G. Marking of Maximum Draught

The maximum draught shall be clearly marked amid ships on both sides corresponding to the maximum draught permissible with regard to strength and stability or the International Load Line Convention where compliance is requested.




Fig. 2.3 Example of marking for a naval ship

H. Draught Readings

Draught readings that can serve to determine the ship's displacement and trim shall be provided near bow and stern on both sides of the ship's hull.

SECTION 3

MATERIALS AND CORROSION PROTECTION

	Page
A. General	3-2
B. Hull Structural Steel	3-2
1. Normal strength hull structural steel	
2. Higher strength hull structural steels	
3. High strength hull structural steels	
4. Austenitic steels	
5. Material selection for the hull	
6. Structural members which are stressed in direction of their thickness	
C. Forged steel and cast steel.....	3-3
D. Aluminium Alloys	3-3
1. General	
2. Influence of welding on mechanical characteristics of aluminium alloys	
3. Riveted connections for aluminium alloy	
E. Reduction of the Corrosion Risk by Special Measures in Design and Construction	3-6
F. Corrosion Protection.....	3-7
1. General instructions	
2. Shop primers	
3. Hollow spaces	
4. Corrosion, protection of wetted inside areas	
5. Corrosion protection of the underwater hull	
6. Special requirements for stainless steels and stainless steel castings	
7. Special requirements for aluminium alloys	
8. Combination of materials	
9. Fitting-out and berthing periods	

A. General

1. All materials to be used for the structural members mentioned in these Rules are to be in accordance with the **BCS** Rules Part A, Chapter 2 Material and Chapter 3 Welding with **BCS** Rules Chapter 103 - Special Materials for Naval Ships. The properties of which deviate from these rule requirements, may only be used upon special approval.

In Table 3.1 the usually applied steels for hull, super-structures and deckhouses are summarized. The usually applied aluminium alloys are defined in Table 3.5.

2. The materials fibre reinforced plastics and wood will be considered only on special request.

3. The drawings submitted for approval shall contain the material specification for the structural members. These drawings are to be kept on board in case any repairs are to be carried out

4. Definitions

Throughout this Chapter the following definitions of material properties apply:

R_{eH} = upper yield stress [N/mm²]

$R_{p0,2}$ = 0,2% proof stress [N/mm²]

R_m = tensile strength [N/mm²]

E = modulus of elasticity [N/mm²]

B. Hull Structural Steel**1. Normal strength hull structural steel**

Normal strength hull structural steel is a hull structural steel with a minimum yield stress R_{eH} of 235 N/mm² and a tensile strength R_m of 400-520 N/mm².

Normal strength hull structural steel is grouped into four grades, which differ from each other in their toughness properties, see Table 3.1. For the application of the individual grades for the hull structural members, see 5. and Table 3.3

2. Higher strength hull structural steels

2.1 Higher strength hull structural steel is a hull structural steel, the yield and tensile properties of which exceed those of normal strength hull structural steel. According to the **BCS** Rules Part A, Chapter 2 Material, for three groups of higher strength hull structural steels the minimum yield stress R_{eH} has been fixed at 315, 355 and 390 N/mm² respectively.

Note:

Especially when higher strength hull structural steels are used, limitation of permissible stresses due to buckling and fatigue strength criteria may be required.

2.2 Higher strength hull structural steel is grouped into the following grades, which differ from each other in their toughness properties, see Table 3.1.

In Table 3.3 the grades of the higher strength hull structural steels are marked by the letter "H".

2.3 Where structural members are completely or partly made from higher strength hull structural steel, a suitable notation will be entered into the ship's certificate.

3. High strength hull structural steels

For elements of the hull structure, where especially high strength properties are required, high strength structural steel for welded construction may be used, as defined in the **BCS** Rules, Part A, Chapter 2- Materials Section 3- Steel Plates, Strips, Section and Bars, C.

In addition steels with the material numbers 1.6780 and 1.6782 are defined in **BCS** Rules, Chapter 103 Special Materials for Naval Ships, Section 2, A., also Table 3.1.

4. Austenitic steels

4.1 Where austenitic steels are applied having a ratio $R_{p0,2} / R_m \leq 0,5$, after special approval the 1 % proof stress $R_{p1,0}$ may be used for scantling purposes instead of the 0,2 % proof stress $R_{p0,2}$.

Further details on materials and requirements are given in the **BCS** Rules, Chapter 103 - Special

Materials for Naval Ships, Section 2, B. and Section 8.

5. Material selection for the hull

5.1 Material selection for longitudinal structural members

The materials in the various longitudinal hull structural members are not to be of lower grade than those corresponding to the material classes and grades specified in Table 3.2 and Table 3.3.

5.2 Material selection for local structural members

5.2.1 The material selection for local structural members, which are not part of the longitudinal hull structure, may in general be carried out according to Table 3.4.

5.2.2 For members not specifically mentioned, normally grade A/AH may be used. However, **BCS** require also higher grades depending on the level.

5.3 Material selection for structural members which are exposed to low temperatures

For ships intended to operate permanently in areas with low air temperatures (below -10°C), **BCS** Rules, Part A, Chapter 1, Section 3, A.2.3.4.2 apply.

For ships with ice strengthening, see **BCS** Rules, Part Chapter 1, Section 3, A.2.3.2. and Table 3.7

6. Structural members which are stressed in direction of their thickness

6.1 Rolled materials, which are significantly stressed in direction of their thickness, have to be examined for doublings and non-metallic inclusions by ultrasonic testing.

6.2 In case of high local stresses in the thickness

direction, e.g. due to shrinkage stresses in single bevel or double bevel T-joints with a large volume of weld metal, steels with guaranteed material properties in the thickness direction according to the **BCS** Rules – Part Chapter 2 – Materials, Section 3, H Steel and Properties are to be used in order to avoid tearing.

C. Forged steel and cast steel

Forged steel and cast steel for stem, stern frame, rudder post, etc. are to comply with the **BCS** Rules, A, Chapter 2, Material. The tensile strength of

Forged steel and cast steel are to be selected under consideration of B.5. In this respect beside strength properties also toughness requirements and weldability shall be observed.

Non-magnetic forged steel and non-magnetic cast steel are to comply with the **BCS** Rules, Chapter 103 - Materials for Naval Ships, Section 5, B.

D. Aluminium Alloys

1. General

1.1 All aluminium materials to be used for the structural members indicated in the **BCS** Rules, Part A

1.2 The strength properties for some typical aluminium alloys are given in Table 3.5. Other aluminium alloys may be considered provided that the specification (manufacture, chemical composition, temper, mechanical properties, welding, etc.) and the scope of application is submitted to **BCS** and approved.

Where in the formula of the following Sections R_{eH} is applied for steel, it has to be replaced by the lower value of $R_{p0.2}$ and $0,70 R_m$ for aluminium alloys.

Table 3.1 Strength properties of selected steel materials

Material	Material Number (1)	E [N/mm ²]	R _{eH} or R _{p0,2} [N/mm ²]	R _m [N/mm ²]
Normal strength hull structural steel				
BCS-A BCS BCS-D BCS-E	1.0440 1.0442 1.0474 1.0476	2,06 x10 ⁵	235	400 - 520
Higher strength hull structural steel				
BCS-A 32 BCS-D 32 BCS-E 32	1.0513 1.0514 1.0515	2,06 x10 ⁵	315	440
BCS-A 36 BCS-D 36 BCS-E 36	1.0583 1.0584 1.0589	2,06 x10 ⁵	355	490
BCS-A 40 BCS-B 40 BC-C401. BCS-E 40	1.0532 1.0534 0560	2,06 x10 ⁵	390	510
Liquid quenched and tempered structural steel				
BCS-M550 BCS-M700	1.6780 1.6782	2,00 x10 ⁵	550 685	650 760
Austenitic steel				
X2CrNiMnMoN Nb21-16-5-3 X2CrNiMnMoN Nb23-17-6-3	1.3964 1.3974	1,95 x10 ⁵	430 510	700 800
(1) Defined in Key of Steels, Verlag Stahlschlüssel Wegst GmbH, D-71672 Marbach/Neckar				

Table 3.2 Material selection for longitudinal structural members

Structural member category	Material class
Secondary: Deck plating exposed to weather, in general Side plating of shell	I
Primary: Bottom plating, including keel plate and bilge strake Strength deck plating Continuous longitudinal members above strength deck	II
Special: Sheer strake at strength deck Stringer plate at strength deck Bilge strake Insert plates at ends of superstructures and deck houses and at hatch corners	III
Residual strength: (1) Longitudinal members relevant for residual strength	III
(1) see Section 21	

Table 3.3 Material classes and steel grades

Thickness t [mm] (1)	≤ 15	> 15 ≤ 20	> 20 ≤ 25	> 25 ≤ 30	> 30 ≤ 40	> 40 ≤ 60	> 60 ≤ 100
Material class							
I	A/AH	A/AH	A/AH	A/AH	B/AH	D/DH	E/EH
II	A/AH	A/AH	B/AH	D/DH	D/DH	E/EH	E/EH
III	A/AH	B/AH	D/DH	D/DH	E/EH	E/EH	E/EH
(1) Actual thickness of the structural member							

Table 3.4 Material classes for local structural members

Structural member	Material class
Face plates and webs of girder systems Hatch covers	II (1)
Rudder body, rudder horn Stern frame Propeller brackets	II
(1) Class I sufficient, where rolled sections are used or the parts are machine cut from normalised plates with condition on delivery of either "normalized", "normalized rolled " or "thermo-mechanical rolled "	

1.3 Unless otherwise specified, the modulus of elasticity E of aluminium alloys of 70000 N/mm² and the Poisson's ratio ν of 0,33 is to be taken into account.

2. Influence of welding on mechanical characteristics of aluminium alloys

2.1 Welding heat input lowers locally the mechanical strength of aluminium alloys hardened by work hardening (series 5000 other than condition 0 or H111) or by heat treatment (series 6000).

2.2 Consequently, where necessary, a drop in mechanical characteristics of welded structures is to be considered in the heat-affected zone, with respect to the mechanical characteristics of the parent material.

2.3 The extension of the heat-affected zone depends on the type of welded joint, weld thickness etc. At least, an extent of not less than 25 mm on each side of the weld axis is to be taken into account.

2.4 Aluminium alloys of series 5000 in 0 condition (annealed) or in H111 condition (annealed flattened) are not subject to a drop in mechanical strength in the welded areas.

Aluminium alloys of series 5000 other than condition 0 or H111 are subjected to a drop in mechanical strength in the welded areas. The mechanical characteristics to consider in welded condition are, normally, those of condition 0 or H111, except otherwise indicated in Table 3.5. Higher mechanical characteristics may be taken into account, provided they are duly justified.

2.5 Aluminium alloys of series 6000 are subject to a drop in mechanical strength in the vicinity of the welded areas. The mechanical characteristics to be considered in welded condition are, normally, to be indicated by the supplier, if not indicated in Table 3.5.

2.6 For forgings and castings to be applied, requirements for chemical composition and mechanical properties are to be defined in each separate case by **BCS**.

2.7 In case of structures subjected to low service

temperatures (i.e. below –25° C) or intended for other particular applications, the alloys to be employed are to be agreed in each separate case by **BCS**, who will the acceptability requirements and conditions.

3. Riveted connections for aluminium alloy

3.1 Use of rivets for connecting structures is limited, in principle, only to members which do not contribute to the overall strength of the hull. Exceptions are to be supported by experimental evidence or good in-service performance.

3.2 The conditions for riveted connection acceptability are to be individually stated in each particular case, depending on the type of member to be connected and the rivet material.

3.3 Whenever riveted connections are to be employed, a detailed plan, illustrating the process, as well as the dimensions and location of rivets and holes, together with the mechanical and metallurgical properties of the rivets, is to be submitted for approval.

3.4 **BCS** may, at its discretion, require tension, compression and shear tests to be carried out on specimens of riveted connections constructed under the same conditions as during actual hull construction, to be witnessed by a **BCS** surveyor.

3.5 **BCS** reserves the right to accept the results of tests performed by recognized bodies or other Societies.

E. Reduction of the Corrosion Risk by Special Measures in Design and Construction

Naval ships, systems and components shall be designed with the aim of ensuring optimum corrosion protection through the application of suitable structural measures.

Amongst others, the following measures have proven their worth in practice:

- Points at which moisture tends to collect must be avoided as far as possible

The structural design shall enable good accessibility for activities of active and passive corrosion protection

- Accumulations of condensed water in steel structural elements shall be avoided by providing sufficient venting possibilities
- The surface shall be as flat as possible
- Stiffeners, internal parts and piping, etc. shall be arranged in areas less at risk from corrosion
- Possibilities of performing cleaning and pickling after welding to be provided, esp. with austenitic steels
- Avoiding corrosion by impingement of drops by using baffle plates
- Chain intermittent welds only permissible in zones which are heat-insulated and free of condensed water
- Burrs and sharp edges shall be rounded off in order to improve coating
- Hollow components which are not accessible shall be sealed off completely

The corrosion additions t_k defined in Section 4, B.3 are based on this assumption

F. Corrosion Protection

1. General instructions

1.1 Details of the documentation necessary for setting up the corrosion protection system are laid down herein (planning, execution, supervision).

1.2 Requirements with respect to the contractors executing the work and the quality control are subject to the conditions laid down in Section 1, E.

1.3 Supplementary to the statements herein, the **BCS** Rules, Part A, Chapter 1, Hull Section 22, contain further requirements, comments and recommendations for the selection of suitable corrosion protection systems, as well as their professional planning/execution and have to be observed too.

2. Shop primers

2.1 General

2.1.1 As a rule, shop primers are used to provide protection for the steel parts during storage, transport and work processes in the manufacturing company until such time as further surface preparation is carried out and the subsequent coatings for corrosion protection are applied.

2.1.2 Customarily, coatings with a thickness of 15 μm to 20 μm are applied. Under normal yard conditions, this should provide corrosion protection for a period of approx. 6 months.

2.1.3 The coating must be of good resistance to withstand the mechanical stresses incurred during the subsequent working of the steel material in the shipbuilding process.

2.1.4 Flame-cutting and welding speeds are not to be unduly impaired. It must be ensured that welding with all welding processes customary in the building of naval ships can be conducted without impermissibly impairing the quality of the weld seam, see **tBCS** Rules Part A, Chapter 3 - Welding, - Section 6 Overweldable Shop Primers.

2.1.5 Due to the possible strain to the system presented by cathodic protection, seawater and chemicals, only shop primers are to be used which are alkali-fast and not hydrolysable.

2.1.6 The suitability and compatibility of shop primer for use in the corrosion protection system is to be guaranteed by the manufacturer of the coating materials.

Table 3.5 Aluminium alloys for welded construction

Guaranteed mechanical chacteristics (1)							
Aluminium alloy				Unwelded condition		Welded condition	
Alloy (2)	Products	Temper (2)	Thickness [mm]	R _{p0,2} [N/mm ²] (4)	R _m [N/mm ²] (5)	R _{p0,2} ['] [N/mm ²] (4)	R _m ['] [N/mm ²] (5)
5083	rolled	O/H111/H112	t ≤ 50	125	275	125	275
		H116		215	305		
		H32/H321					
5083	extruded	O/H111	t ≤ 50	110	270	110	270
		H112		125			
5086	rolled	O/H111/H112	t ≤ 50	100	240	100	240
		H116		195	275		
		H32/H321		185			
5086	extruded	O/H111/H112	t ≤ 50	95	240	95	240
5383	rolled	O/H111	t ≤ 40	145	290	145	290
		H116/H321		220	305		
5383	extruded	O/H111	t ≤ 50	145	290	145	290
		H112		190	310		
5059	rolled	O/H11	t ≤ 50	160	330	155	300
		H116/H321	t ≤ 20	270	370		
				20 < t ≤ 40	260		
5059	extruded	H112	t ≤ 50	200	330	155	300
5454	rolled	O/H111	t ≤ 40	85	215	85	215
		H32		180	250		
5754	rolled	O/H111/H112	t ≤ 50	80	190	80	190
		H32	t ≤ 40	165	240		
6005A	extruded	T5/T6	t ≤ 50	215	260	115	165
6060 (3)	extruded	T5	t ≤ 5	120	160	65	95
	extruded		5 < t ≤ 25	100	140		
6061	extruded	T5/T6	t ≤ 50	240	260	115	165
6082	extruded	T5/T6	t ≤ 50	260	310	115	170
6106	extruded	T6	t ≤ 10	200	250	65	130

(1) The guaranteed mechanical characteristics in this Table correspond to general standard values. For more information, refer to the minimum values guaranteed by the product supplier. Higher values may be accepted on the basis of welding tests including recurrent workmanship test at the shipyard only.

(2) Other grades or tempers may be considered, subject to the Society’s agreement.

(3) 6060 alloy is not to be for structural members sustaining impact loads (e.g. bottom longitudinals). The use of alloy 6106 is recommended in that case.

(4) Rp0,2 and Rp0,2' are the minimum guaranteed proof strengths at 0,2 % in unwelded and welded condition respectively.

(5) Rm and Rm' are the minimum guaranteed tensile strengths in unwelded and welded condition respectively.

2.2 Approvals

Only those over weldable shop primers may be used for which **BCS** has issued a confirmation of acceptability based on a porosity test in accordance with the **BCS** Rules, Part A, Chapter 3 - Welding Section 6-Overweldable Shop Primers.

3. Hollow spaces

Hollow spaces, such as those in closed box girders, tube supports and the like, which can either be shown to be airtight or are accepted as such from normal shipbuilding experience, need not have their internal surfaces protected. During assembling, however, such hollow spaces must be kept clean and dry.

4. Corrosion, protection of wetted inside areas

4.1 General

All seawater ballast tanks and other inside areas of the ship frequently wetted with seawater and therefore endangered by corrosion, which have boundaries formed by the ship's shell (bottom, outside plating, deck) must be provided with a corrosion protection system.

Such corrosion protection system shall consist of a coating in combination with a cathodic protection system.

4.2 Coating system

4.2.1 Approvals

4.2.1.1 The applied coatings and coating systems must be approved by **BCS**. The approvals must be obtained by the manufacturers of the coating materials from **BCS** HeadOffice.

4.2.1.2 Approved coatings and coating systems are compiled in a list "Approved Coatings for Seawater Ballast Tanks". The current list is obtainable from **BCS** Head Office.

4.2.1.3 Approval does not constitute confirmation of the suitability and compatibility of the coatings in the corrosion protection system. They are to be ensured by either the shipyard or the manufacturer of the coating materials.

4.2.2 Surface preparation and coating

4.2.2.1 The surface must be prepared according to the instructions of the manufacturer of the coating material and in accordance with the **BCS** Rules – Part Chapter 1, Hull, Section 22 E.2.

4.2.2.2 Surface preparation is subject to specification in the product data sheet and must correspond to a valid surface quality grade, e.g. ISO 8501 or ISO 12944-4.

4.2.2.3 Slag and loose weld spatters must be removed before the coating is applied.

4.2.2.4 Welded or otherwise attached accessory material (tack plates, lugs etc.) must be completely - integrated into the corrosion protection, or otherwise removed.

4.2.2.5 The coatings must be in accordance with the manufacturer's specifications, resistant against seawater, coastal water, harbor water and the substances they may contain.

4.2.2.6 In addition, the coatings must be resistant against the cathodic protection, i.e. the coatings must not exhibit any impairment of their purpose up to a potential of -1200 mV against the copper/copper-sulphate electrode. Proof of resistance against cathodic corrosion protection can be provided in accordance with recognized standards, e.g. ISO 15711, or similar.

4.2.2.7 The process of application is to be carried out according to the coating manufacturer's instructions and in accordance with the **BCS** Rules - Part A 1 Hull Section 22 E.3.

4.2.2.8 The minimum coating thickness shall be 250 µm.

4.3 Cathodic protection

The selection of anodes, protection current requirements, mass calculation and arrangement of anodes shall be accordance with the **BCS** Rules, Part Chapter 1, Hull, Section 22, J.2.

4.4 Documentation

4.4.1 The work processes involved in setting up a coating system as well as the coating materials to be used must be laid down in a coating plan.

4.4.2 The coating plan for ballast water tanks and other inside areas frequently wetted must be submitted to BCSr approval.

4.4.3 The coating protocol is to be compiled in such a way that all work steps executed, including surface preparation and coating materials used, are documented.

4.4.4 This documentation is to be compiled by the coating manufacturer and/or the contractor executing the work and/or the shipyard. An inspection plan must be agreed to between the parties involved. The papers pertaining to the documentation must be signed by these parties. On completion of the coating system, the signed papers constituting the documentation are to be handed to the **BCS** Surveyor for checking acceptance. The documentation is to following data:

- Location and date
- Naval ship and the spaces treated
- Manufacturer's specifications for the coating system (number of coatings, total coating thickness, processing conditions)
- Product data sheet for the coating and approval number

- Contractors and persons carrying out the work
- Surface preparation (procedure, working materials, and ambient conditions)
- Condition of surface prior to coating (cleanness, roughness, existing primer, surface quality grade achieved)
- Application (procedure, number of coatings)
- Application conditions (time, surface/ambient temperature, humidity, dew point, ventilation)
- The date the tanks were first ballasted is to be recorded
- Report on coating thickness measurement and visual inspections
- Signatures of involved parties (shipyard, coating manufacturer, work contractor)

4.4.5 Coating protocols already in existence and used by coating manufacturers, work contractors, shipyards and Naval Authorities will be accepted by **BCS** provided they contain the above data and are by all parties involved. Any missing data is furnished.

4.4.6 The documentation concerning the design and computation of the cathodic protection must be submitted for perusal. An anode plan needs not to be submitted.

5. Corrosion protection of the underwater hull

5.1 General

5.1.1 Naval ships shall provide a suitable corrosion protection system for the underwater hull, consisting of coating and cathodic protection. This

applies especially for ships with Class Notation **IWS** (In-Water Survey, see Chapter 101 - Classification and Surveys). The requirements according to the **BCS**

- Part A, Chapter 1 Hull, Section 22 E.2 have observed.

5.1.2 Coatings based on epoxy, polyurethane and polyvinyl chloride are considered suitable.

5.1.3 The coating manufacturer's instructions with regard to surface preparation as well as application conditions and processing must be observed.

5.1.4 The coating, system without antifouling, shall have a minimum dry film thickness of 250 µm, shall be compatible to cathodic protection in accordance with recognized standards and shall be suitable for being cleaned underwater by mechanical means.

5.1.5 The cathodic protection can be provided by means of sacrificial anodes, or by impressed current systems.

5.1.6 In the case of impressed current systems, overprotection due to inadequately low potential is to be avoided. A screen (dielectric shield) is to be provided in the immediate vicinity of the impressed current anodes.

5.1.7 Cathodic protection by means of sacrificial anodes is to be designed at least for one dry-docking period and for protection of the complete underwater hull. Upon special request of the Naval Authority a part protection (stern protection) can be accepted, but only for ships not intended for **IWS** Class Notation.

The use of aluminium anodes is only acceptable if the ship is intended to operate for at least 4500 hours per year.

5.2 Documentation

5.2.1 The coating plan and the design data including the necessary calculation for the cathodic protection are to be submitted for approval.

5.2.2 In the case of impressed current systems, the following details must also be submitted:

- Location and constructional integration (e.g. by a cofferdam) of the anodes in the ship's skin
- Descriptions of how all appendages, e.g. rudder, propeller and shafts, are incorporated into the cathodic protection
- Electrical supply and electrical distribution system

5.2.3 The work processes involved in setting up the coating system as well as the coating materials to be used must be laid down in the coating plan.

5.2.4 A coating protocol is to be compiled in such a way that details of all the work processes executed, including surface preparation as well as the coating materials used, are recorded.

5.2.5 This documentation is to be compiled by the coating manufacturer and/or the contractor executing the work and/or the shipyard. An inspection plan must be agreed upon between the parties involved. The papers pertaining to the documentation must be signed by these parties. On completion of the coating system, the signed papers constituting the documentation are to be handed to the **BCS** Surveyor for acceptance.

5.2.6 In the case of impressed current systems, the functionality of the cathodic corrosion protection is to be tested during sea trials. The values obtained for the protection current and voltage must be recorded.

6. Special requirements for stainless steels and stainless steel castings

6.1 Protective measures

Stainless steels and stainless steel castings exhibit a passive surface state in seawater, as is the case in several other media. Accordingly, coating of

structures of these types of steel is only recommended under special conditions. Depending on the composition and grain structure, stainless steels are sensitive to local corrosion, such as pitting and crevice corrosion.

6.2 Cathodic protection

Cathodic corrosion protection may prevent or reduce pitting and crevice corrosion; in the case of crevice corrosion the effect is limited, depending on the crevice geometry.

Note:

Uncoated stainless steels need not to be protected cathodically if they are suitable for withstanding the corrosion stress. Coated stainless steels must be cathodically protected in the submerged zone.

6.3 Design and workmanship

The following fundamental principles shall be observed:

- Crevices shall be avoided as far as possible, if this is not feasible, the crevice shall be made as wide as possible
- Flanges shall be made of materials with a greater corrosion resistance
- Heat transmission paths should be avoided
- Welds to be executed in technically competent manner
- Weld joints to be post-treated in a technically competent manner
- Coarse mechanical grinding is not permitted
- The surface should be smooth as possible
- Only suitable processing tools are to be used e.g. "stainless steel brush"

6.4 Further information

Further information including material selection, cathodic protection, surface preparation, etc. is contained in the **BCS** Rules - Part A Chapter 1 Hull Section 22.

7. Special requirements for aluminium alloys

7.1 For hull structures or components of zinc-free aluminium materials which are continuously submerged in seawater, cathodic protection with a protective potential of less than -0,55 V by sacrificial anodes is required. For aluminium materials which are only exposed to spray water, corrosion protection is not necessary. In many cases, a coating is selected for the reason of aesthetics, signature reduction or as a basis for an antifouling system. The requirements for corrosion protection shall be observed with such applications.

7.2 Further information including material selection, cathodic protection, surface preparation, etc. is contained in the **BCS** Rules - Part A Chapter 1 Hull Section 22.

8. Combination of materials

8.1 Preventive measures are to be taken to avoid contact corrosion associated with the combination of dissimilar metals with different potentials in an electrolyte solution, such as seawater.

8.2 In addition to selecting appropriate materials, steps such as suitable insulation, an effective coating and the application of cathodic protection can be taken in order to prevent contact corrosion.

Any direct contact between steel and aluminium alloy is to be avoided in wetted or immersed areas.

8.3 Any heterogeneous joining system is subject to **BCS's** agreement. The use of transition joints made aluminium/steelcladded plates or profiles is subject **BCS's** agreement.

Transition joints are to be type-approved.

Qualifications tests for welding procedures are to be carried out for each joint configuration.

A welding booklet giving preparations and various welding parameters for each type of assembly is to be submitted for review.

9. Fitting-out and berthing periods

9.1 For protection against corrosion arising from stray currents, such as those occurring due to inappropriate direct-current electrical supply to the naval ship for welding or mains lighting, as well as those arising

from direct-current supplies to other facilities e.g. shore cranes and neighboring ships, the provision of even additional cathodic protection by means of sacrificial anodes is not suitable.

9.2 Suitable measures are to be taken to prevent the formation of stray currents and suitable electric drainage is to be provided.

9.3 Particularly in the event of lengthy fitting-out periods, welding rectifiers are to be so arranged that stray currents can be eliminated. This is considered to be especially important for naval ships.

SECTION 4

DESIGN PRINCIPLES

	Page
A. General	4-3
1. Acceptance criteria	
2. Definitions	
3. Sign of stresses	
4. Rounding-off tolerances	
5. Definitions of primary and secondary stiffening members	
6. Unsupported span	
B. Design of Plates.....	4-6
1. General	
2. Definitions	
3. Corrosion additions and rounding-off tolerances	
4. Plate thickness	
5. Buckling strength	
6. Determination of elastic bending stresses	
C. Scantlings of Secondary Stiffening Mem-bers, Primary Supporting Members and Pillars	4-8
1. General	
2. Definitions	
3. Nominal Loads	
4. Ultimate strength criteria	
5. Scantlings	
6. Deflection criterion	
D. End attachments.....	4-14
1. Definitions	
2. Sniped ends of stiffeners	
3. Corrugated bulkhead elements	
4. Brackets	
5. Additional stresses in asymmetric sections	
E. Effective Width of Plating	4-16
1. Girders, frames and stiffeners	
2. Cantilevers	
F. Proof of Buckling Strength	4-18
1. General	
2. Single plate buckling	
3. Proof of partial and total fields	
G. Structural Details.....	4-24
1. Longitudinal members	
2. Primary supporting members	
3. Openings in highly loaded structures	
4. Structures made of aluminium alloys	

H.	Evaluation of Notch Stress	4-30
1.	Permissible notch stress	
2.	Notch factors to evaluate actual notch stress	
3.	Openings in decks contributing to longitudinal strength	

A. General

This Section contains design principles and acceptance criteria for the main structural elements of the hull.

1. Acceptance criteria

The strength assessment according to this Rule is based on the application of ultimate strength formulations using the theory of plasticity and the yield line theory. The material behaviour for these calculations was assumed to be elastic perfectly plastic (without any hardening effects).

The requirements are formulated in a partial safety factor format. The general acceptance criterion can be expressed as follows:

$$f(R_{eH}) / \gamma_m \geq \gamma_{fstat} \cdot f(F_{stst}) + \psi_i \cdot \gamma_{fdyn} \cdot f(F_{dyn})$$

Where:

$f(R_{eH})$ = Function of the structural resistance based on the minimum yield stress and 0,2% proof stress respectively of the material up to a strain of 10 %

$f(F_{stst})$ = Function of the static loads acting on the structure

$f(F_{dyn})$ = Function of the dynamic loads acting on the structure

$\gamma_m, \gamma_{fstat}, \gamma_{fdyn}, \psi_i$ see 2.

The design loads described in Section 5 and 6 may be used in general. For special hull shapes individual load analyses are required. The wave induced design loads generally correspond to a probability level $Q_0 = 10^{-8}$ and a design life of 25 years.

Other concepts (e.g. for detail structures) are explained in their context.

2. Definitions

If not otherwise specified in the following sections the Partial Safety Factors (PSF) given in Table 4.1 have to

be applied.

LCA: Permanent (static) and cyclic loads acting on the undamaged structure in ordinary operation condition (dimensioning of local structures acc. to the requirements of this Section)

LCB: Static and cyclic loads acting on the undamaged structure in extreme operation or damaged condition, i.e. hull girder strength. Damaged condition means that the strength of the structure is not (significantly) reduced, i.e. watertight bulkheads in case of compartments flooded.

LCC: Permanent and cyclic loads in ordinary operation condition. This load case is used for buckling, notch stress, fatigue and deflection analyses and pillars.

Table 4.1 Partial safety factors (PSF)

Load case	LCA	LCB	LCC
Global (hull girder) loads			
Static load γ_{fstat}	1,0	1,0	1,0
Dynamic load γ_{fdyn}	1,0	1,0	1,0
Local (pressure, cargo, etc.) loads			
Static load γ_{fstat}	1,25	1,05	1,0
Dynamic load γ_{fdyn}	1,25	1,05	1,0
For structural resistance γ_m	1,1	1,1	1,0

γ_m = Partial safety factor for structural resistance, see Table 4.1

γ_{fstat} = Partial safety factor for static load components, see Table 4.1

γ_{fdyn} = Partial safety factor for dynamic load components, see Table 4.1

f_{pL} = $R_m / (1,5 \cdot R_{eH})$ for isotropic plate material
 $\leq 1,0$ for isotropic plate material

f_Q = Probability factor which may be determined for a straight-line spectrum of seaway induced stress ranges and for a design life n

≥ 25 years. If applicable, the probability level Q is given in the corresponding formulas.

$$= \log (25.Q/n) / \log Q_0$$

$$= 1,0 \text{ in general}$$

n = life time [years]

Q_0 = 10^{-8} probability level, reference value

Q = 10^{-8} in general

ψ = Combination factor for simultaneousness of statistically independent dynamic loads

$$= 1,0 \text{ in general or for major load of load combination}$$

3. Sign of stresses

In general, except for buckling calculations according to F.1.2, for design purposes normal stresses, i.e. bending and/or in-plane stresses are to be taken positive for tension and negative for compression.

4. Rounding-off tolerances

4.1 Where in determining plate thicknesses in accordance with the provisions of the following Sections the figures differ from full or half mm, they may be rounded off to full or half millimetres up to 0,2 or 0,7; above 0,2 and 0,7 mm they are to be rounded up.

If plate thicknesses are not rounded up the thicknesses required are to be shown in the drawings.

4.2 The section of profiles usual in trade and including the effective width according to E. may be 3 % less than the required values according to these Rules.

5. Definitions of primary and secondary stiffening members

Primary and secondary stiffening members are defined as shown in Figure 4.1 and 4.2.

The actual sectional properties are to be related to an axis parallel to the attached plating. The effective width of plating is to be calculated according to E.




Figure 4.1 Definitions of primary and secondary stiffening members of the hull structure (longitudinal framing system)




Figure 4.2 Definitions of primary and secondary stiffening members of the hull structure (transverse framing system)

6. Unsupported span

to be taken into account when determining the span of girder.

6.1 Secondary stiffening members

The unsupported span ℓ is the true length of the stiffeners between two supporting girders or else their length including end attachments (brackets).

The frame spacings and spans are normally assumed to be measured in a vertical plane parallel to the centerline of the ship. However, if the ship's side deviates more than 10° from this plane, the frame distances and spans shall be measured along the side of the ship.

In case of curved frames the true length may be multiplied by the factor $\sqrt{c_r}$ which is given in Table 4.2, see also Figure 4.3.

Table 4.2 Curvature factor c_r for curved transverse frames

s/ℓ	c_r
$< 0,125$	$1,0 - 2 \cdot \frac{s}{\ell}$
$\geq 0,125$	0,75

6.2 Corrugated bulkhead elements

The unsupported span ℓ of corrugated bulkhead elements is their length between bottom or deck and their length between vertical or horizontal girders. Where corrugated bulkhead elements are connected to box type elements of comparatively low rigidity, their depth is to be included into the span ℓ unless otherwise proved by calculations.

6.3 Primary supporting members

The unsupported span ℓ of transverses and girders is to be determined according to Figure 4.4, depending on the type of end attachment.

In special cases, the rigidity of the adjoining girders is




Figure 4.3 Curved transverse frame




Figure 4.4 2D- transverse members

B. Design of Plates**1. General**

The general scantling requirements for the hull structural plating subject to lateral loads are specified in the following.

The thickness of the plating is not to be less than:

$$t = t' + t_k$$

2. Definitions

t' = Required net thickness

t_k = Corrosion addition according to 3.

C_a = Factor considering aspect ratio of plate panel

$$= \frac{\sqrt{3 + \alpha^2} - \alpha}{\sqrt{3}}$$

α = Aspect ratio of single plate field

$$= a/b \leq 1,0$$

β = $1/\alpha$

a = Breadth of smaller side of plate panel [m]

b = Breadth of larger side of plate panel [m]

C_r = 1 for flat plates
 $= 1 - \frac{a}{2 \cdot r}$ for curved plates

r = radius of curvature [m]

$r_{min} \geq 2 \cdot a$

σ_L = Hull girder bending stress [N/mm²], see Section 6, D.4.

τ_L = Shear stress due to hull girder bending [N/mm²], see Section 6, D.4.

2.1 Load centre of lateral pressure for vertical plating

As load centre for plates is defined:

- Vertical stiffening system:

0,5 x stiffener spacing above the lower support of plate field, or edge of plate when the thickness changes within the plate field

- Horizontal stiffening system:

midpoint of plate field

3. Corrosion additions and rounding-off tolerances**3.1 General**

The following corrosion additions apply provided an effective corrosion protection system is used and continuously maintained.

Different additions required by the Naval Authority may be accepted by **BCS**. But in no case the additions shall less than the fabrication tolerances, see **BCS** Materials.

3.2 Steel

Based on the calculated values the scantling determination requires the corrosion addition t_k to the theoretical plate thickness:

- $t_k = 0,5$ mm in general

- $= 0,7$ mm for lubrication oil, gas oil or equivalent tanks

- $= 1,0$ mm for water ballast, sewage tanks, sea chests

- $= 2,0$ mm for chain locker

- for special applications t_k shall be agreed with **BCS**

For all elements of the ship's structure which are forming a boundary of tanks, the t_K values for tanks have to be considered.

3.3 Aluminium alloys

If the measures for corrosion protection as described in Section 3, E. and F.7. are fully applied, the corrosion addition t_K can be assumed as 0,2 mm for the aluminium alloys defined in Section 3, D.

If the under-thickness tolerance for extrusions is more than 7 %, the exceeding difference has to be considered for the calculations.

4. Plate thickness

4.1 Minimum thickness of plating

At no point the thickness of welded steel structures shall be less than the minimum thickness t_{min} defined in Table 4.3. Minor thicknesses of extruded aluminium are subject of separate approval.

4.2 Thickness for lateral pressures

The net thickness of the plating is not to be less than:

$$t' = 15,8 \cdot a \sqrt{\frac{p \cdot \gamma_m}{f_{pL} \cdot \sigma_{perm}}} \cdot c_a \cdot c_r \quad [\text{mm}]$$

p = Respective total lateral design pressure [kN/m²]

σ_{perm} = Permissible stress [N/mm²]

$$= 1,125 \cdot R_{eH} \cdot \left[\sqrt{1,0 - 3 \left(\frac{t_L}{R_{eH}} \right)^2} - 0,786 \left(\frac{\sigma_L}{R_{eH}} \right)^2 - 0,062 \frac{\sigma_L}{R_{eH}} \right]$$

For longitudinally stiffened plates (larger side of plate parallel to ships longitudinal direction, parallel to direction of σ_L)

$$= 1,125 \cdot R_{eH} \cdot \left[\sqrt{1,0 - 3 \left(\frac{t_L}{R_{eH}} \right)^2} - 0,89 \frac{\sigma_L}{R_{eH}} \right]$$

For transversely stiffened plates (larger side of plate transverse to ships longitudinal direction, transverse to the direction of σ_L).

σ_L and τ_L , see Section 6,D.4.

Table 4.3 Minimum thickness of plating

Elements of the hull structure		Minimum thickness $t_{\min}$ [mm]
Designation	Reference position	
Flat plate keel	Section 7	$14 \cdot \sqrt{\frac{L}{R_{eH}}}$
Shell plating: $z \leq T + c_0/2$ (1) $z > T + c_0/2$		$10 \cdot \sqrt{\frac{L}{R_{eH}}}$
		$7 \cdot \sqrt{\frac{L}{R_{eH}}}$
Chain locker	Section 18,E	5,0
All strength relevant structural plating	Various Sections	3,0
(1) For c_0 see section 5, A.3		

4.3 Thickness for wheel or single point loads

The net thickness of deck plating for single point or wheel loads is to be determined by the following formula:

$$t' = c \cdot \sqrt{\frac{P_E \cdot \gamma_m}{f_{pL} \cdot R_{eH}}}$$

P_E = Total wheel or single point load in [kN]

c = Load distribution factor as defined below

4.3.1 The load distribution factor c for a wheel or group of wheels is to be determined according to the following formula:

for the aspect ratio $\beta = 1$:

for the range $0 < f/F < 0,3$:

$$c = 26 - \sqrt{\frac{f}{F} \left(656 - 849 \frac{f}{F} \right)}$$

for the range $0,3 \leq f/F \leq 1,0$:

$$c = 16,7 - 5,6 \cdot f/F$$

for the aspect ratio $\beta \geq 2,5$:

for the range $0 < f/F < 0,3$:

$$c = 27,8 - \sqrt{\frac{f}{F} \cdot \left(1003 - 1389 \frac{f}{F} \right)}$$

for the range $0,3 \leq f/F \leq 1,0$:

$$c = 16,7 - 7,2 \cdot f/F$$

for intermediate values of β the factor c is to be obtained by direct interpolation.

f = Print area of wheel or group of wheels in m^2 .
If it is not known the definition of Section 5, E.2.2 and G.3.2.1 can be used.

F = Area of plate panel βa^2 in m^2 , but need not be taken greater than $2,5 a^2$

4.3.2 For forces induced by a tug or fender into the shell plating following load distribution factor c may be taken:

$c = 10$ in general

5. Buckling strength

The thicknesses obtained from 4. are to be verified for sufficient buckling strength according to F. For this purpose the design stresses according to Section 6,D.4 from longitudinal strength and stresses due to local loads according to C., are to be considered in load case C.

6. Determination of elastic bending stresses

Plate bending stresses due to lateral cyclic loads are to be considered in the fatigue analyses (Load Case C) in combination with the membrane stresses.

In case of uniformly loaded plates the maximum plate bending stresses at corresponding edges are to be calculated as follows:

$$\sigma_b = C_i \cdot p \cdot (a/t_a)^2 \quad [N/mm^2]$$

t_a = Plate thickness as built [mm]

C_1 = Stress factor at smaller edge

$$= \frac{343}{1 + \left(\frac{1,63 - \beta}{\beta^2 + 0,9} \right)^2} \quad \text{for } \beta < 1,63$$

$$= 343 \quad \text{for } \beta \geq 1,63$$

C_2 = stress factor at larger edge

$$= \frac{500}{1 + \left(\frac{2,493 - \beta}{\beta^2 + 0,9} \right)^2} \quad \text{for } \beta < 2,493$$

$$= 500 \quad \text{for } \beta \geq 2,493$$

In transverse direction of each edge the bending stress $\sigma_{bT} = \nu \sigma_b$ is correspondingly to be taken.

C. Scantlings of Secondary Stiffening Members, Primary Supporting Members and Pillars

1. General

The local scantlings of structural elements in ship's longitudinal direction are to be determined considering both, local design loads according to Section 5 and global design loads according to Section 6.

2. Definitions

$P_{A,B}$ = Corresponding total lateral design pressure [kN/m²] at point A or point B, respectively

$$= \gamma_{fstat} P_{A,Bstat} + \gamma_{fdyn} P_{A,Bdyn}$$

N = Sum of local and global forces [kN] in longitudinal (normal) direction of the structural element according to 4.2.1

F_s = Nominal shear force [kN] according to 3.

M_b = Nominal bending moment [kNm] according to 3.

ℓ = Unsupported span [m], according to Table 4.5 and Figure 4.4

a = Spacing [m] of the secondary stiffeners

e = Load width [m] for primary members
 = Spacing of primary members (in general)
 = Unsupported length of secondary stiffeners

m_a = Factor considering aspect ratio

$$= \frac{a}{6 \cdot \ell} \cdot \left[4 - \left(\frac{a}{\ell} \right)^2 \right]$$

a need not be greater than ℓ

$$m_n = \left[\frac{1}{\frac{a}{\ell} + 1} \right]$$

n_a = Number of supported secondary stiffeners within the length ℓ

j = Number of constrained (fixed) end conditions

= 2,0 for both ends fixed

= 1,0 for one end simply supported and one end fixed

= 0,0 for both end simply supported

ℓ_{ki} = Length of end connection [m], see Table 4.5

α_i = Angle of end connection [°], see Table 4.5

n_k = Factor considering end connection

$$= \left[1 - \frac{\sum \ell_{ki} \cdot \sin^2 \alpha_i}{\ell} \right]^2$$

W_{el} = Elastic section modulus [cm³] including effective width of plating according to E.

W_{pl} = Plastic section modulus [cm³] including effective width of plating according to E.

f_p = Shape factor

≤ R_m / R_{eH} but not greater than:

= 1,65 for flat bars with plating
 = 1,40 for bulb profiles with plating
 = 1,25 for rolled angle bars with plating
 = 1,15 for T-profiles with plating
 = 1,05 for corrugated bulkhead elements
 = 1,00 for sandwich panels
 = 1,70 for rods
 = 1,27 for tubes
 $= 1,5 \cdot \frac{1 + 4f_A}{1 + 6f_A}$

For doubly symmetric profiles including plating

$$\text{with } f = \frac{t_w}{A} \cdot \frac{b_f - 0,5}{h_w + 1}$$

b_f , t_f = Flange breadth and thickness

h_w, t_w = Web height and thickness

3. Nominal Loads

3.1 General

If the requirements of 4.1 and 4.2 are not fulfilled, the calculation of the elastic shear forces and bending moments of a trapezoidal lateral load can be carried out according to the formulas given in Table 4.5 considering the static and dynamic PSF according to A.2. and Section 5.

$$P_{A,B} = \gamma_{fstat} P_{A,Bstat} + \gamma_{fdyn} P_{A,Bdyn}$$

For other types of load combinations e.g. concentrated loads and/or other end connections the elastic shear forces and bending moments have to be determined by direct calculation.

3.2 For the shear force and bending moment at the fixed end point A of cantilevers the following formulations can be applied:

$$F_{sA} = \frac{s \cdot \ell}{2} (p_A + p_B)$$

$$M_{bA} = \frac{n_k \cdot s \cdot \ell^2}{6} \left(\frac{p_A}{2} + p_B \right)$$

3.3 Ultimate capacity

If the requirements of 4.1 and 4.2 are fulfilled, the following formulations for the determination of the shear forces and bending moments can be applied.

3.3.1 For the general case of a trapezoidal lateral load and typical end connection, the following values for F_s and M_b can be used for secondary and primary members:

- Nominal shear forces [kN] at end point A or B, respectively:

$$F_{sA,B} = \frac{s \cdot \ell}{6} \left\{ p_{A,B} \left[2 - m \frac{\left(\frac{\ell_E}{\ell} \right)}{3 - m} + p_{B,A} \frac{\left(\frac{\ell_E}{\ell} \right)^2}{1 - m} \right] \right\}$$

- Nominal bending moment [kNm]

$$M_b = \frac{n_k \cdot s \cdot \ell^2}{12 + 6j} \left(\frac{1}{0,75} - \frac{\left(\frac{\ell_E}{\ell} \right)^2}{2} \right) \cdot \left(\frac{1}{p_A} + \frac{1}{p_B} \right)$$

- Shear force and bending moment at the fixed end point A of cantilevers :

$$F_{sA} = \frac{s \cdot \ell}{2} (p_A + p_B)$$

$$M_{bA} = \frac{n_k \cdot s \cdot \ell^2}{6} \left(\frac{1}{p_A} + \frac{1}{2p_B} \right)$$

- for secondary stiffening members :

$$s = a$$

$$m = m_a$$

- for primary supporting members :

$$s = e$$

$$m = m_n$$

3.3.2 For the concentrated loads and typical end connection, the following nominal values for F_s and M_b can be used for primary members supporting secondary stiffeners and secondary members:

$$F_s = p_E \quad [\text{kN}]$$

$$M_b = \frac{p_E \cdot \ell}{4 + 2j} \left(\frac{\ell_E}{2 \cdot \ell} \right) \quad [\text{kNm}]$$

ℓ = Unsupported length [m]

ℓ_E = Length of application of the force p_E ;
= 0,0 if ℓ_E is not known

$\ell_E < \ell$

j = See 2.

This formula is based on the assumption that the ultimate bending capacity M_p has been calculated considering the maximum shear force p_E .

3.3.3 For ℓ or other loads and end connections F_s and M_b are to be calculated separately.

4. Ultimate strength criteria

4.1 General

The ultimate strength in this section is defined as the maximum normal force, shear and/or bending capacity beyond which the girder will collapse. The ultimate strength has to be calculated with the following limitations:

- Yielding of material up to a maximum strain of 10 %
- Buckling of compressed structural elements including nominal pre-deflection as described in H.
- Non linear deformation effects
- Sufficient rotation capacity in way of determined plastic hinges according to 4.2.1

In general appropriate FE-programs can be used.

Alternatively, i.e. for various cross sections within unsupported length or for grillage systems, the scantlings of secondary members can be determined on the basis of an analysis according to 7.

4.2 Ultimate capacity

4.2.1 Care is to be taken at the plastic hinges

location. In general, following design principles are to be fulfilled at plastic hinges within $\pm$ twice of the height of the structural member:

- Constant scantlings of the profile
- No cut-outs or holes
- No welds at flanges in local transverse direction for aluminum alloys

Plastic hinge method should not be used for aluminum members with transverse welds on the tension side of the member at the plastic hinge location.

(Mono-) symmetric profiles are preferably provided. For asymmetrical flanges additional tripping brackets are to be provided at plastic hinge within web depth (for aluminum structure with a minimum distance of 30 mm to the hinge).

4.2.2 A limitation of bending and rotation capacity due to buckling according to F. is not expected for cross-sections with following guidance values for the ratio web depth to web thickness and/or flange breadth to flange thickness. Subject to hole and cut-outs they can form a plastic hinge with the rotation capacity required for plastic analysis without reduction of the resistance:

- flat bars : $h_w / t_w \leq 9 \epsilon$

- Angle, tee and bulb sections :

$$\text{web: } h_w / t_w \leq 33 \epsilon$$

$$\text{flange: } b_f / t_f \leq 9 \epsilon$$

$$\epsilon = \epsilon_{St} = \sqrt{\frac{235}{R_{eH}}} \quad \text{for steel}$$

$$\epsilon = \epsilon_{Al} = \sqrt{\frac{40}{R_{eH}}} \quad \text{for aluminium}$$

Used scantlings are defined according to Figure 4.9

5. Scantlings

5.1 Simplified dimensioning

5.1.1 The scantlings of lateral loaded secondary and primary members can be determined on the basis of the following criteria if the requirements of 4.1 and 4.2 are not fulfilled:

- If the cross section is only loaded by shear, the following criterion can be applied (buckling due to shear has to be checked additionally)

$$\frac{F_s V_m}{Q_p} \leq 1,0$$

- If combined loads are applied, the following combined criterion for simultaneous bending, shear and/or axial force has to be applied

$$\frac{N}{N_{ur}} + \frac{M_{by} + N \cdot e_N}{M_{ury}} + \frac{M_{bz} + N \cdot e_N}{M_{urz}} \leq 1$$

e_N = Vertical or horizontal shift of the main axis of the uniformly compressed effective area according to F.2.2 related to the gross crosssection A.

N = Axial force [kN]

$$= \frac{\sigma_x + \sigma_L}{10} \cdot A$$

$$= N_x + \frac{\sigma_L}{10} \cdot A$$

N_x = Local axial force [kN]

σ_x = Local normal stress [N/mm²]

σ_L = Global design stress [N/mm²] according to Section 6, D.4. for longitudinal members.

N_{ur} = Reduced normal force capacity due to shear [kN]

$$= N_u \cdot K_S$$

N_u = Normal force capacity considering the effective width of compressed parts of the cross section acc. to F.2.2 [kN]

$$= 0,1 \cdot A_{\text{eff}} \cdot \frac{R_{eH} \cdot f_{pL}}{Y_m}$$

A_{eff} = Effective area of the cross section considering the effective width of compressed parts acc. to F.2.2 [cm²]

Q_p = Shear capacity [kN]

$$= \frac{1}{\sqrt{300}} A_{\text{eff}} \cdot R_{eH} \cdot f_{pL} \quad [\text{kN}]$$

M_{ur} = Reduced bending capacity due to shear

$$= M_u \cdot \kappa_s$$

M_u = Bending capacity considering the effective width of compressed parts of the cross section acc. to F.2.2 [kNm]

$$= \frac{W_{el}}{1000} \cdot \frac{R_{eH} \cdot f_{pL}}{Y_m}$$

κ_s = Shear reduction factor

$$= 1 - \left(\frac{5F_s - 1}{4Q_p} \right)^2$$

$$= 1,0 \quad \text{if } \frac{F_s}{Q_p} \leq 0,2$$

5.1.2 If the cross section fulfils the requirements given in 4.1 and 4.2, N_u [kN] and M_u [kNm] can be determined as follows:

$$N_u = 0,1A \cdot \frac{R_{eH} \cdot f_{pL}}{Y_m}$$

$$M_u = \frac{W_p}{1000} \cdot \frac{R_{eH} \cdot f_{pL}}{Y_m}$$

W_p = Plastic section modulus

$$= f_p W_{el}$$

f_p = Shape factor according to 2.

For the determination of A and W_{el} in the equations above, the effective width of the plating according to E. has to be considered.

5.2 Alternative dimensioning for stiffener

5.2.1 The following alternative analysis may also be

used for secondary stiffening, considering the reduction factors for bending, tension or compression respectively, according to E. and F.

For the calculation of the elastic stresses the nominal loads according to 3.1 are to be considered together with the corresponding static and dynamic partial safety factors γ_i according to A.2. and Section 5.

The actual sectional properties are to be related to an axis parallel to the attached plating.

If applicable, the global design stresses σ_L and τ_L (Section 6, D.4.) are to be considered.

For fatigue strength calculations the formulas given in Table 4.5 can be used, if applicable.

5.2.2 For secondary stiffening members the required web area A_s [cm²] used as effective shear area and the elastic section modulus W_{el} [cm³] can alternatively be determined as follows:

$$A_s \geq \frac{V \cdot F}{\sqrt{300}} \left[\frac{1}{R_{eH} \cdot f_{pL}} \right] \quad [\text{cm}^2]$$

$$W_{el} \geq 10^3 M \cdot \frac{Y_m \cdot k_{sp}}{\sigma_{perm} \cdot f_{pL}} \quad [\text{cm}^3]$$

σ_{perm} = Permissible stress [N/mm²]

$$= R_{eH} - 0,89 \sigma_L$$

τ = 0,0, if the shear stress is less than 0,12 R_{eH}

σ_x = Normal stress in stiffener direction

k_{sp} = Factor for profile type, see Table 4.6.

5.3 Pillars

5.3.1 Definition of loads and geometric parameters

P_s = Pillar load (load case C) [kN]

$$P_s = p_L \cdot A + P_i$$

$$= \gamma_{fstat} \cdot P_{sstat} + \gamma_{fdyn} \cdot P_{sdyn}$$

p_L = Load on decks [kN/m²] according to Section 5, E.

A = Load area for one pillar [m²]

P_i = Load from pillars located above the pillar considered [kN]

ℓ_s = Length of the pillar [cm]

I_s = Moment of inertia of the pillar [cm⁴] under consideration of effective width according to F.2.2

A_s = Effective sectional area of the pillar [cm²]

A_H = Effective sectional area of heads and heels considering hot spots [cm²]

γ_m = 1,0 in general

= 1,2 in cargo area

n_p = 0,34 for pipes and box sections

= 0,49 for open sections

for aluminum without heat treatment (i.e. 5000 series):

$\lambda_0 = 0,0$

$n_p = 0,32$

for aluminum with heat treatment (i.e. 6000 series):

$\lambda_0 = 0,1$

$n_p = 0,20$

σ_{ki} = Critical stress [N/mm²]

$$= \frac{\pi^2 \cdot E \cdot I_s}{\ell_s^2 \cdot k_s^2 \cdot A_s}$$

E = Modulus of elasticity [N/mm²]

k_s = 1,0 in general

= 0,7 for pillars with constrained ends which are supported in direction perpendicular to the pillar axis, if agreed by **BCS** in each single case.

5.3.2 Buckling criterion

The chosen scantlings of a pillar have to meet the following buckling criterion:

$$\frac{\sigma_x \cdot \gamma_m}{\kappa \cdot R_{eH}} \leq 1$$

σ_x = Stress in longitudinal direction of the pillar [N/mm²]

$$= P_s \cdot 10 / A_s$$

κ = Reduction factor

$$= \frac{1}{\varphi + \sqrt{\varphi^2 - \lambda^2}}$$

$$\varphi = 0,5 \cdot \left[1 + n_p \cdot (\lambda - 0,2) + \lambda^2 \right]$$

$$\lambda = \sqrt{\frac{R_{eH}}{\sigma_{ki}}} \quad \lambda_{\min} = \lambda_0$$

for steel:

$$\lambda_0 = 0,2$$

Pillars which are additionally loaded by bending moments have to be specially considered.

5.3.3 Heads and heels

Structural members at heads and heels of pillars as well as substructures are to be constructed according to the forces they are subjected to. The connection is to be so designed that the following condition is met:

$$\frac{R_{eH}}{Y_m} \geq \frac{10 \cdot P_s}{A_H}$$

Where pillars are affected by tension loads doublings are not permitted.

5.3.4 Pillars in tanks

Tubular pillars are not permitted in tanks for flammable liquids.

6. Deflection criterion

6.1 The maximum permissible elastic deflection of a loaded girder, with the length ℓ under consideration of a partial safety factor $\gamma_f = 1$ shall be determined by:

$$f_{\text{perm}} = \ell / \text{value}, \text{ value acc. to Table 4.4.}$$

Table 4.4 Values for determination of permissible deflection

Structural element	Value	
	steel	aluminium
Slamming (shell)	500	700
Shell, bhd., tank	400	560
Stringer, decks, ramps	200	280

6.2 Smaller deflections may be required if the proper functioning of naval equipment, like driving devices, weapons, sensors, etc. would be impaired by the deflections defined above.

D. End attachments

1. Definitions

For determining scantlings of beams, stiffeners and girders the terms "constraint" and "simple support" will be used.

"Constraint" will be assumed where for instance the stiffeners are rigidly connected to other members by means of brackets or are running throughout over supporting girders. "Simple support" will be assumed where for instance the stiffener ends are sniped or the stiffeners are connected to plating only.

2. Sniped ends of stiffeners

Stiffeners may be sniped at the ends, if the thickness of the plating supported by stiffeners is not less than:

$$t = 20 \sqrt{\frac{F \cdot \gamma_m}{R_{eH}}} + t_K \text{ [mm]}$$

F = Maximum support force [kN] to be transferred by the plating

$$= F_A \text{ or } F_B \text{ according to Table 4.5}$$

3. Corrugated bulkhead elements

Care is to be taken that the forces acting at the supports of corrugated bulkheads are properly transmitted into the adjacent structure by fitting structural elements such as carlings, girders or floors in line with the corrugations.

Note

Where carlings or similar elements cannot be fitted in line with the web strips of corrugated bulkhead elements, these web strips cannot be included into the section modulus at the support point for transmitting the moment of constraint.

Other than in Section 9, C. 2. the section modulus of a corrugated element is then to be determined by the following formula.

$$W_{el} = t \cdot b(d + t) \left[\frac{\text{cm}^3}{\text{mm}} \right]$$

4. Brackets

4.1 For the scantlings of brackets the required section modulus of the stiffener is determining. Where stiffeners of different section module are connected to each other, the scantlings of the brackets are generally governed by the smaller stiffener.

4.2 The net thickness of brackets is not to be less than:

$$t' = c \cdot \sqrt[3]{M_{bp}} \text{ [mm]}$$

$$c = 1,9 \text{ for non-flanged brackets}$$

$$= 1,5 \text{ for flanged brackets}$$

M_{bp} = Nominal bending moment [kNm] of profile with $n = 1,0$; but not less than the capacity of the profile M_p according to C.4.1 or alternatively

$$M_p = W_{el} \frac{R_{eH} f_p}{k_{sp}}$$

t_{min} = 5,0 mm

t_{max} = web thickness of smaller stiffener

For minimum thicknesses in tanks see Section 10.

4.3 The arm length of brackets is not to be less than:

$$\ell = 1148 \cdot \frac{\sqrt[3]{M_{bp}}}{\sqrt{R_{eHb}}} \cdot c_t \text{ [mm]}$$

ℓ_{min} = 100 mm

M_{bp} = see 4.2

R_{eHb} = minimum yield stress of the bracket material [N/mm²]

$$c_t = \sqrt{\frac{t}{t_a}}$$

t_a = "as built" thickness of bracket [mm]

$\geq t$ according to 4.2

The arm length ℓ is the length of the welded connection.

Note

For deviating arm lengths the thickness of bracket is to be estimated by direct calculations considering sufficient safety against buckling.

4.4 The throat thickness of the welded connection is to be determined according to Section 15.

4.5 Where flanged brackets are used, the width of flange is to be determined according to the following formula:

$$b = 40 + 33 \frac{M_{bp}}{R_{eHp}} \text{ [mm]}$$

$\leq 90 \text{ mm}$

M_{bp} = See 4.2

R_{eHp} = Minimum yield strength of the profile material [N/mm²]

4.6 Tween deck frames are to be connected to the main frames below. The end attachment may be carried out in accordance with Figure 4.5.

The following requirement must be fulfilled:

$$M_{p0} \geq M_{p1} + M_{p2}$$

M_{pi} = capacity of profile i (see 4.2)

Index 0 refers to the profile with the greatest capacity of the connection point.




Figure 4.5 Connection of tween deck frames with decks and frames below

5. Additional stresses in asymmetric sections

The additional stress σ_h occurring in asymmetric sections according to Figure 4.6 may be calculated by the following formula:

$$\sigma_h = \frac{Q}{c \cdot W_y \cdot W_z} \cdot \frac{b}{\ell_f} \cdot t_f \cdot \frac{1}{2} \cdot \frac{1}{2} \cdot \text{Mpa.}$$

Q = Load on section parallel to its web within the unsupported span ℓ_f [kN]

= $p \cdot a \cdot \ell_f$ [kN] in case of uniformly distributed load p [kN/m²]

- ℓ_f = Unsupported span of flange [m]
- t_f, b_1 = Flange dimensions [mm]
- b_2 = As shown in Figure 4.6
- $b_1 \geq b_2$
- W_y = Elastic section modulus of section related to the y-y axis including the effective width of plating [cm³]
- W_z = Elastic section modulus of the partial section consisting of flange and half of web area related to the z-z axis [cm³], (bulb sections may be converted into similar L-section).
- c = Factor depending on kind of load, stiffness of the section's web and length and kind of support of profile

For profiles clamped at both ends $c = 80$ can be taken for approximation.

This additional stress σ_h is to be added directly to other stresses such as those resulting from local and hull girder bending.




Figure 4.6 Additional stresses at asymmetric sections

The total stress [N/mm²] according to local bending thus results in:

$$\sigma = \frac{Q \cdot \ell_f \cdot 1000}{12 \cdot W_y} \left[1 + \frac{12 \cdot t_f (b^2 - b^2)}{1000 \cdot c \cdot W_z} \right]$$

The required section modulus W_y is to be multiplied by the factor k_{sp} depending on the type of profile and the boundary conditions expressed by the factor c .

$$k_{sp} = \frac{12 \cdot W_y}{Q \cdot \ell_f \cdot 1000} \cdot \sigma$$

For k_{sp} at least the values in Table 4.6 are to be taken.

Table 4.6 Factor k_{sp} for various sections

Type of section	k_{sp}
Flat bars and symmetric T-sections	1,00
Bulb sections	1,03
Asymmetric T-sections $\frac{b_2}{b_1} \approx 0,5$	1,05
Rolled angles (L-sections)	1,15

E. Effective Width of Plating

1. Girders, frames and stiffeners

1.1 The effective width of plating e_m of stiffeners, frames and girders may be determined according to Table 4.7 considering the type of loading.

Special calculations may be required for determining the effective width of one-sided or non-symmetrical flanges.

1.2 The effective area of plates is not to be less than the area of the face plate.

1.3 The effective width of stiffeners and girders subjected to compressive stresses may be determined according to F.2.2, but is in no case to be taken greater than determined by 1.1.

Table 4.5 Determination of elastic stresses for load case LCC





Arrangement and loads	Type of end connection		
	Simple support at both ends	Simple support at one end, constraint at other end	Constraint at both ends
			
Calculation of details for fatigue strength assessment:			
Pressure at A [kN/m ²] Pressure at B [kN/m ²]	$p_A = p_{Astat} + p_{Adyn}$ $p_B = p_{Bstat} + p_{Bdyn}$		
Shear force (elastic) [kN]	$F_{A0} = \frac{a \cdot \ell}{6} \left\{ p \left[2 - m(3 - m) \right] + p_B (1 - m_2) \right\}$ $F_{B0} = \frac{a \cdot \ell}{6} \left\{ p (1 - m^2) + p_B [2 - m(3 - m)] \right\}$	$F_A = F_{A0} - \frac{M_B}{\ell}$ $F_B = F_{B0} + \frac{M_B}{\ell}$	$F_A = F_{A0} + \frac{M_A - M_B}{\ell}$ $F_B = F_{B0} - \frac{M_A - M_B}{\ell}$
Bending moment (elastic) [kNm]	$M_0 = \frac{a \cdot \ell^2}{12} \left(0,75 - m^2 \right) \cdot \left(p_A + p_B \right)$	$M_B = \frac{a \cdot \ell^2}{12} \cdot n \cdot \left[p_A (0,7 - 0,925 m^2) + p_B (0,8 - 0,925 m^2) \right]$	$M_A = \frac{a \cdot \ell^2}{12} \cdot n \cdot \left[p_A (0,6 - 1,15 m^2) + p_B (0,4 - 0,35 m^2) \right]$ $M_B = \frac{a \cdot \ell^2}{12} \cdot n \cdot \left[p_A (0,4 - 0,35 m^2) + p_B (0,6 - 1,15 m^2) \right]$
Elastic shear stress [N/mm ²]		$\tau_B = \frac{F_B \cdot 10}{A_{SB}}$	$\tau_A = \frac{F_A \cdot 10}{A_{SA}}$ $\tau_B = \frac{F_B \cdot 10}{A_{SB}}$
Elastic bending stress [N/mm ²]	$\sigma = \frac{M_0 \cdot k_{sp} \cdot 10^3}{W_{el}}$	$\sigma_B = \frac{M_B \cdot k_{sp} \cdot 10^3}{W_{el}}$	$\sigma_A = \frac{M_A \cdot k_{sp} \cdot 10^3}{W_{el}}$ $\sigma_B = \frac{M_B \cdot k_{sp} \cdot 10^3}{W_{el}}$
Other types of load combinations and/or end connections are subject to direct calculation			

Table 4.7 Effective width of plating e_m of frames and girders

l/e	0	1	2	3	4	5	6	7	≥ 8
e_{m1}/e	0	0,36	0,64	0,82	0,91	0,96	0,98	1,00	1,0
e_{m2}/e	0	0,20	0,37	0,52	0,65	0,75	0,84	0,89	0,9

e_{m1} is to be applied where girders are loaded by uniformly distributed loads or else by not less than 6 equally spaced single loads.

e_{m2} is to be applied where girders are loaded by 3 or less single loads.

Intermediate values may be obtained by direct interpolation.

l = length between zero-points of bending moment curve, i.e. unsupported span in case of simply supported girders and 0,6 x unsupported span in case of constraint of both ends of girder

e = width of plating supported, measured from centre to centre of the adjacent unsupported fields

2. Cantilevers

Where cantilevers are fitted at every frame, the effective width of plating may be taken as the frame spacing.

Where cantilevers are fitted at a greater spacing the effective width of plating at the respective cross section may approximately be taken as the distance of the cross section from the point on which the load is acting, however, not greater than the spacing of the cantilevers

F. Proof of Buckling Strength

1. General

1.1 Calculation method

The calculation method for buckling strength used in the following is based on the standard DIN18800.

1.2 Definitions

A_e = Effective area for calculation of plastic section moduli [mm²]


A_x, A_y = Sectional area of longitudinal or transverse stiffeners respectively [mm²]

a = Length of single or partial plate field [mm]

b = Breadth of single plate field [mm]

α = Aspect ratio of single plate field

$$= \frac{a}{b}$$



longitudinal : stiffener in the direction of the length a
transverse : stiffener in the direction of the breadth b

Figure 4.7 System of longitudinal and transverse stiffeners

c_s = Factor accounting for the boundary conditions of the transverse stiffener

= 1,0 for simply supported stiffeners

= 2,0 for partially constraint stiffeners

f_p = Ratio of plastic and elastic section modulus of the profile, see C.2.

h_{wx}, h_{wy} = Web height [mm] of longitudinal or transverse stiffeners

I_x, I_y = Moments of inertia [cm⁴] of longitudinal or transverse stiffeners including effective width of plating according to 2.2

M_0 = Bending moment due to deformation w_0 of longitudinal or transverse stiffeners [Nmm]

M_1 = Bending moment due to lateral load p [Nmm]

n_a, n_b = Number of single plate field breadth within the partial or total plate field, see Figure 4.7

t = Nominal plate thickness [mm]

= $t_a - t_k$ [mm]

t_a = Plate thickness as built [mm]

t_k = Corrosion addition according to B.3. [mm]

t_{wx}, t_{wy} = Web thickness [mm] of longitudinal or transverse stiffeners

w_0 = Assumed imperfection [mm]

w_1 = Deformation of stiffener due to lateral load p at midpoint of stiffener span [mm]

e = Degree of restraint

κ = Reduction factor for torsion

σ_x = Membrane stress in x-direction [N/mm²]

σ_y = Membrane stress in y-direction [N/mm²]

τ = Shear stress in the x-y plane [N/mm²]

Compressive and shear stresses are to be taken positive, tensile stresses are to be taken negative.

Note

If the stresses in the x- and y-direction contain already the Poisson - effect, the following modified stress values may be used:

$$\sigma_x^* = \frac{\sigma_x - 0,3 \cdot \sigma_y}{0,91}$$

$$\sigma_y^* = \frac{\sigma_y - 0,3 \cdot \sigma_x}{0,91}$$

σ_x^*, σ_y^* = Stresses containing the Poisson-effect

Ψ = Edge stress ratio according to Table 4.10

F_1 = Correction factor for boundary condition at the longitudinal stiffeners according to Table 4.8

σ_e = Reference stress

$$= \frac{\pi^2 \cdot E \cdot \left(\frac{t}{b} \right)^2}{12(1-\nu^2)} \quad [\text{MPa}]$$

E = Modulus of elasticity [N/mm²], see A.2. Section B1, B.14.

ν = Poisson ratio, see A.2. Section B1, B.14.

R_{eH} = See, A.2

γ_m = Partial safety factors according to Table 4.1

λ = Reference degree of slenderness:

$$\lambda = \sqrt{\frac{R_{eH}}{K \cdot \sigma_e}}$$

K = Buckling factor according to Tables 4.10 and 4.11

In general, the ratio plate field breadth to plate thickness shall not exceed $b/t = 100$.

2. Single plate buckling

2.1 Proof is to be provided that the following condition is complied with for the single plate field $a \cdot b$:

$$\left(\frac{\sigma_x \cdot \gamma}{\kappa_x \cdot R_{eH}^m} \right)^{e_1} + \left(\frac{\sigma_y \cdot \gamma}{\kappa_y \cdot R_{eH}^m} \right)^{e_2} + B \cdot \left(\frac{\sigma_x \cdot \sigma_y \cdot \gamma^2}{R_{eH}^y \cdot 2^m} \right) + \left(\frac{\tau \cdot \gamma \cdot \sqrt{3}}{\kappa_t \cdot R_{eH}} \right)^{e_3} \leq 1,0$$

Each term of the above condition must be less than 1,0.

The reduction factors κ_x , κ_y and κ_τ are given in Table 4.10 and/or 4.11.

Where $\sigma_x \leq 0$ (tension stress), $\kappa_x = 1,0$.

Where $\sigma_y \leq 0$ (tension stress), $\kappa_y = 1,0$.

The exponents e_1 , e_2 and e_3 as well as the factor B are calculated or set respectively according to Table 4.9.

Table 4.8 Correction factor F_1 for boundary conditions

End form of stiffeners	Profile type	F_1
sniped at both ends or single side welded	all types	1,00 (1)
both ends are effectively connected to adjacent structures	flat bars	1,05 (1)
	bulb sections	1,10 (1)
	angle and tee sections	1,20 (1)
	girders of high rigidity, e.g. bottom transverses	1,30 (1)

(1) only guidance values, exact values may be determined by direct calculations

Table 4.9 Exponents e_1 - e_3 and factor B

Exponents e_1 - e_3 and factor B	plate field	
	plane	curved
e_1	$1 + \kappa_x^4$	1,25
e_2	$1 + \kappa_y^4$	1,25
e_3	$1 + \kappa_x \cdot \kappa_y \cdot \kappa_\tau^2$	2,0
B σ_x and σ_y positive (compression stress)	$(\kappa_x \cdot \kappa_y)^5$	0
B σ_x or σ_y negative (tension stress)	1	—

2.2 Effective width of plating

The effective width of plating may be determined by the following formulae, see also Figure 4.7:

$$b_m = \kappa_x \cdot b \text{ for longitudinal stiffeners}$$


$$a_m = \kappa_y \cdot a \text{ for transverse stiffeners}$$

The effective width of plating is not to be taken greater than the value obtained from E. 1.1.

Note

The effective width e'_m of the stiffed flange plates of girders may be determined approximately as follows:

Stiffening parallel to web of girder:



$$b < e_m$$

$$e'_m = n \cdot b_m$$

$$n = \text{integer number of the stiffener spacing } b \text{ inside the effective width } e_m \text{ according to Table 4.7.}$$


$$= \text{int} \left(\frac{e_m}{b} \right)$$

stiffening perpendicular to web of girder:

$$a \geq e_m$$

$$e'_m = n \cdot a_m < e_m$$

$$n = 2,7 \cdot \frac{e_m}{a} \leq 1$$



$$e = \text{width of plating supported according to E.1.1.}$$

For $b \geq e_m$ or $a < e_m$ respectively, b and a must be exchanged.

a_m and b_m for flange plates are in general to be determined for $\psi = 1$.

Stress distribution between two girders:

$$\sigma_x(y) = \sigma_{x1} \{1 - y/e [3 + c_1 - 4c_2 - 2y/e (1 + c_1 - 2c_2)]\}$$

$$c_1 = \sigma_{x2} / \sigma_{x1} \quad 0 \leq c_1 \leq 1$$

$$c_2 = 1,5/e \cdot (e''_{m1} + e''_{m2}) - 0,5$$

$$e''_{m1} = e'_{m1} / e_{m1}$$

$$e''_{m2} = e'_{m2} / e_{m1}$$

σ_{x1}, σ_{x2} = normal stresses in flange plates of adjacent girder 1 and 2 with spacing e

y = distance of considered location from girder 1

Scantlings of plates and stiffeners are in general to be determined according to the maximum stresses $\sigma_x(y)$ at girder webs and stiffeners respectively. For stiffeners under compression arranged parallel to the girder web with spacing b no lesser value than $0,25 \cdot R_{eH}$ shall be inserted for $\sigma_x(y=b)$. Shear stress distribution in the flange plates may be assumed linearly.

2.3 Webs and flanges

For non-stiffened webs and flanges of sections and girders proof of sufficient buckling strength as for single plate fields is to be provided according to 2.1.

Note

The following guidance values are recommended for the ratio web depth to web thickness and/or flange breadth to flange thickness for normal and higher strength hull structural steel:

$$\text{flat bars: } \frac{h_w}{t_w} \leq \frac{215}{\sqrt{R_{eH}}}$$

angle-, tee and bulb sections:

$$\text{web: } \frac{h_w}{t_w} \leq \frac{661}{\sqrt{R_{eH}}}$$

$$\text{flange: } \frac{b_i}{t_w} \leq \frac{215}{\sqrt{R_{eH}}}$$

b_i = b_1 or b_2 according to Figure 4.8, the larger value is to be taken.




Figure 4.8 Main parameters of typical sections

3. Proof of partial and total fields

Proof is to be provided that the continuous longitudinal and transverse stiffeners of partial and total plate fields comply for lateral and torsional buckling with the conditions of Table 4.11.

The parameters of typical sections are shown in Figure 4.8 and the resulting moments of inertia are summarized in Table 4.12.

3.1 Longitudinal and transverse stiffeners

Proof is to be provided that the continuous longitudinal and transverse stiffeners of partial and total plate fields comply with the conditions set out in 3.2 and 3.3.

3.2 Lateral buckling

$$\frac{\sigma_a + \sigma_b}{R_{eH}} \cdot S \leq 1$$

σ_a = Uniformly distributed compressive stress in the direction of the stiffener axis in [N/mm²]

σ_a = σ_x for longitudinal stiffeners

σ_a = σ_y for transverse stiffeners

σ_b = Bending stress in the stiffeners

$$\sigma_b = \frac{M_0 + M_1}{W_{st} \cdot 10^3} \quad [\text{N/mm}^2]$$

M_0 = Bending moment due to deformation w of stiffener

$$M_0 = F_{Ki} \frac{p_z \cdot W}{C_f - p_z} \quad [\text{N} \cdot \text{mm}]$$

$$(C_f - p_z) > 0$$

M_1 = Bending moment due to the lateral load p for continuous longitudinal stiffeners:

$$M_1 = \frac{p \cdot b \cdot a^2}{24 \cdot 10^3} \quad [\text{N} \cdot \text{mm}]$$

for transverse stiffeners :

$$M_1 = \frac{p \cdot a \cdot (n \cdot b)^2}{c_s \cdot 8 \cdot 10^3} \quad [\text{N} \cdot \text{mm}]$$

p = Lateral load in $[\text{kN}/\text{m}^2]$ according to Section 5

F_{Ki} = Ideal buckling force of the stiffener in $[\text{N}]$

$$F_{Kix} = \frac{\pi^2 \cdot E \cdot I_x}{a^2} \cdot 10^4 \quad \text{for long. stiffeners}$$

$$F_{Kiy} = \frac{\pi^2 \cdot E \cdot I_y}{(n \cdot b)^2} \cdot 10^4 \quad \text{for transv. stiffeners}$$

I_x, I_y = Moments of inertia of the longitudinal or transverse stiffener including effective width of plating according to 2.2 in $[\text{cm}^4]$

$$I_x \geq \frac{b \cdot t^3}{12 \cdot 10^4}$$

$$I_y \geq \frac{a \cdot t^3}{12 \cdot 10^4}$$

p_z = Nominal lateral load of the stiffener due to σ_x , σ_y and τ in $[\text{N}/\text{mm}^2]$

for longitudinal stiffeners:

$$p_{zx} = \frac{t_a}{a} \left(\sigma_{xl} \left(\frac{n \cdot b}{a} \right)^2 + 2 \cdot c_y \cdot \sigma_y + \sqrt{\frac{2 \cdot \tau}{t_1}} \right)$$

for transverse stiffeners:

$$p_{zy} = \frac{t_a}{a} \left(2 \cdot c_x \cdot \sigma_{xl} + \sigma_y \left(\frac{n \cdot a}{n \cdot b} \right)^2 \left(1 + \frac{A_y}{a \cdot t_a} \right) + \sqrt{\frac{2 \cdot \tau}{t_1}} \right)$$

$$\sigma_{xl} = \sigma_x \left(1 + \frac{A_x}{b \cdot t_a} \right)$$

c_x, c_y = Factor taking into account the stresses vertical to the stiffener's axis and distributed variable along the stiffener's length

$$c_x, c_y = 0,5 (1 + \Psi) \quad \text{for } 0 \leq \Psi \leq 1$$

$$c_x, c_y = \frac{0,5}{1 - \Psi} \quad \text{for } \Psi < 0$$

Ψ = Edge stress ratio according to Table 4.10.

A_x, A_y = Sectional area of the longitudinal or transverse stiffener respectively in $[\text{mm}^2]$

$$\tau_1 = \left[\tau - t \sqrt{\frac{ReH \cdot E}{\left(\frac{m_1}{a^2} + \frac{m_2}{b^2} \right)}} \right] \geq 0$$

for longitudinal stiffeners: :

$$\frac{a}{b} \geq 2,0 : m_1 = 1,47 \quad m_2 = 0,49$$

$$\frac{a}{b} < 2,0 : m_1 = 1,96 \quad m_2 = 0,37$$

for transverse stiffeners :

$$\frac{a}{n \cdot b} \geq 0,5 : m_1 = 0,37 \quad m_2 = \frac{1,96}{n^2}$$

$$\frac{a}{n \cdot b} < 0,5 : m_1 = 0,49 \quad m_2 = \frac{1,47}{n^2}$$

$$W = W_0 + W_1$$

W_0 = Assumed imperfection in $[\text{mm}]$

$$\frac{a}{250} \geq W_{0x} \leq \frac{b}{250} \quad \text{for long. stiffeners}$$

$$\frac{n \cdot b}{250} \geq W_{0y} \leq \frac{a}{250} \quad \text{for transv. stiffeners}$$

however $W_0 \leq 10 \text{ mm}$.

Note :

For stiffeners sniped at both ends W_0 must not be taken less than the distance from the midpoint of plating to the neutral

axis of the profile including effective width of plating.

W_1 = Deformation of stiffener due to lateral load p at midpoint of stiffener span in $[\text{mm}]$

In case of uniformly distributed load the following values for W_1 may be used:

for longitudinal stiffeners:

$$W_1 = \frac{p \cdot b \cdot a^4}{384 \cdot 10^7 \cdot E \cdot I_x}$$

for transverse stiffeners:

$$w_1 = \frac{5 \cdot a \cdot p \cdot (n \cdot b)^4}{384 \cdot 10^7 \cdot E \cdot \frac{1}{t} \cdot c^2}$$

C_f = Elastic support provided by the stiffener in [N/mm²]

$$C_{fx} = F_{Kix} \cdot \frac{\pi^2}{a^2} \cdot (1 + c_{px}) \quad \text{for long. stiffeners}$$

$$C_{px} = \frac{1}{0,91 \cdot \left(\frac{12 \cdot 10^4 \cdot I_x}{t^3 \cdot b} - 1 \right)} \cdot \frac{1}{1 + \frac{\left(\frac{a}{2b} + \frac{2b}{a} \right)^2}{c_{x\alpha}}}$$

$$C_{x\alpha} = \left[\frac{a}{2b} + \frac{2b}{a} \right]^2 \quad \text{for } a \geq 2b$$

$$= \left[1 + \left(\frac{a}{2b} \right)^2 \right]^2 \quad \text{for } a < 2b$$

$$C_{fy} = C_s \cdot F_{Kiy} \cdot \frac{\pi^2}{(n \cdot b)^2} \cdot (1 + c_{py}) \quad \text{for transverse stiffeners}$$

C_s = Factor accounting for the boundary conditions of the transverse stiffener

$$C_s = 1,0 \quad \text{for simply supported stiffeners}$$

$$C_s = 2,0 \quad \text{for partially constraint stiffeners}$$

$$C_{py} = \frac{1}{0,91 \cdot \left(\frac{12 \cdot 10^4 \cdot I_y}{t^3 \cdot a} - 1 \right)} \cdot \frac{1}{1 + \frac{\left(\frac{n \cdot b}{2a} + \frac{2a}{n \cdot b} \right)^2}{c_{y\alpha}}}$$

$$C_{y\alpha} = \left[\frac{n \cdot b}{2a} + \frac{2a}{n \cdot b} \right]^2 \quad \text{for } n \cdot b \geq 2a$$

$$= \left[1 + \left(\frac{n \cdot b}{2a} \right)^2 \right]^2 \quad \text{for } n \cdot b < 2a$$

W_{st} = Section modulus of stiffener (long. or transverse) in [cm³] including effective width of plating according to 2.2.

If no lateral load p is acting the bending stress σ_b is to be calculated at the midpoint of the stiffener span for the fibre which results in the largest stress value. If a lateral load p is acting, the stress calculation is to be

carried out for both fibres of the stiffener's cross sectional area (If necessary, for the biaxial stress field at the plating side).

Note:

Longitudinal and transverse stiffeners not subjected to lateral load p have sufficient scantlings if their moments of inertia I_x and I_y are not less than obtained by the following formulae:

$$I_x = \frac{p \cdot a^2}{\pi^2 \cdot 10^4} \left[\frac{R_{eH} \cdot w}{S} + \frac{w \cdot h}{\pi^2 \cdot E} \right] \quad [\text{cm}^4]$$

$$I_y = \frac{p \cdot (n \cdot b)^2}{\pi^2 \cdot 10^4} \left[\frac{R_{eH} \cdot w}{S} + \frac{w \cdot h}{\pi^2 \cdot E} \right] \quad [\text{cm}^4]$$

3.3 Torsional buckling

3.3.1 Longitudinal stiffeners:

$$\frac{\sigma_x \cdot S}{K_T \cdot R_{eH}} \leq 1,0$$

$$K_T = 1,0 \quad \text{for } \lambda_T \leq 0,2$$

$$K_T = \frac{1}{\phi + \sqrt{\phi^2 - \lambda_T^2}} \quad \text{for } \lambda_T > 0,2$$

$$\phi = 0,5 \cdot [1 + 0,21 (\lambda_T - 0,2) + \lambda_T^2]$$

λ_T = Reference degree of slenderness

$$\lambda_T = \sqrt{\frac{R_{eH}}{\sigma_{KIT}}}$$

$$\sigma_{KIT} = \frac{E}{I_P} \left(\frac{\pi^2 \cdot I_{\omega} \cdot 10^2}{a^2} \cdot \varepsilon + 0,385 \cdot I_T \right) \quad [\text{N/mm}^2]$$

I_P, I_T, I_{ω} see Table 4.12.

I_P = Polar moment of inertia of the stiffener related to the point C in [cm⁴]

I_T = St. Venant's moment of inertia of the stiffener in [cm⁴]

I_{ω} = Sectorial moment of inertia of the stiffener related to the point C in [cm⁴]

ε = Degree of fixation

$$\varepsilon = 1 + 10^{-4} \sqrt{\frac{a^4}{I_{\omega} \left(\frac{b}{t^3} + \frac{4}{3} \frac{h_w}{t_w^3} \right)}}$$

h_w = Web height [mm]

t_w = Web thickness [mm]

b_f = Flange breadth [mm]

t_f = Flange thickness [mm]

A_w = Web area $h_w \cdot t_w$

A_f = Flange area $b_f \cdot t_f$

3.3.2 Transverse stiffeners

For transverse stiffeners loaded by compressive stresses and which are not supported by longitudinal stiffeners proof is to be provided in accordance with 3.3.1 analogously.

G. Structural Details

1. Longitudinal members

1.1 All longitudinal members taken into account for calculating the midship section modulus are to extend over the required length amidships and are to be tapered gradually to the required end scantlings, see also Section 6.

1.2 Abrupt discontinuities of strength of longitudinal members are to be avoided as far as practicable. Where longitudinal members having different scantlings are connected with each other, smooth transitions are to be provided.

1.3 At the ends of longitudinal bulkheads or continuous longitudinal walls suitable shifting brackets are to be provided.

1.4 Flanged structural elements transmitting forces perpendicular to the knuckle, are to be adequately supported at their knuckle, i.e. the knuckles of the inner bottom are to be located above floors, longitudinal girders or bulkheads.

If longitudinal structures, such as longitudinal bulkheads or decks, include a knuckle which is formed by two butt-welded plates, the knuckle is to be supported in the vicinity of the joint rather than at the exact location of the joint. The minimum distance d to the supporting structure is to be at least.

$$d = 25 + t_f / 2$$

but not more than 50 mm, see Figure 4.10.

2. Primary supporting members

2.1 In general the depth of girders should not be less than 1/25 of the unsupported span. The web depth of girders supporting continuous secondary stiffeners is to be at least 1,5 times the depth of the stiffeners.

2.2 Where transverses and girders fitted in the same plane are connected to each other, major discontinuities of strength shall be avoided. The web depth of the smaller girder shall, in general, not be less than 60 % of the web depth of the greater one.

2.3 The taper between face plates with different dimensions is to be gradual. In general the taper shall not exceed 1: 3. At intersections the forces acting in the face plates are to be properly transmitted.

2.4 For transmitting the acting forces the face plates are to be supported at their knuckles. For supporting the face plates of cantilevers, see Figure 4.9.




Figure 4.9 Support of the face plates of cantilevers

Table 4.10 Plane Plate Fields



Load case		Edge stress ratio Ψ	Aspect ratio α	Buckling factor K	Reduction factor κ
1		$1 \geq \Psi \geq 0$	$\alpha > 1$	$K = \frac{8,4}{\Psi + 1,1}$	$\kappa_x = 1$ for $\lambda \leq \lambda_c$ $\kappa_x = c \left(\frac{1}{\lambda} - \frac{0,22}{\lambda^2} \right)$ for $\lambda > \lambda_c$ $c = 1,25 - 0,12 \Psi \leq 1,25$ $\lambda_c = \frac{c}{2} \left(1 + \sqrt{1 - \frac{0,88}{c}} \right)$
		$0 > \Psi > -1$ $\Psi \leq -1$		$K = 7,63 - \Psi(6,26 - 10\Psi)$ $K = (1 - \Psi)^2 \cdot 5,975$	
2		$1 \geq \Psi \geq 0$	$\alpha \geq 1$	$K = F_1 \left(1 + \frac{1}{\alpha^2} \right)^2 \frac{2,1}{(\Psi + 1,1)}$	$\kappa_y = c \left(\frac{1}{\lambda} - \frac{R + F^2 (H - R)}{\lambda^2} \right)$ $c = 1,25 - 0,12 \Psi \leq 1,25$ $R = \lambda \left(1 - \frac{\lambda}{c} \right)$ for $\lambda < \lambda_c$ $R = 0,22$ for $\lambda \geq \lambda_c$ $\lambda_c = \frac{c}{2} \left(1 + \sqrt{1 - \frac{0,88}{c}} \right)$ $F = \left\{ 1 - \frac{K}{\lambda_p^2} \right\} \left\{ 1 - \frac{0,91}{\lambda_p^2} \right\} \geq 0$ $\lambda_p^2 = \lambda^2 - 0,5$ $1 \leq \lambda_p^2 \leq 3$ $c = 1$ For σ_y due to direct loads $c = \left(1 - \frac{F_1}{\alpha} \right) \geq 0$ For σ_y due to bending (in general) $c_1 = 0$ For σ_y due to bending in extreme load cases (e.g. w.t. bulkheads) $H = \lambda - \frac{2\lambda}{c \cdot (T + \sqrt{T^2 - 4})} \geq R$ $T = \lambda + \frac{14}{15\lambda} + \frac{1}{3}$
		$0 > \Psi > -1$	$1 \leq \alpha \leq 1,5$	$K = F_1 \left[\left(1 + \frac{1}{\alpha^2} \right)^2 \frac{2,1}{1,1} (1 + \Psi) - \frac{\Psi}{\alpha^2} (13,9 - 10\Psi) \right]$	
		$\Psi \leq -1$	$\alpha > 1,5$	$K = F_1 \left[\left(1 + \frac{1}{\alpha^2} \right)^2 \frac{2,1}{1,1} (1 + \Psi) - \frac{\Psi}{\alpha^2} (5,87 + 1,87 \alpha^2 + \frac{8,6}{\alpha^2} - 10\Psi) \right]$	
			$1 \leq \alpha \leq \frac{3(1 - \Psi)}{4}$	$K = F_1 \left(\frac{1 - \Psi}{\alpha} \right)^2 5,975$	
			$1 > \frac{3(1 - \Psi)}{4}$	$K = F_1 \left[\left(\frac{1 - \Psi}{\alpha} \right)^2 3,9675 + 0,5375 \left(\frac{1 - \Psi}{\alpha} \right)^4 + 1,87 \right]$	

Table 4.10 Plane Plate Fields







Load case		Edge stress ratio Ψ	Aspect ratio α	Buckling factor K	Reduction factor κ
3		$1 \geq \Psi \geq 0$	$\alpha > 0$	$K = \frac{4(0,425 + 1/\alpha^2)}{3\Psi + 1}$ $K = 4 \left(0,425 + \frac{1}{\alpha^2} \right) (1 + \Psi)$	$\kappa_x = 1$ for $\lambda \leq 0,7$
		$0 > \Psi \geq -1$		$-5 \cdot \Psi(1 - 3,42 \Psi)$	
4		$1 \geq \Psi \geq -1$	$\alpha > 0$	$K = \left(0,425 + \frac{1}{\alpha^2} \right) \frac{3 - \Psi}{2}$	$\kappa_x = \frac{1}{\lambda^2 + 0,51}$ for $\lambda > 0,7$
5		-	$\alpha \geq 1$ $0 < \alpha < 1$	$K = K_r \sqrt{3}$ $K_r = \left[5,34 + \frac{4}{\alpha^2} \right]$ $K_r = \left[4 + \frac{5,34}{\alpha^2} \right]$	$\kappa_\tau = 1$ for $\lambda \leq 0,84$ $\kappa_\tau = \frac{0,84}{\lambda}$ for $\lambda > 0,84$
6		-		$K = K' r$ $K' = K$ acc. to load case 5 $r = \text{reduction factor}$ $r = \left(1 - \frac{d_a}{a} \right) \left(1 - \frac{d_b}{b} \right)$ with $\frac{d_a}{a} \leq 0,7$ and $\frac{d_b}{b} \leq 0,7$	
7		-	$\alpha \geq 1,64$ $\alpha < 1,64$	$K = 1,28$ $K = \frac{1}{\alpha^2} + 0,56 + 0,13 \alpha^2$	$\kappa_x = 1$ for $\lambda \leq 0,7$ $\kappa_x = \frac{1}{\lambda^2 + 0,51}$ for $\lambda > 0,7$
8		-	$\alpha \geq \frac{2}{3}$ $\alpha < \frac{2}{3}$	$K = 6,97$ $K = \frac{1}{\alpha^2} + 2,5 + 5 \alpha^2$	$\kappa_x = 1$ for $\lambda \leq 0,83$ $\kappa_x = 1,13 \left[\frac{1}{\lambda} - \frac{0,22}{\lambda^2} \right]$ for $\lambda > 0,83$

Table 4.10 Plane Plate Fields



Load case		Edge stress ratio Ψ	Aspect ratio α	Buckling factor K	Reduction factor κ
9		-	$\alpha \geq 4$	$K = 4$	$\kappa_x = 1$ for $\lambda \leq 0,83$ $\kappa_x = 1,13 \left[\frac{1}{\lambda} - \frac{0,22}{\lambda^2} \right]$ for $\lambda > 0,83$
			$4 > \alpha > 1$	$K = 4 + \left[\frac{4 - \alpha}{3} \right]^4 2,74$	
			$\alpha \leq 1$	$K = \frac{4}{\alpha^2} + 2,07 + 0,67 \alpha^2$	
10		-	$\alpha \geq 4$	$K = 6,97$	
			$4 > \alpha > 1$	$K = 6,97 + \left[\frac{4 - \alpha}{3} \right]^4 3,1$	
			$\alpha \leq 1$	$K = \frac{4}{\alpha^2} + 2,07 + 4 \alpha^2$	
Explanations for boundary conditions :					
----- plate edge free					
----- plate edge simply supported					
———— plate edge clamped					

Table 4.11 Curved plate field $R/t \leq 2500$ (1)







Load case	Aspect ratio b/R	Buckling factor K	Reduction factor κ
1a  with  $p_e = \text{external pressure}$ in $[N/mm^2]$	$\frac{b}{R} \leq 1,63 \sqrt{\frac{R}{t}}$	$K = \frac{b}{\sqrt{R \cdot t}} + 3 \frac{(R \cdot t)^{0,175}}{b^{0,35}}$	$\kappa_x = 1, \quad (2)$ for $\lambda \leq 0,4$ $\kappa_x = 1,274 - 0,686\lambda$ for $0,4 < \lambda \leq 1,2$ $\kappa_x = \frac{0,65}{\lambda^3}$ for $\lambda > 1,2$
1b  $p_e = \text{external pressure}$ in $[N/mm^2]$	$\frac{b}{R} > 1,63 \sqrt{\frac{R}{t}}$	$K = 0,3 \frac{b^2}{R^2} + 2,25 \left(\frac{R^2}{b \cdot t} \right)^2$	$\kappa_x = 1, \quad (2)$ for $\lambda \leq 0,4$ $\kappa_x = 1,274 - 0,686\lambda$ for $0,4 < \lambda \leq 1,2$ $\kappa_x = \frac{0,65}{\lambda^3}$ for $\lambda > 1,2$
2 	$\frac{b}{R} \leq 0,5 \sqrt{\frac{R}{t}}$	$K = 1 + \frac{2}{3} \frac{b^2}{R \cdot t}$	$\kappa_y = 1, \quad (2)$ for $\lambda \leq 0,25$ $\kappa_y = 1,233 - 0,933\lambda$ for $0,25 < \lambda \leq 1$
	$\frac{b}{R} > 0,5 \sqrt{\frac{R}{t}}$	$K = 0,267 \frac{b^2}{R \cdot t} \left[3 - \frac{b}{R} \sqrt{\frac{t}{R}} \right]$ $\geq 0,4 \frac{b^2}{R \cdot t}$	$\kappa_y = 0,3/\lambda^3$ for $1 < \lambda \leq 1,5$ $\kappa_y = 0,2/\lambda^2$ for $\lambda > 1,5$
3 	$\frac{b}{R} \leq \sqrt{\frac{R}{t}}$	$K = \frac{0,6 \cdot b}{\sqrt{R \cdot t}} + \frac{\sqrt{R \cdot t}}{b} - 0,3 \frac{R \cdot t}{b^2}$	as in load case 1a
	$\frac{b}{R} > \sqrt{\frac{R}{t}}$	$K = 0,3 \frac{b^2}{R^2} + 0,291 \left(\frac{R^2}{b \cdot t} \right)^2$	
4 	$\frac{b}{R} \leq 8,7 \sqrt{\frac{R}{t}}$	$K = K_\tau \cdot \sqrt[3]{\frac{R}{t}}$ $K_\tau = \left[28,3 + \frac{0,67 \cdot b^3}{R^{1,5} \cdot t^{1,5}} \right]^{0,5}$	$\kappa_\tau = 1,$ for $\lambda \leq 0,4$ $\kappa_\tau = 1,274 - 0,686\lambda$ for $0,4 < \lambda \leq 1,2$
	$\frac{b}{R} > 8,7 \sqrt{\frac{R}{t}}$	$K_\tau = 0,28 \frac{b^2}{R \cdot t}$	$\kappa_\tau = \frac{0,65}{\lambda^2}$ for $\lambda > 1,2$
Explanations for boundary conditions : - - - - - plate edge free - - - - - plate edge simply supported = = = = = plate edge clamped			
(1) For curved plate fields with a very large radius the κ value need not to be taken less than that one derived for the expanded plane field. (2) For curved single fields. e.g. the bilge strake, which are located within plane partial or total fields, the reduction factor κ may taken as follows: Load case 1 b: $\kappa_p = 0,8/\lambda^2 \leq 1,0$; load case 2: $\kappa_y = 0,65/\lambda^2 \leq 1,0$			

Table 4.12 Geometric properties of typical sections

Section	I_P	I_T	I_ω
Flat bar	$\frac{h_w^3 \cdot t_w}{3 \cdot 10^4}$	$\frac{h_w \cdot t_w^3}{3 \cdot 10^4} \left(1 - 0,63 \frac{t_w}{h_w} \right)$	$\frac{h_w^3 \cdot t_w^3}{36 \cdot 10^6}$
Sections with bulb or flange	$\left(\frac{A_w \cdot h_w^2}{3} + A_f \cdot e_f^2 \right) 10^4$	$\frac{h_w \cdot t_w^3}{3 \cdot 10^4} \left(1 - 0,63 \frac{t_w}{h_w} \right) + \frac{b_f \cdot t_f^3}{3 \cdot 10^4} \left(1 - 0,63 \frac{t_f}{b_f} \right)$	for bulb and angle sections: $\frac{A \cdot e^2 \cdot b^2}{12 \cdot 10^6} \left(\frac{A_f}{A + A_w} + 2,6 \frac{A_w}{A + A_w} \right)$ for tee-sections: $\frac{b_f^3 \cdot t_f \cdot e_f^2}{12 \cdot 10^6}$
Web area $A_w = h_w \cdot t_w$ Flange area $A_f = b_f \cdot t_f$			

2.5 Upon special approval the stiffeners at the knuckles may be omitted if the following condition is complied with:

$$\sigma_a \leq \frac{\sigma_p \cdot b_e}{b_f} \quad [\text{Mpa}]$$

σ_a = actual stress in the face plate at the knuckle $[\text{N/mm}^2]$

σ_p = permissible stress in the face plate $[\text{N/mm}^2]$

b_f = breadth of faceplate $[\text{mm}]$

b_e = effective breadth of faceplate

$$= t_w + n_1 [t_f + c (b - t_f)] \quad [\text{mm}]$$

t_w = web thickness $[\text{mm}]$

t_f = face plate thickness $[\text{mm}]$

$$b = \frac{b_f - t_f}{n_1} \quad [\text{mm}]$$

$$c = \frac{1}{\frac{(b - t_f)^3}{R \cdot t_f} - n_2} + \frac{n_3 \cdot t_f}{\alpha^2 \cdot R}$$

$$C_{\max} = 1$$

$$2\alpha = \text{knuckle angle in } [^\circ], \text{ see Figure 4.10}$$

$$\alpha_{\max} = 45^\circ$$

$$R = \text{radius of rounded face plates } [\text{mm}]$$

$$= t_f \text{ for knuckled face plates}$$

$$n_1 = 1 \quad \text{for unsymmetrical face plates (faceplate at one side only)}$$

$$= 2 \quad \text{for symmetrical face plates}$$

$$n_2 = 0 \quad \text{for face plates with one or two unsupported edges parallel to the web}$$

$$= \frac{(b - t_f)^2}{R \cdot t_f} \leq 1$$

for face plates of multi-web girders

$$n_3 = 3 \quad \text{if no radial stiffener is fitted}$$

$$= 3000 \quad \text{if two or more radial stiffeners are fitted or if one knuckle stiffener is fitted according to Figure 4.10.}$$

$$= \left(\frac{d}{t_f} - 8 \right)^4$$

if one stiffener is fitted according to Figure 4.10

$$3 \leq n_3 \leq 3\,000$$

d = distance of the stiffener from the knuckle [mm]

For proof of fatigue strength of the weld seam in the knuckle, the stress concentration factor K_s (angle 2α according to Figure 4.10 $< 35^\circ$) related to the stress σ_a in the face plate of thickness t_f may be estimated as follows and may be evaluated with case 5 of Table 17.3:




Figure 4.10 Location of stiffeners at knuckles

$$n_4 = 7,143 \quad \text{for} \quad \frac{d}{t_f} > 8$$

$$= \frac{d}{t_f} - 0,51 \sqrt{\frac{d}{t_f}} \quad \text{for} \quad 8 \geq \frac{d}{t_f} > 1,35$$

$$= 0,5 \cdot \frac{d}{t_f} + 0,125 \quad \text{for} \quad 1,35 \geq \frac{d}{t_f} > -0,25$$

Scantlings of stiffeners (guidance):

$$\text{thickness: } t_b = \frac{\sigma_a t_f}{\sigma_p} \cdot 2 \sin \alpha$$

$$\text{height: } h = 1,5 \cdot b$$

2.6 For preventing the face plates from tripping adequately spaced stiffeners or tripping brackets are to be provided. The spacing of these tripping elements shall not exceed $12 \cdot b_f$ arranged alternately on both sides of the web for symmetrical face plates.

2.7 The webs are to be stiffened to prevent buckling.

2.8 The location of lightening holes shall be such that the distance from hole edge to face plate is not less than 0,3 times the web depth.

2.9 In way of high shear stresses lightening holes in the webs are to be avoided as far as possible.

3. Openings in highly loaded structures

3.1 Openings in highly loaded structures should have the shorter dimension transverse to the direction of the main stresses. The corners of the plate have to be rounded-off and avoiding notch effects, grinding will be necessary in most cases.

3.2 Superstructures and deckhouses

Superstructures with longitudinal walls immediately besides the shell are subjected - even for a very restricted length - to the same elongation as the hull. Therefore at the ends of these structures high longitudinal stresses as well as shear stresses are transferred to the longitudinal walls of superstructures and deckhouses. Fatigue strength investigations have to be made and submitted for approval.

4. Structures made of aluminium alloys

Special designs using extruded sections may be approved by **BCS** after detailed examination. Drawings the extruded sections used have to be submitted.

H. Evaluation of Notch Stress

1. Permissible notch stress

The notch stress σ_K roughly calculated for linear-elastic material behaviour at free plate edges, e.g. at

openings in decks, walls, girders etc., should, in general, fulfil the following criterion:

$$\sigma_K \leq f \cdot R_{eH}$$

f	=	1,1	for normal strength hull structural steel
	=	0,9	for higher strength hull structural steel with $R_{eH} = 315 \text{ N/mm}^2$
	=	0,8	for higher strength hull structural steel with $R_{eH} = 355 \text{ N/mm}^2$
	=	0,73	for higher strength hull structural steel with $R_{eH} = 390 \text{ N/mm}^2$

For aluminium alloys the permissible notch stress has to be determined individually concerning the respective alloy.

If plate edges are free of notches and corners are rounded-off, a 20 % higher notch stress σ_K may be permitted.

A further increase of stresses may be permitted on the basis of a fatigue strength analysis as per Section 17.

2. Notch factors to evaluate actual notch stress

2.1 The actual notch stress can be determined by multiplying the nominal stress with the notch factor K_t .

For some types of openings the notch factors are given in Figs. 4.11 and 4.12. An exact evaluation of notch stresses is possible by means of finite element calculations.

Note

These notch factors can only be used for girders with multiple openings if there is no correlation between the different openings regarding deformations and stresses.

3. Openings in decks contributing to longitudinal strength

3.1 All openings in the decks contributing to longitudinal strength must have well rounded corners. Circular openings are to be edge-reinforced. The sectional area of the face bar is not to be less than:

$$A_f = 0,25 \cdot d \cdot t \text{ [cm}^2\text{]}$$

$$d = \text{diameter of openings [cm]}$$

$$t = \text{deck thickness [cm]}$$

The reinforcing face bar may be dispensed with, where the diameter is less than 300 mm and the smallest distance from another opening is not less than 5 x diameter of the smaller opening. The distance between the outer edge of openings for pipes etc. and the ship's side is not to be less than the opening diameter.




Figure 4.11 Notch factor K_t for rounded openings

3.2 The corners of the opening are to be surrounded by strengthened plates which are to extend over at least one frame spacing fore-and-aft and athwart-ships. Within 0,5 L amidships, the thickness of the strengthened plate is to be equal to the deck thickness abreast the opening plus the deck thickness

between the openings. Outside 0,5 L amidships the thickness of the strengthened plate need not exceed 1,6 times the thickness of the deck plating abreast the opening.

3.3 The hatchway corner radius is not to be less than:

$$r = n \cdot b \cdot \left(1 - \frac{b}{B} \right)$$

$$r_{\min} = 0,1m$$

$$n = \frac{\ell}{200}$$

$$n_{\min} = 0,1$$

$$n_{\max} = 0,25$$

$$\ell = \text{length of opening [m]}$$

$$b = \text{breadth [m], of the opening or total breadth of openings in case of more than one. } b/B \text{ need not to be taken smaller than } 0,4$$

3.4 Where the hatchway corners are elliptic or parabolic, strengthening according to 3.2 is not required. The dimensions of the elliptical and parabolic corners shall be as shown in Figure 4.13.

Where smaller values are taken for a and c, reinforced insert plates are required which will be considered in each individual case.

3.5 For ships with very large deck openings the design of the corner of the openings has to be specially considered on the basis of the stresses due to longitudinal hull girder bending, torsion and transverse loads by direct calculations.

4. An exact distribution of notch stresses can be evaluated by means of finite element calculations.

For fatigue investigations the stress increase due to geometry of cut-outs has to be considered, see Table 17.3.




Figure 4.12 Notch factor K_t for rectangular openings with rounded corners at uniaxial state of stresses (above) and at biaxial-state of stresses (below)




Figure 4.13 Design of elliptical or parabolic corners

SECTION 5

DESIGN LOADS

	Page
A. General, Definitions.....	5-2
1. Scope	
2. Load plan	
3. Definitions	
B. Design Values of Acceleration Components	5-3
C. External Sea Loads	5-4
3. Design loads on bilge keels and sonar domes	
4. Loads on propulsion and manoeuvring devices	
D. Loads on Watertight and Non-Watertight Partitions	5-7
1. Watertight partitions	
2. Non-watertight partitions	
E. Loads on Decks	5-7
1. Uniformly distributed loads	
2. Single point loads	
F. Loads on Tank Structures	5-9
1. Design pressure p_{T1}	
2. Maximum static design pressure p_{T2}	
3. Design pressure for filled spaces p_{T3}	
4. Ballast tank operations	
5. Tanks for replenishment at sea operations	
G. Loads due to military equipment.....	5-10
1. Loads on the hull structure introduced by weapons and sensors	
2. Loads due to explosions	
3. Loads due to aircraft operations	
4. Loads caused by replenishment at sea (RAS)	
5. Loads from beach landing operations	
H. Deadweight of Structures	5-13
I. Wind Loads	5-13
1. General	
2. Wind force	

A. General, Definitions

$$= 10,75 \cdot C_{RW} \text{ for } L > 300 \text{ m}$$

1. Scope

This Section provides specifications for design loads to determine scantlings of hull structural elements. These design loads may be obtained from design formulas given in other Sections or from direct calculations. The dynamic portions of these design loads may be applied only within the design concept of this Chapter.

In addition to environmental loads and loads from normal ship operation, military loads are defined. Basic load values for military loads are given in G. For military loads, the Naval Authority must supply the necessary details to the shipyard and the subcontractors.

2. Load plan

2.1 All loads significant for design of the hull structure shall be incorporated into a load plan. This should be done in a clearly arranged form. For conversions of naval ships, a plan showing the differing new loads shall be submitted.

2.2 The load plan shall at least contain the following information:

- Principle dimensions of the ship
- Dynamic loads p_s on sea and weather exposed structures
- Accelerations
- Data of tanks
- Static deck loads, such as uniform distributed loads, point loads, etc.

3. Definitions

C_0 = wave coefficient

$$= \left(\frac{L}{25} + 4,1 \right) \cdot C_{RW} \text{ for } L < 90 \text{ m}$$

$$= \left(10,75 - \left(\frac{300 - L}{100} \right)^{1,5} \right) \cdot C_{RW}$$

for $90 \leq L \leq 300 \text{ m}$

C_v = Velocity coefficient

$$= \sqrt[3]{\frac{V_0}{1,6 \sqrt{L}}} \geq 1 \text{ and } 1,6 \cdot \sqrt{L} \geq 14$$

C_{RW} = Service range coefficient

C_{RW} = 1,0 for unlimited service range
 = 0,90 for restricted service area **Y**
 = 0,75 for restricted service area **K50**
 = 0,66 for restricted service area **K20**
 = 0,60 for restricted service area **K6**

for restricted service to be determined on a case by case basis, see also Chapter 101 - Classification and Surveys (Naval Ship Technology), Section 2, C.

C_α = flare factor

$$= \frac{0,4}{1,2 - 1,09 \cdot \sin \alpha} \text{ in general}$$

$\geq 1,0$ for bow doors and stem structures

= 0 for decks and walls

α = Flare angle [°], see Fig. 5.2

g = Acceleration of gravity

$$= 9,81 \text{ m/s}^2$$

p = Total lateral design pressure [kN/m²]

$$= \gamma_{fstat} \cdot p_{stat} + \gamma_{fdyn} \cdot p_{dyn}$$

p_{stat} = Static lateral pressure [kN/m²]

p_{dyn} = Dynamic lateral pressure [kN/m²]

γ_{fstat} = Partial safety factor for static load components, see Section 4, Table 4.1

γ_{fdyn} = Partial safety factor for dynamic load components, see Section 4, Table 4.1

p_{BK} = Pressure on bilge keel [kN/m²] according to C.3. (LCA)

p_{dw} = Deadweight load of the structures [kN/m²] according to H. (LCB)

p_{sL} = Design impact pressure [kN/m²] on the ship's shell forward of $x/L = 0,6$ according to C.2. (LCA)

P_E = Single point load [kN] according to E.2. (LCA) or G.3.2 (LCA)

p_L = Load on internal decks [kN/m²] according to E.1 (LCA)

P_{NT} = Static load on non-watertight partitions [kN/m²] according to D.2. (LCA)

p_s = Design pressure [kN/m²] sea and/or weather exposed structures according to C.1. (LCA)

p_{T1} = Design pressure for tanks [kN/m²] according to F.1. (LCA)

p_{T2} = Design pressure for tanks [kN/m²] according to F.2. (LCB)

p_{T3} = Design load [kN/m²] ammunition rooms and chain locker according to F.3. (LCB)

p_w = Design wind pressure [kN/m²] according to I. (LCA)

p_{wT} = Design load on watertight partitions [kN/m²] according to D.1. (LCB)

ρ = Density of liquid [t/m³]

B. Design Values of Acceleration Components

The following formulas may be taken for guidance to calculate acceleration components a_x , a_y and a_z owing to ship motions. These acceleration components are maximum dimensionless accelerations (i.e., relative to the acceleration of gravity) in the respective x-, y- and z-directions and account for the following motion components:

Vertical acceleration (perpendicular to the base line) due to heave and pitch motions:

$$a_z = a_0 \cdot k_v \cdot f_Q$$

Transverse acceleration due to sway, yaw and roll motions, including the gravity component of roll as maximum value of a_{y1} and a_{y2} but is not to be taken less than 0,5 g :

$$a_{y1} = 0,35 (1 + k_v \cdot a_0) f_Q$$

$$a_{y2} = c_0 \frac{z}{B^2} f_Q$$

Longitudinal acceleration due to surge and pitch motions, including the gravity component of pitch:

$$a_x = 5,8 \cdot a_0 \frac{z}{L} f_Q \quad \text{but not less than } 0,3 f_Q$$

a_x , a_y , a_z are considered as acting separately for calculation purposes in both direction, each.

$$a_0 = \frac{c_0 \cdot c_B}{L^2} (0,6 \cdot v_0 + 2,3 \cdot \sqrt{L})^2$$

k_v = distribution factor, see also Figure 5.1.

$$= 1,8 - (8x/3L) \quad \text{for } x/L < 0,3$$

$$= 1,0 \quad \text{for } 0,3 \leq x/L \leq 0,6$$

$$= 5,5 (x/L) - 2,3 \quad \text{for } x/L > 0,6$$




Figure 5.1 Distribution factor k_v

f_Q = probability factor according to Section 4, A.2.

Q = 10^{-8} for fixed elements such as pillars, etc.

= 10^{-7} for lattice masts

= 10^{-6} for bulkheads, masts

= 10^{-5} for military cargo, loose equipment,
content of tanks, deck loads, etc.

In special cases, it is recommended to determine the accelerations by direct calculation.

p_{Smin} = 4,0 kN/m² for weather decks in general and unprotected front walls

p_{Smin} = 2,5 kN/m² for observation decks

p_{Smin} = 3,0 kN/m² for walls, except unprotected front walls

p_0 = Basic external dynamic load

$$p_0 = 5,0 \cdot \sqrt{C_B} \cdot c_0 \cdot c_v \cdot f_Q \left[\frac{m^2}{s^2} \right] \text{ kN / m}$$

f_Q = Probability factor according to section 4, A.2.

Q = 10^{-8} in general and for pillars

= 10^{-7} for stiffener

= 10^{-6} for girder

c_F = Distribution factor according to Table 5.1

Coefficients n_1 , n_2 and n_3 for different elements of the ship's surface are defined in Table 5.2.

The definitions for the different parts of the ship exposed to sea loads are given in Figure 5.2.

For the definition of load centre see Section 4, B.2.1.

2. The design impact pressure on the ship's shell forward of $x/L = 0,6$ is to be determined according to the following formula:

$$p_{SL} = C_A \cdot c_\alpha \cdot c_{SL} \cdot (0,2 \cdot v_0 + 0,6 \cdot \sqrt{L})^2 \left[\frac{m^2}{s^2} \right] \text{ kN/m}^2$$

$$C_A = 1 + (5/A) \quad C_{Amax} = 2,0$$

A = loaded area [m²] between the supports of the structure considered

c_{SL} = distribution factor, see also Fig. 5.3

$$c_{SL} = 4 \cdot \left(\frac{x}{L} - 0,6 \right) \text{ for } 0,6 \leq \frac{x}{L} < 0,85$$

$$c_{SL} = 1,0 \text{ for } \frac{x}{L} \geq 0,85$$

C. External Sea Loads

1. The external total design load p_s at the load centre is defined as follows:

$$p_s = \gamma_{stat} p_{Sstat} + \gamma_{dyn} p_{Sdyn} \quad [\text{kN/m}^2]$$

p_{Sstat} = Static pressure [kN/m²]

$$= 10 \cdot (1,4 \cdot T - z) \quad \text{for } z < T$$

$$= 0 \quad \text{for } z \geq T$$

p_{Sdyn} = Dynamic pressure [kN/m²]:

For $z < T$:

$$p_{Sdyn} = p_0 \cdot c_F \cdot \left[1 + \left(\frac{z}{T} \right)^{0,75} \right]$$

For $z \geq T$:

$$p_{Sdyn} = p_0 \cdot c_F \cdot \left[0,25 + \frac{1,75}{1 + \frac{z-T}{c_0}} \right] \cdot n_1 \cdot n_2 \cdot n_3$$

$$\geq p_{smin}$$





Figure 5.2 Definition of different parts of the ship's surface exposed to the sea

For the design of the shell structure, p_{SL} shall not be less than p_s according to 1. The partial safety factor for the local dynamic pressure γ_{dyn} may be taken as 1.0.




Figure 5.3 Distribution factor C_{SL}

3. Design loads on bilge keels and sonar domes

3.1 Loads on bilge keels

For ships with length L between 50 m and 200 m, the design load p_{BK} acting on the bilge keel (Fig. 5.4) located between $0,4 L$ and $0,6 L$ can be calculated as follows:

The partial safety factor for the local dynamic pressure γ_{dyn} is to be set to 1,85. For ship lengths below 50 m and above 200 m, the loads on bilge keels have to be specially considered.

$$p_{\text{BKdyn}} = \frac{52000 \cdot \rho}{(L + 240)^{1,1}} \left[\text{kN/m}^2 \right]$$

$$p_{\text{BK}} = p_{\text{BKdyn}} \cdot \gamma_{\text{dyn}} \left[\text{kN/m}^2 \right]$$

Table 5.1 Distribution factor c_F , height factor c_z and factor n_4

Region	Factor c_F	Factor c_z	Factor n_4
$0 \leq \frac{x}{L} < 0,25$	$1 + \frac{6 + c_\alpha^2}{1 + 3 C_B} \cdot \left(0,25 - \frac{x}{L} \right) - c_z \geq 1$	$\frac{z - T}{c_0} - 0,5 \geq 0$	$0,75 + \frac{x}{L}$
$0,25 \leq \frac{x}{L} < 0,7$	1,0	-	1,0
$0,7 \leq \frac{x}{L} \leq 0,9$	$1 + \frac{20 + (c_\alpha + c_v)^2 \cdot \left(\frac{x}{L} - 0,7 \right)^2}{C_B} - c_z \geq 1$	$\frac{z - T}{c_0} - 1,0 \geq 0$	$3,94 - 4,2 \cdot \frac{x}{L}$
$0,9 < \frac{x}{L} < 1,0$	$1 + \frac{1}{25 C_B} \cdot (20 + (c_\alpha + c_v)^2) - c_z \geq 1$		

Table 5.2 Definition of n_1 , n_2 and n_3

Surface element	Factor n ₁	Factor n ₂	Factor n ₃
Shell	1,0	1,0	1,0
Weather decks	0,25	1,0	1,0
Unprotected front walls	$0,25 \leq 1,0 - \frac{n(z - T - 0,02 L - 0,5)}{c_0} \leq 1,0$	$0,3 + 0,7 \frac{b'}{B'}$	$2 + \frac{T - z + h_N}{0,02L + 1} \geq 1$
Protected front walls and side walls			1
Aft end walls			$1 - \left(\frac{x}{L} \right)^2 \geq 0,6$

n₄ see Table 5.1

h_N = 0,8 + 0,01 L ≤ 2,3

b' = breadth of superstructure or deckhouse at position considered

B' = actual maximum breadth of ship on the exposed weather deck at position considered




Figure 5.4 Design load p_{BK} at bilge keel

3.2 Load on sonar domes

The loads on a sonar dome in the forward bottom area of a ship have to be determined by combining the following load components:

- Static load on the ship's bottom according to 1.
- Impact pressure according to 2.
- Internal static pressure from water filling the sonar dome
- Internal dynamic pressure (static pressure multiplied with the vertical acceleration component)
- Hydrodynamic pressure at maximum ahead speed v_{max} and in the turning manoeuvre respectively to be obtained from calculations or model tank tests.

4. Loads on propulsion and manoeuvring devices

In addition to requirements for propeller brackets, rudders and manoeuvring devices as documented in the relevant Sections, it must be proven that these parts are able to withstand the shock loads defined by the Naval Authority.

D. Loads on Watertight and Non-Watertight Partitions

1. Watertight partitions

The total design load for watertight bulkheads is:

$$p_{WT} = p_{WTstat} \cdot \gamma_{fstat} + p_{WTdyn} \cdot \gamma_{fdyn} \text{ [kN/m}^2\text{]}$$

$$p_{WTstat} = g \cdot \rho \cdot (T_{dam} - z) \text{ [kN/m}^2\text{]}$$

$$p_{WTdyn} = g \cdot \rho \text{ [kN/m}^2\text{]}$$

T_{dam} = Draught for the extreme damage waterline above base line [m].

For ships without proven damage stability, the height of the bulkhead deck above baseline has to be used.

For the collision bulkhead, the distance of the upper edge of the collision bulkhead at the ship's side to the base line has to be used.

z = distance from the load centre of the structure to the base line [m]

For the definition of load centre see Section 4, B.2.1.

2. Non-watertight partitions

The static load P_{NT} is to be defined by the Naval Authority or the Shipyard, but shall not be less than:

$$P_{NT} = p_{NTstat} \cdot \gamma_{fstat} \text{ [kN/m}^2\text{]}$$

$$P_{NWTstat} = 2 \text{ kN/m}^2$$

3. Additional loads

In addition, static and dynamic loads from equipment mounted on bulkheads and walls have to be considered.

E. Loads on Decks

The load on weather decks is calculated at the minimum height z of the deck according to C.1.

Where additional loads, such as vehicles, helicopters, mines, general stowage, etc. are intended to be carried on the weather deck, the relevant combination of these loads as defined below is to be determined.

The following uniformly distributed loads are minimum values. Intended distributed and single point deck loads are to be defined in the load plan.

1. Uniformly distributed loads

The total design load for decks consists of static and dynamic components.

$$P_L = p_{Lstat} \cdot \gamma_{fstat} + p_{Ldyn} \cdot \gamma_{fdyn} \text{ [kN/m}^2\text{]}$$

$$p_{Lstat} = \text{static service load} \quad \text{[kN/m}^2\text{]}$$

$$\geq 3,5 \text{ [kN/m}^2\text{]} \text{ in general}$$

$$= 8,0 \text{ [kN/m}^2\text{]} \quad \text{for platforms of machinery decks}$$

$$= 6,0 \text{ [kN/m}^2\text{]} \text{ for platforms of mooring decks}$$

$$= 7 \cdot h \quad \text{for tween decks}$$

but not less than 15 kN/m² in general
if no specific load of equipment or provision, etc. is given.

$$h = \text{Mean height of internal deck [m]}$$

$$p_{Ldyn} = \text{Dynamic load component [kN/m}^2\text{]}$$

$$= p_{Lstat} \cdot a_z$$

$$a_z = \text{Acceleration component in z-direction in } g, \text{ according to B.}$$

2. Single point loads

2.1 General

The deck loads due to pallets, mines, etc. is to be determined as a uniformly distributed load.

For containers p_{Estat} [kN] is to be taken as one-fourth of their total weight.

The total load consists of static and dynamic components.

$$P_E = \gamma_{fstat} P_{Estat} + \gamma_{fdyn} P_{Edyn} \quad \text{[kN]}$$

$$P_{Estat} = \text{static load [kN]}$$

$$P_{Edyn} = \text{dynamic load component [kN]}$$

$$= P_{Estat} \cdot a_z$$

$$a_z = \text{acceleration component in z-direction in } g \text{ according to B.}$$

2.2 Wheel loads

The maximum pressure is equivalent to the internal air pressure in the tyres. Axle and wheel spacing and tyre print dimensions have to be taken into account at all traffic lanes.

$$p_{Estat} = \frac{Q}{n} \text{ [kN]}$$

$$Q = \text{Axle load of a vehicle [kN] for } Q \text{ total weight of a fork lift truck to be taken}$$

$$n = \text{Number of wheels or twin wheels per axle}$$

The wheel print area f can be estimated as follows:

$$f = 100 P_{Estat} / p \text{ [cm}^2\text{]}$$

$$p = \text{Specific wheel resp. tyre pressure [bar]. If no special information is available, the values defined in Table 5.3 may be used.}$$

In case of narrowly spaced wheels these may be grouped together to one wheel print area.

2.3 Armoured tracked vehicles

For armoured, tracked vehicles, Q is the half weight of the vehicle. The "wheel print" is given by the length and width of the chains touching the deck and has to be defined by the Naval Authority. The load can be assumed as uniformly distributed on this area. The ranges of total weight and specific pressure are defined in Table 5.4. Special attention is to be paid to the upper edge of internal ramps because, as the vehicle passes this edge, its total weight will be concentrated on this edge.

Table 5.3 Specific wheel pressures for different kinds of vehicles

Kind of vehicle	Specific wheel pressure [bar]	
	Pneumatic tyres	Solid rubber tyres
Personnel carrier	2	-
Trucks	8	-
Trailers	8	15
Fork lift trucks	6	15

Table 5.4 Total weight and specific pressure of armoured, tracked vehicles

Kind of armoured, tracked vehicle / tank	Range of total weight [kN]	Specific track pressure [kN/m ²]
Armoured personnel carriers	150-250	65
Light tanks	300-450	80
Armoured howitzers	250-400	90
Battle tanks	450-700	90

F. Loads on Tank Structures

1. Design pressure p_{T1}

The total design pressure p_{T1} consists of static and dynamic components :

$$p_{T1} = p_{T1stat} \cdot \gamma_{fstat} + p_{T1dyn} \cdot \gamma_{fdyn} \text{ [kN/m}^2\text{]}$$

1.1 Static pressure

The static pressure is in upright condition :

$$p_{T1stat} = g \cdot h_1 \cdot \rho + 100 \cdot \Delta p \text{ [kN/m}^2\text{]}$$

in heeled condition :

$$p_{T1stat} = g \cdot h_1 \cdot \rho \cdot \cos \varphi + 100 \cdot \Delta p \text{ [kN/m}^2\text{]}$$

h_1 = Distance of load centre from tank top [m]

ρ = Density of tank liquid [t/m³]

$$\geq 1,025 \text{ t/m}^3$$

φ = Design heeling angle [°] for tanks

$$= \text{Arctan} (f_{bk} \cdot H/B) \text{ in general}$$

f_{bk} = 0,5 for ships with bilge keel

$$= 0,6 \text{ for ships without bilge keel}$$

$$= P_v/100 \text{ (for } P_v \text{ See Part A, Chapter 1, Section 5, A.2.3)}$$

Δp = Additional pressure component created by overflow systems, replenishment at sea (see 5.), etc. [bar]

For fuel tanks and ballast tanks connected to an overflow system, the dynamic pressure increases due to overflowing and has to be taken into account in addition to the static pressure. The static pressure corresponds to a pressure height extending up to the highest point of the overflow system ; see also **BCS** Rules - Guidelines Construction , Fitting Equipment and Testing of Fuel Overflow Systems.

For the definition of load centre see Section 4, B.2.1.

1.2 Dynamic pressure

The dynamic pressure in upright condition is:

$$p_{T1dyn} = g \cdot h_1 \cdot \rho \cdot a_z \text{ [kN/m}^2\text{]}$$

in heeled condition :

$$p_{T1dyn} = \rho \cdot g (0,3 \cdot b + y) \sin \varphi$$

a_z = Vertical acceleration component according to B.

b = Upper breadth of tank [m].

y = Distance of load center from the vertical longitudinal central plane of tank [m].

2. Maximum static design pressure p_{T2}

The maximum static design pressure at load centre may be taken as:

$$p_{T2} = \gamma_{fstat} \rho g (h_1 + h_2) \text{ [kN/m}^2\text{]}$$

h_1 = distance [m] of load centre to tank top

h_2 = distance [m] from tank top to top of overflow acc. to Section 19, F.

= not less than 2,5 m or $10 \cdot \Delta p$

3. Design pressure for filled spaces p_{T3}

The total design load for filled spaces of moderate size is:

$$p_{T3} = \gamma_{fstat} p_{T3stat} + \gamma_{fdyn} p_{T3dyn} \text{ [kN/m}^2\text{]}$$

$$p_{T3stat} = \rho g h_3 \text{ [kN/m}^2\text{]}$$

$$p_{T3dyn} = p_{T3stat} a_z \text{ [kN/m}^2\text{]}$$

h_3 = distance [m] of the load centre from top, i.e. ceiling of ammunition room or top of chain locker pipe etc.

These formulas are also to be applied to ammunition rooms which are finally flooded because of fire protection.

4. Ballast tank operations

Ballast tank operations for Dock Landing Ships (LHD and LSD) and Landing Ships (LST) have to be specially considered on the basis of the requirements when launching and berthing of landing craft or when beaching, see Section 22.

5. Tanks for replenishment at sea operations

For tanks to be used for replenishment at sea (RAS) operations, the surge pressures of the transferred liquid have to be considered.

Note

To increase safety during RAS operations, it is recommended to electronically monitor the supply procedure and the tank pressure because, normally, the structural strength of the tank is the weakest element in the safety chain.

G. Loads due to military equipment

1. Loads on the hull structure introduced by weapons and sensors

These loads and the relevant acceptance criteria, such as permissible deflections, vibration levels, etc., are to be defined by the Naval Authority or the Shipyard and have to be specified in a load plan.

2. Loads due to explosions

The loads due to internal and external explosions above and below the water surface as well as the relevant acceptance criteria are to be provided by the Naval Authority and have to be specified in a load plan. Reference is also made to Section 16 and 21,A.4.

3. Loads due to aircraft operations

3.1 Fixed wing aircraft

3.1.1 For the operation of fixed wing aircraft, the following areas on the deck have to be distinguished and clearly marked for their application:

- Landing area:
an area on the weather deck or a specially designed platform. It may be equipped with arresting gear for landing aircraft, creating special point loads on starboard and port side of the landing strip.
- Take-off area:
the forces introduced by starting catapults as well as the structure of a ramp to assist take off are to be specially considered. Thermal loads caused by jet blast must be observed.

- Parking areas:
on the sides of the landing / take-off deck or
in a special hangar deck

3.1.2 In parking areas of the aircraft, the load is to be calculated for the following conditions:

- Maximum take-off weight of the aircraft
- Acceleration factors a_x , a_y , a_z according to B.
- Arrangement of lash-down system, including pre-stresses, if applicable

3.1.3 To determine the imposed loads on the different deck areas in more detail, the following information is needed from the Naval Authority:

- Number and kinds of aircraft to be operated
- Weight, weight distribution and wheel configuration
- Landing speeds and dynamic factors, landing equipment foreseen
- Starting equipment and procedure

3.2 Helicopters and drones

For the design of landing, parking and hangar decks suitable for helicopter/drone operation, the structure has to be investigated under the most unfavourable parking position of any kind and type of helicopter. For the parking positions, the actual lashing system of the helicopters is to be considered.

For scantling purposes, other loads (cargo, snow/ice, etc.) are to be considered simultaneously or separately, depending on the conditions of operation to be expected.

If detailed information on helicopters is not available, loads given in 3.2.1 to 3.2.3 may be used as a basis.

3.2.1 Wheel or skid load

3.2.1.1 At any parking position:

The total wheel or skid load consists of static and dynamic components.

$$P_E = P_{Estat} \cdot \gamma_{fstat} + P_{Edyn} \cdot \gamma_{fdyn} \text{ [kN]}$$

P_{Estat} = Wheel or skid load according to the construction of the heaviest kind of helicopter to be used on board, see Fig. 5.5. This load is evenly distributed over the contact area

$f = 0,3 \cdot 0,3 \text{ m}^2$ for a single wheel, or it is specified according to data supplied by helicopter manufacturers. For dual wheels or skids, this load is to be determined individually in accordance with given dimensions.

$$= 0,5 G \text{ [kN]}$$

$$P_{Edyn} = P_{Estat} a_z \text{ [kN]}$$

G = Maximum take-off weight [kN] of the helicopter, including deadweight, crew, fuel, cargo, weapons, etc.

a_z = Vertical acceleration factor according to B.

e = Wheel or skid distance according to the kinds of helicopters to be operated, see Fig. 5.5




Fig. 5.5 Distribution of static wheel loads

3.2.1.2 Total load for normal landing:

The landing impact for one wheel or skid according to Fig. 5.5 at any landing position is:

$$P_E = 2,0 P_{Estat} \text{ [kN]}$$

3.2.1.3 Emergency and crash landing:

If in addition emergency and crash landing situations have to be considered, the loads and partial safety factors for local static and dynamic loads have to be agreed with Naval Authority and **BCS**.

3.2.2 Uniform loads on flight or hangar deck

The following uniformly distributed are minimum values. These loads may be higher, depending on the definitions in the load plan.

The total design load consists of static and dynamic components.

$$p_L = \gamma_{\text{stat}} p_{L\text{stat}} + \gamma_{\text{dyn}} p_{L\text{dyn}} \text{ [kN/m}^2\text{]}$$

$$p_{L\text{stat}} = 2,0 \text{ kN/m}^2 \text{ for flight deck}$$

$$= 3,0 \text{ kN/m}^2 \text{ for hangar deck}$$

$$p_{L\text{dyn}} = p_{L\text{stat}} \cdot \alpha_z \text{ [kN/m}^2\text{]}$$

3.2.3 Tie down forces

The tie down system or the helicopter handling system cause additional tie down forces to act on the helicopter deck. The following forces have to be considered:

- Horizontal acceleration forces of the helicopter at take-off weight G based on the acceleration components a_x and a_y , see B.
- Prestress forces if a tie down system is used
- Components from wind forces on the helicopter, if lashed on deck (outside the hangar), for a wind speed $v_w = 50 \text{ m/s}$, see I.2.

Note :

If no other information is available, the following loads may be assumed for lashing of helicopters in hangars:

- fastening pots in the deck: 35 kN
- lashing to walls: 15 kN

4. Loads caused by replenishment at sea (RAS)

4.1 Replenishment at sea using transverse board to board procedures

4.1.1 A system for replenishment at sea between two naval ships, in general, serves the following logistic purposes:

- Exchange of personnel (normally one person at a time)
- Transport of provisions (often on pallets weighing between 1 and 2 tons maximum)
- Pumping of liquids, mostly fuel, lubrication oils and freshwater, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 4

Weights of loads and volumes of liquids to be transferred, sea states while replenishing, as well as maximum distances between the ships have to be defined by the Naval Authority.

4.1.2 The special twin-cable rope arrangement between the two ships causes two main reaction forces to act on both ships:

- The force of the support line that carries the loads. This force is governed by the weight of the load being transferred. (The weight is a force acting vertically downward.)
- The force of the hauling rope that pulls the pallet carrying the goods being transferred or the force of fasteners for the hose connection between the ships. (This force acts mainly in the horizontal direction.)

Generally, the cable arrangement will have a force diversion point at the masts, or special rigging is provided to distribute cable loads. When the replenishment system is not used, the appropriate cables will be stored on rope drums onboard, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 4.

4.1.3 For calculation of rigging reaction forces at cable tie-downs and foundations, ship motions and the corresponding transverse acceleration (see B.) as well as a ship heeling angle of $\pm 5^\circ$ have to be taken into account.

4.2 Replenishment at sea using stern / bow procedures

4.2.1 This kind of replenishment method, suitable only for the transfer of liquids, consists of floating hoses

equipped with quick-closing couplings supported by a bridle. An accompanying safety rope connection, extending from the stern of the supplying ship, must be provided. Equipment may be taken onboard the receiving ship from a ship's side near the bow or the stern, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 4.

4.2.2 In general, the floating hoses between the two ships form a loop, thereby avoiding the formation of direct reaction forces and compensating for temporary speed differences between the two ships. Details on volumes to be transferred, lengths of hose connections, and maximum speed of the two ships during replenishment operations have to be provided by the Naval Authority and serve as a basis for calculating hose resistance forces that affect ship operations.

Note:

Approximate values of loads from hoses depend on the nominal diameter of the hoses and are defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 4, D.3.

5. Loads from beach landing operations

For naval landing ships, additional loads caused by contact of the ship's bottom with the landing beach must be expected to occur over about 30 - 50 percent of the forward bottom area. Therefore, additional load cases have to be considered for the global longitudinal strength analysis as well as for the local strength analysis. The operational requirements have to be defined by the Naval Authority.

H. Deadweight of Structures

The deadweight of the structures may be considered as a distributed load. The total load consists of static and dynamic components.

$$p_{DW} = p_{DWstat} \cdot \gamma_{fstat} + p_{DWdyn} \cdot \gamma_{fdyn} \text{ [kN/m}^2\text{]}$$

$$p_{DWstat} = G_{DW} \cdot g \text{ [kN/m}^2\text{]}$$

$$p_{DWdyn} = p_{DWstat} \cdot a \text{ [kN/m}^2\text{]}$$

$$G_{DW} = \text{Deadweight per element area [t/m}^2\text{]}$$

$$a = \text{Acceleration components } a_x, a_y \text{ or } a_z \text{ of the acceleration according to B.}$$

Note

In general, for usual structural elements the deadweight of the structure is considered within the given design loads, e.g., for shell structures and decks.

I. Wind Loads

1. General

Wind loads are to be considered for strength analysis of extremely exposed parts of the ship, such as masts, as well as for the stability of the ship and for flight operations, etc.

Maximum wind speeds, air density, etc. have to be agreed on with the Naval Authority according to the area of operation of the naval ship. In the following Sections standard values are provided.

2. Wind force

$$F_w = q_w \cdot C_f \cdot A_w \cdot \gamma_{fdyn} \text{ [kN]}$$

$$q_w = \text{Wind pressure}$$

$$= 0,5 \cdot \rho_L \cdot v_w^2 \text{ [kN/m}^2\text{]}$$

$$\rho_L = \text{Density of air [t/m}^3\text{]}$$

$$= 1,4 \cdot 10^{-3} \text{ t/m}^3 \text{ as guidance value for standard requirements.}$$

$$v_w = \text{Wind speed [m/s], see Section 1, Table 1.2 (in general, systems out of operation)}$$

$$C_f = \text{Form coefficient}$$

$$A_w = \text{Projected area exposed to wind forces [m}^2\text{]}$$

Note:

For plane areas the form coefficient may be assumed to be $c_f = 1,0$; for rounded areas, the coefficient may be assumed to be $c_f = 0,6$.

The water content in the air may increase the air density ρ_L by about 30 percent.

SECTION 6**LONGITUDINAL STRENGTH**

	Page
A. General	6-2
1. Scope	
2. Sign convention	
3. Definitions	
B. Definition of Load Cases.....	6-4
2. Intact condition	
3. Damaged condition	
4. Residual strength condition	
C. Hull Girder Loads	6-4
1. Still water bending moments and shear forces	
2. Wave induced loads	
D. Structural Resistance.....	6-9
1. General	
2. Structural design	
3. Ultimate load calculation of the ship's transverse sections	
4. Hull girder stresses	
5. Deflection criterion	

A. General

- A longitudinal centre of gravity aft of 0,45 L

1. Scope

- $CB > 0,6$,

1.1 The envelope of minimum and maximum values of the still water bending moments and still water shear forces according to C.1. for the envisaged loading and ballast conditions are to be calculated.

BCS may require determination of vertical wave

1.2 In general for ships of usual monohull form the wave induced bending moments and shear forces specified under C.2.2 are accepted.

2. Sign convention

Following conditions are to be considered for wave induced design loads:

The sign convention shown in Figure 6.1 is to be observed for the longitudinal distribution of weight and buoyancy and for the resulting global loads in calm water and in waves. Positive directions of forces and moments are defined as follows:

- Intact condition
- Damaged condition, if applicable, according to B.3.
- Residual strength condition, if applicable, according to B.4.

- Weight: positive
- Buoyancy: negative
- Vertical shear forces Q_z : positive in direction of positive z-axis at the front section, positive in direction of the negative z-axis at the rear section
- Horizontal shear forces Q_y : positive in direction of positive y-axis at the front section, positive in direction of the negative y-axis at the rear section
- Normal forces F_x : positive in direction of the positive x-axis at the front section, positive in direction of the negative x-axis at the rear section
- Vertical moments M_y : positive if tension in deck is created
- Horizontal moments M_z : positive if tension on starboard is created

The partial safety factors according to Table 6.1 may be used for the ultimate strength calculation acc. to D.3.:

Table 6.1 Partial safety factors

Condition	Intact		Damaged	
	Direct calc.	Acc. to C.2.2	Direct calc.	Acc. to C.2.2
Wave induced loads determined by	acc. to C.2.1		acc. to C.2.1	
γ_{fstat}	1,05	1,05	1,05	1,05
γ_{fdyn}	1,1	1,25	1,05	1,15
γ_m	1,15	1,15	1,1	1,1

1.3 For ships of unusual monohull shape and design i.e. for ships with:

- Extreme bow flare

- Torsional moments M_x : positive in clockwise direction around the positive x-axis at the front section, positive in counter clockwise direction at the rear section

3. Definitions

M_{SW} = Vertical still water bending moments [MNm] (maximum and minimum value).

M_{SWf} = Vertical still water bending moments [MNm] in damaged condition.

M_{WH} = Horizontal wave bending moments [MNm] .

M_{WT} = Torsional wave bending moments [MNm]

M_{WV} = Vertical wave bending moments [MNm]

M_{WVf} = Vertical wave bending moments in damaged condition [MNm]

= M_{WV} for $c_v = 1$

M_U = Ultimate vertical bending moments of the ship's transverse section in the hogging ($M_{U,H}$) and sagging ($M_{U,S}$) conditions [MNm].

Q_{SW} = Vertical still water shear force [MN].

Q_{SWf} = Vertical still water shear force in damaged condition [MN].

Q_{WH} = Horizontal wave shear force [MN].

Q_{WV} = Vertical wave shear force [MN].

Q_{WVf} = Vertical wave shear force [MN] in damaged condition

= Q_{WV} for $c_v = 1$

Q_U = Ultimate vertical shear force of the ship's transverse section [MN]

C_0 = Wave coefficient according to Section 5, A.3.

c_v = Velocity coefficient according to Section 5, A.3.

$\gamma_m, \gamma_{fstat}, \gamma_{dyn}$ see Section 4, Table 4.1




Figure 6.1 Sign convention

B. Definition of Load Cases

1. For all load cases selected in accordance with the stability requirements described in Section 2 the longitudinal strength of the hull girder has to be proven.

2. Intact condition

2.1 Section 2, B.2 defines a series of load cases for stability considerations of the undamaged ship. The most critical of these cases form the basis for the longitudinal strength calculations.

2.2 The final choice of load cases and weight distributions to be considered for calculations - especially for unusual kinds of naval ships - is to be agreed on between Naval Authority, shipyard and **BCS**.

3. Damaged condition

If the symbol **FS** is assigned according to Section 2, C., longitudinal strength of the damaged ship and of the flooded ship is to be investigated. For these cases it is to be understood that the hull girder strength of the damaged ship is not significantly reduced.

4. Residual strength condition

For ships assigned with Class Notation **RSM** according to Section 21, loads are to be considered according to 3.

C. Hull Girder Loads

Total values of vertical bending moments and vertical shear forces result from the superposition of still water loads with the wave induced loads according to 2.1 or 2.2, respectively.

For ships with large deck openings, the horizontal bending moments and shear forces are to be considered in addition.

Where deemed necessary, loads due to torsion of the ship's hull are to be taken into account.

1. Still water bending moments and shear forces

Due to the provided loading cases the vertical longitudinal bending moments and shear forces are to be proved by calculations for cases in intact conditions (M_{sw} , Q_{sw}) and if required by Naval Authority for damaged or residual strength conditions (M_{swf} , Q_{swf}).

2. Wave induced loads

2.1 Direct calculation of wave-induced hull girder design loads

2.1.1 As a basis for direct calculation of design values, weight distributions according to load cases defined in B. are to be used.

In principle, the estimated representative mass distributions for the defined load cases will be the average of the mass distributions that result in the highest and the lowest still water vertical bending moment. This representative mass distribution leads to an average displacement and an average vertical still water bending moment, M_{sw} .

If required by the Naval Authority, similar direct calculations of weight distributions for the damaged and flooded conditions are to be performed according to B.3. The corresponding representative mass distribution yields an average displacement and an average still water bending moment for the flooded ship, M_{swf} .

2.1.2 Analyses of the ship in harmonic waves are to be executed by direct computational methods that evaluate response operators of wave-induced vertical bending moments and vertical shear forces. Using an adequate nonlinear correction procedure that accounts for a realistic wave breaking criterion, the wave contour along the ship's side has to be determined for relevant harmonic waves with selected wave heights and phase positions. Hydrodynamic pressures are to be extrapolated up to the wave contour.

2.1.3 Hydrodynamic calculations are to be performed for ship speeds that correspond to the operational profile of the ship. If such a profile is not

available, a ship speed of half of the expected maximum, continuous ahead speed in calm water, v_0 , is to be assumed.

2.1.4 After completing the nonlinear correction, forces acting on the ship, including inertial forces, generally are not in balance. Equilibrium can be achieved by resolving the motion equations, resulting in nonlinearly corrected response values, e. g., bending moments. Repeating this procedure for different wave periods and wave headings yields nonlinearly corrected (pseudo) response amplitude operators that depend on wave height. Depending on the considered phase location, different transfer functions result for the sagging and hogging conditions.

2.1.5 Bending moments and shear forces are to be evaluated according to stochastic methods for linear systems. For the stationary seaways, a $\cos^2$ distribution of wave energy in the main wave encounter direction is to be assumed. The seaways' main wave headings relative to the ship are to be considered as equally distributed. Wave heights (H) used to obtain the wave amplitude dependent (pseudo) transfer functions are to be taken as equal to the significant wave height (H_s) of the corresponding natural seaway (i. e., $H = H_s$).

2.1.6 Calculated long-term values of bending moments and shear forces are to be based on relevant long term wave statistics as defined by, e.g., the Naval Authority. If no data are specified, the wave scatter diagram of the North Atlantic, presented in Table 6.3, is to be applied. This table lists probabilities of occurrence of sea states identified by the significant wave height H_s [m] and the zero up-crossing period T [s].

The number of load cycles for long-term values are to be estimated according to the operational profile of the ship. If no information is available, $5 \cdot 10^7$ load cycles are to be assumed. This considers lifetime of 25 years with 230 days per year at sea in the North Atlantic.

2.1.7 Total values of vertical bending moments and vertical shear forces result from the superposition of their long-term values with additional slamming loads caused by wave impact in the ship's forebody region. This can be evaluated by multiplication the calculated vertical wave bending moment (shear force) in sagging condition according to 2.1.6 with the distribution factor C_{MSL} or C_{QSL} , respectively.



$$\begin{aligned}
 C_{MSL} &= 1,25 + 0,4 \cdot x/L && \text{for } 0 \leq x/L < 0,25 \\
 &= 1,15 && \text{for } 0,25 \leq x/L \leq 0,5 \\
 &= 0,79 + 0,72 \cdot x/L && \text{for } 0,5 < x/L < 0,75 \\
 &= 1,12 + 0,28 \cdot x/L && \text{for } 0,75 \leq x/L \leq 1,0 \\
 C_{QSL} &= 1,0 + 2,5 \cdot x/L && \text{for } 0 \leq x/L < 0,1 \\
 &= 1,25 && \text{for } 0,1 < x/L < 0,3 \\
 &= 1,75 - 5/3 \cdot x/L && \text{for } 0,3 < x/L < 0,45 \\
 &= 1,0 && \text{for } 0,45 \leq x/L \leq 0,5 \\
 &= 1/6 + 5/3 \cdot x/L && \text{for } 0,5 < x/L < 0,65 \\
 &= 1,25 && \text{for } 0,65 \leq x/L \leq 0,75 \\
 &= 2 \cdot x/L && \text{for } 0,75 < x/L \leq 1,0
 \end{aligned}$$

Table 6.2 Distribution factor C_M

Range	Hogging	Sagging
$0 \leq \frac{x}{L} < 0,4$	$2,25 \cdot \sqrt{C_B} \cdot \frac{x}{L}$	$-0,02 - 2,45 \cdot \frac{x}{L}$
$0,4 \leq \frac{x}{L} < 0,6$	$0,9 \sqrt{C_B}$	-1
$0,6 \leq \frac{x}{L} \leq 1$	$\left[0,9 - 2,25 \left(\frac{x}{L} - 0,6 \right) \right] \cdot \sqrt{C_B}$	$-1 + 2,375 \left(\frac{x}{L} - 0,6 \right)$

Table 6.3 Distribution factor c_Q

Range	Positive shear forces	Negative shear forces
$0 \leq \frac{x}{L} < 0,10$	$8,80 \cdot \sqrt{C_B} \cdot \frac{x}{L}$	$-0,1 - 8,50 \cdot \frac{x}{L}$
$0,10 \leq \frac{x}{L} < 0,30$	$0,88 \sqrt{C_B}$	- 0,95
$0,30 \leq \frac{x}{L} < 0,45$	$2,64 \cdot \sqrt{C_B} - 0,9 - \frac{x}{L} \cdot \left(\frac{88}{15} \cdot \sqrt{C_B} - 3 \right)$	$-1,95 + \frac{10}{3} \cdot \frac{x}{L}$
$0,45 \leq \frac{x}{L} < 0,50$	0,45	- 0,45
$0,50 \leq \frac{x}{L} < 0,65$	$\frac{61}{15} \cdot \frac{x}{L} - \frac{19}{12}$	$-1,95 - \frac{x}{L} \cdot \left(6,4 \sqrt{C_B} - 3 \right) + 3,2 \cdot \sqrt{C_B}$
$0,65 \leq \frac{x}{L} < 0,75$	1,06	$-0,96 \sqrt{C_B}$
$0,75 \leq \frac{x}{L} < 1,00$	$3,64 - 3,44 \cdot \frac{x}{L}$	$-3,84 \cdot \sqrt{C_B} \cdot \left(1 - \frac{x}{L} \right)$

Figure 6.2 Distribution factor c_M over the ship's lengthFigure 6.3 Distribution factor c_Q over the ship's length

2.1.8 Where deemed necessary, direct calculations described herein are to include loads caused by horizontal bending and torsion of the ship's hull.

2.2 Wave-induced hull girder design loads

2.2.1 Vertical wave bending moments

The vertical wave bending moment is to be determined according to the following formula:

$$M_{wv} = 0,24 \cdot L^2 \cdot B \cdot \sqrt{C_B} \cdot c_0 \cdot c_v \cdot c_M \quad [\text{kNm}]$$

c_M = distribution factor, see Table 6.2 and Figure 6.2

2.2.2 Vertical wave shear forces

Vertical wave shear forces are to be determined according to the following formula:

$$Q_{wv} = 1,0 \cdot 10^{-3} \cdot L \cdot B \cdot \sqrt{C_B} \cdot c_0 \cdot c_v \cdot c_Q \quad [\text{MN}]$$

c_Q = distribution factor, see Table 6.3 and Figure 6.3

2.2.3 Horizontal shear forces

The horizontal wave shear force Q_{wh} is determined by the following formulae :

$$Q_{wh} = Q_{whmax} \cdot c_{QH} \quad [\text{MN}]$$

$$Q_{whmax} = 1,25 \cdot 10^{-3} \cdot \sqrt{L \cdot T} \cdot B \cdot c_0 \quad [\text{MN}]$$

c_{QH} = distribution factor, see Table 6.5 and Figure 6.4.




Figure 6.4 Distribution factor c_{QH} over the ship's length

2.2.4 Horizontal wave bending moments

The horizontal wave bending moment M_{wh} is to be determined according to the following formula:

$$M_{wh} = 0,32 \cdot L \cdot Q_{whmax} \cdot c_M \quad [\text{MNm}]$$

c_M = Absolute value of the distribution factor in sagging condition, see Table 6.2 and Figure 6.2.

2.2.5 Torsion

Effects of the hull girder torsion moment M_{wt} are to be considered if deemed necessary.

Table 6.5 Distribution factor c_{QH}

Range	c_{QH}
$0 \leq x/L < 0,1$	$0,4 + 6 \cdot x/L$
$0,1 \leq x/L \leq 0,3$	1
$0,3 < x/L < 0,4$	$1,0 - 5 \cdot (x/L - 0,3)$
$0,4 \leq x/L \leq 0,6$	0,5
$0,6 < x/L < 0,7$	$0,5 + 5 \cdot (x/L - 0,6)$
$0,7 \leq x/L \leq 0,8$	1,0
$0,8 < x/L \leq 1,0$	$1,0 - 4,25 \cdot (x/L - 0,8)$

Table 6.4 Wave scatter diagram

Zero upcrossing period T [s]								
Hs[m]	3,5	4,5	5,5	6,5	7,5	8,5	9,5	10,5
0,5	1,300E-5	1,337E-3	8,656E-3	1,186E-2	6,342E-3	1,863E-3	3,690E-4	5,600E-5
1,5	0,000E+0	2,930E-4	9,860E-3	4,976E-2	7,738E-2	5,570E-2	2,376E-2	7,035E-3
2,5	0,000E+0	2,200E-5	1,975E-3	2,159E-2	6,230E-2	7,450E-2	4,860E-2	2,066E-2
3,5	0,000E+0	2,000E-6	3,490E-4	6,955E-3	3,227E-2	5,675E-2	5,099E-2	2,838E-2
4,5	0,000E+0	0,000E+0	6,000E-5	1,961E-3	1,354E-2	3,288E-2	3,857E-2	2,686E-2
5,5	0,000E+0	0,000E+0	1,000E-5	5,100E-4	4,984E-3	1,603E-2	2,373E-2	2,008E-2
6,5	0,000E+0	0,000E+0	2,000E-6	1,260E-4	1,670E-3	6,903E-3	1,258E-2	1,269E-2
7,5	0,000E+0	0,000E+0	0,000E+0	3,000E-5	5,210E-4	2,701E-3	5,944E-3	7,032E-3
8,5	0,000E+0	0,000E+0	0,000E+0	7,000E-6	1,540E-4	9,790E-4	2,559E-3	3,506E-3
9,5	0,000E+0	0,000E+0	0,000E+0	2,000E-6	4,300E-5	3,320E-4	1,019E-3	1,599E-3
10,5	0,000E+0	0,000E+0	0,000E+0	0,000E+0	1,200E-5	1,070E-4	3,790E-4	6,750E-4
11,5	0,000E+0	0,000E+0	0,000E+0	0,000E+0	3,000E-6	3,300E-5	1,330E-4	2,660E-4
12,5	0,000E+0	0,000E+0	0,000E+0	0,000E+0	1,000E-6	1,000E-5	4,400E-5	9,900E-5
13,5	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0	3,000E-6	1,400E-5	3,500E-5
14,5	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0	1,000E-6	4,000E-6	1,200E-5
15,5	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0	1,000E-6	4,000E-6
16,5	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0	1,000E-6

Zero upcrossing period T [s]								
Hs[m]	11,5	12,5	13,5	14,5	15,5	16,5	17,5	18,5
0,5	7,000E-6	1,000E-6	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0	0,000E+0
1,5	1,607E-3	3,050E-4	5,100E-5	8,000E-6	1,000E-6	0,000E+0	0,000E+0	0,000E+0
2,5	6,445E-3	1,602E-3	3,370E-4	6,300E-5	1,100E-5	2,000E-6	0,000E+0	0,000E+0
3,5	1,114E-2	3,377E-3	8,430E-4	1,820E-4	3,500E-5	6,000E-6	1,000E-6	0,000E+0
4,5	1,275E-2	4,551E-3	1,309E-3	3,190E-4	6,900E-5	1,300E-5	2,000E-6	0,000E+0
5,5	1,126E-2	4,636E-3	1,509E-3	4,100E-4	9,700E-5	2,100E-5	4,000E-6	1,000E-6
6,5	8,259E-3	3,868E-3	1,408E-3	4,220E-4	1,090E-4	2,500E-5	5,000E-6	1,000E-6
7,5	5,249E-3	2,767E-3	1,117E-3	3,670E-4	1,020E-4	2,500E-5	6,000E-6	1,000E-6
8,5	2,969E-3	1,746E-3	7,760E-4	2,770E-4	8,400E-5	2,200E-5	5,000E-6	1,000E-6
9,5	1,522E-3	9,920E-4	4,830E-4	1,870E-4	6,100E-5	1,700E-5	4,000E-6	1,000E-6
10,5	7,170E-4	5,150E-4	2,730E-4	1,140E-4	4,000E-5	1,200E-5	3,000E-6	1,000E-6
11,5	3,140E-4	2,470E-4	1,420E-4	6,400E-5	2,400E-5	7,000E-6	2,000E-6	1,000E-6
12,5	1,280E-4	1,100E-4	6,800E-5	3,300E-5	1,300E-5	4,000E-6	1,000E-6	0,000E+0
13,5	5,000E-5	4,600E-5	3,100E-5	1,600E-5	7,000E-6	2,000E-6	1,000E-6	0,000E+0
14,5	1,800E-5	1,800E-5	1,300E-5	7,000E-6	3,000E-6	1,000E-6	0,000E+0	0,000E+0
15,5	6,000E-6	7,000E-6	5,000E-6	3,000E-6	1,000E-6	1,000E-6	0,000E+0	0,000E+0
16,5	2,000E-6	2,000E-6	2,000E-6	1,000E-6	1,000E-6	0,000E+0	0,000E+0	0,000E+0

D. Structural Resistance

1. General

The calculation of the structural resistance or stresses can be carried out by an analysis of the complete hull.

If no complete hull analysis is carried out, the sectional area of effective continuous longitudinal members contributing to the longitudinal strength can be taken into account. Relevant parts of the shadow areas are to be deducted from sectional areas according to Figure 6.5 and Figure 6.6.




Figure 6.5 Application of the shadow principle for the ship's hull and superstructures




Figure 6.6 Application of the shadow principle for the ship's hull and superstructures

Smaller openings (manholes, lightening holes, single scallops in way of seams, etc.) need not be deducted, provided the sum of their breadths or shadow area breadths in one transverse section does not reduce the section modulus at deck or bottom by more than 3 % and provided that the height of lightening holes, drainage openings and single scallops in longitudinals or longitudinal girders does not exceed 25 % of the web depth or, for scallops, 75 mm

Refer also to Section 4,G.1.2.

2. Structural design

2.1 In general, longitudinal structures are to be designed such that they run through transverse structures continuously. Major discontinuities have to be avoided.

If longitudinal structures are staggered, sufficient shifting elements shall be provided.

3. Ultimate load calculation of the ship's transverse sections

3.1 Ultimate vertical bending criterium

$$|\gamma_{\text{stat}} \cdot M_{\text{SW}} + \gamma_{\text{dyn}} \cdot M_{\text{WV}}| \leq |M_U / \gamma_m|$$

$$|\gamma_{\text{stat}} \cdot M_{\text{SWf}} + \gamma_{\text{dyn}} \cdot M_{\text{WVf}}| \leq |M_U / \gamma_m|$$

The assumed safety factor correspond to a probability level of $Q = 10^{-8}$.

3.1.1 Progressive collapse analysis

A progressive collapse analysis is to be used to calculate the ultimate vertical bending moments of a ship's effective transverse section. The procedure is to be based on a simplified incremental-iterative approach where the capacities are defined as the peaks of the resulting moment-curvature curve ($M-\chi$) in hogging (positive) and sagging (negative) conditions, i.e. χ is the hull girder curvature [1/m]. See Figure 6.7.




Figure 6.7 Moment-curvature curve

The main steps to be used in the incremental-iterative approach are summarised as follows:

Step 1 The ship's transverse section is to be divided into plate-stiffener combinations (see 3.1.2.2 (a)) and hard corners (see 3.1.2.2(b)).

Step2 The average stress - average strain relationships $\sigma_{CRk} - \epsilon$ for all structural elements (i.e. stiffener-plate combinations and hard corners) are to be defined, where the subscript k refers to the modes 0, 1, 2, 3 or 4, as applicable (see 3.1.2).

Step 3 The initial and incremental value of curvature $\Delta\chi$ is to be defined by the following formula:

$$\Delta\chi = \frac{0,05 \frac{R_{eH}}{E}}{Z_D - Z_{NA,e}}$$

R_{eH} = minimum nominal yield point of structural elements in the strength deck [MPa]

Z_D = z co-ordinate of strength deck at side [m]

$Z_{NA,e}$ = z co-ordinate of elastic neutral axis for the ship's transverse section [m]

Step 4 For the value of curvature, $\chi_i = \chi_{i-1} + \Delta\chi$, the average strain $\epsilon_{Ei,j} = \chi_i z_i$ and corresponding average stress $\sigma_{i,j}$ is to be defined for each structural element i (see 3.1.2). For structural elements under tension, $\sigma_{i,j} = \sigma_{CR0}$ (see

3.1.2.1). For plate-stiffener combinations under compression, $\sigma_{i,j} = \text{minimum } [\sigma_{CR1}, \sigma_{CR2}, \sigma_{CR3}]$ (see 3.1.2.2 (a)). For hard corners under compression, (see 3.1.2.2 (b)).

z_i = z co-ordinate of ith structural element [m] relative to basis, see also Figure 6.9.

Step 5 For the value of curvature, $\chi_i = \chi_{i-1} + \Delta\chi$, the height of the neutral axis $z_{NA,j}$ is to be determined iteratively through force equilibrium over the ship's transverse section:

$$\sum_{i=1}^m A_i \cdot \sigma_{i,j} = \sum_{i=1}^n A_i \sigma_{i,j}$$

m is the number of structural elements located above $z_{NA,j}$

n is the number of structural elements located below $z_{NA,j}$

A_i = cross-sectional area of ith plate-stiffener combination or hard corner

Step 6 For the value of curvature, $\chi_i = \chi_{i-1} + \Delta\chi$, the corresponding bending moment is to be calculated by summing the contributions of all structural elements within the ship's transverse section:

$$M_{U,j} = \sum \sigma_{i,j} A_i (z_{NA,j} - z_i)$$

Steps 4 through 6 are to be repeated for increasing increments of curvature until the peaks in the M- χ curve are well defined. The ultimate vertical bending moments $M_{U,H}$ and $M_{U,S}$ are to be taken as the peak values of the M- χ curve.

3.1.2 Average stress - average strain curves

A typical average stress - average strain curve $\sigma_{CRk} - \epsilon$ for a structural element within a ship's transverse section is shown in Figure 6.8, where the subscript k refers to the modes 0, 1, 2, 3 or 4, as applicable.




Figure 6.8 Typical average stress-average strain curve

3.1.2.1 Negative strain ($\sigma_{CR0-\epsilon}$)

The portion of the curve corresponding to negative strain (i.e. tension) is in every case to be based on elasto-plastic behaviour (i.e. material yielding) according to the following:

$$\sigma_{CR0} = \Phi R_{eH} \quad [\text{MPa}]$$

Φ = Edge function

$$= -1 \quad \text{for} \quad \epsilon < -1$$

$$= \epsilon \quad \text{for} \quad -1 \leq \epsilon \leq 0$$

ϵ = Relative strain

$$= \epsilon_E / \epsilon_Y$$

ϵ_E = Element strain

ϵ_Y = Strain at yield stress in the element

$$= R_{eH} / E$$




Figure 6.9 Structural elements

3.1.2.2 Positive strain

The portion of the curve corresponding to positive strain (i.e. compression) is to be based on some mode of collapse behaviour (i.e. buckling) for two types of structural elements; (a) plate-stiffener combinations and (b) hard corners, see Figure 6.9.

(a) Plate-stiffener combinations ($\sigma_{CR1-\epsilon}$, $\sigma_{CR2-\epsilon}$, $\sigma_{CR3-\epsilon}$)

Plate-stiffener combinations are comprised of a single stiffener together with the attached plating from adjacent plate fields. Under positive strain, three average stress - average strain curves are to be defined for each plate-stiffener combination based on beam column buckling ($\sigma_{CR1-\epsilon}$), torsional buckling ($\sigma_{CR2-\epsilon}$) and web/flange local buckling ($\sigma_{CR3-\epsilon}$).

(i) Beam column buckling $\sigma_{CR1-\epsilon}$

The positive strain portion of the average stress - average strain curve $\sigma_{CR1-\epsilon}$ based on beam column buckling of plate-stiffener combinations is described according to the following:

$$\sigma_{CR1} = \phi R_{eH} K_{BC} \frac{A_{stif} + b_{m,1} \cdot t_1/2 + b_{m,2} \cdot t_2/2}{A_{stif} + b_1 t_1/2 + b_2 \cdot t_2/2}$$

Φ = Edge function

$$= \epsilon \quad \text{for} \quad 0 \leq \epsilon \leq 1,0$$

$$= 1,0 \quad \text{for} \quad \epsilon > 1$$

K_{BC} = Reduction factor

$$= 1,0 \quad \text{for} \quad \lambda_K \leq \lambda_0$$

$$= \frac{1}{k_D + \sqrt{k_D^2 - \lambda_K^2}} \quad \text{for} \quad \lambda_K > 0,2$$

$$\lambda_K = \sqrt{\frac{\epsilon_E a^2 A_X}{\pi^2 I_X}} \cdot 10^{-4}$$

$$\lambda_0 = 0,2$$

$$k_D = (1 + \eta_p (\lambda_K - \lambda_0) + \lambda_K^2) / 2$$

$$\eta_p = 0,21$$

$$a = \text{Length of stiffener [mm]}$$

$$A_x = \text{Sectional area of stiffener with attached shell plating of breadth } (b_{m,1}/2 + b_{m,2}/2) \text{ [mm}^2\text{]}$$

$$I_x = \text{Moment of inertia of stiffener with attached shell plating of breadth } (b_{m,1}/2 + b_{m,2}/2) \text{ [cm}^4\text{]}$$

$b_{m,1}, b_{m,2}$ = Effective breadths of single plate fields on sides 1 and 2 of stiffener [mm] according to Section 4, F.2.2, in general based on Load Case 1 of Table 4.9, where the reference degree of slenderness is to be defined as

$$\lambda = \sqrt{\frac{\epsilon_E}{0,9 \left(\frac{t}{b} \right)^2 \cdot K}}$$

b_1, b_2 = Breadths of single plate fields on sides 1 and 2 of stiffener [mm], see also Figure 6.9

t_1, t_2 = Thicknesses of single plate fields on sides 1 and 2 of stiffener [mm]

A_{stif} = Sectional area of the stiffener without attached plating [mm²]

(ii) Torsional buckling $\sigma_{CR2}^{-\epsilon}$

The positive strain portion of the average stress - average strain curve $\sigma_{CR2}^{-\epsilon}$ based on torsional buckling of plate-stiffener combinations is described according to the following:

$$\sigma_{CR2} = \phi \cdot R_{eH} \frac{A_{stif} \cdot \kappa_T + b_{m,1} \cdot t_1/2 + b_{m,2} \cdot t_2/2}{A_{stif} + b_1 \cdot t_1/2 + b_2 \cdot t_2/2}$$

κ_T = Reduction factor according to Section 4, F.3.3.

(iii) Web/flange local buckling $\sigma_{CR3}^{-\epsilon}$

The positive strain portion of the average stress - average strain curve $\sigma_{CR3}^{-\epsilon}$ based on web/flange local

buckling of plate-stiffener combinations is described according to the following:

$$\sigma_{CR3} = \phi \cdot R_{eH} \cdot \frac{h_{w,m} \cdot t_w + b_{f,m} \cdot t_f + b_{m,1} \cdot t_1/2 + b_{m,2} \cdot t_2/2}{h_w t_w + b_f \cdot t_f + b_1 \cdot t_1/2 + b_2 \cdot t_2/2}$$

$h_{w,m}, b_{f,m}$ = Effective width of web/flange plating [mm]

according to Section 4, F.2.2 (generally based on Load Case 3 of Table 4.9 for flat bars and flanges, otherwise Load Case 1) where the reference degree of slenderness is to be defined as

$$\lambda = \sqrt{\frac{\epsilon_E}{0,9 \left(\frac{t}{b} \right)^2 \cdot K}}$$

h_w = Web height [mm]

t_w = Web thickness [mm]

b_f = Flange breadth, where applicable [mm]

t_f = Flange thickness, where applicable [mm]

(b) Hard corners ($\sigma_{CR4}^{-\epsilon}$)

Hard corners are sturdy structural elements comprised of plates not lying in the same plane. Bilge strakes (i.e. one curved plate), sheer strake-deck stringer connections (i.e. two plane plates) and bulkhead-deck connections (i.e. three plane plates) are typical hard corners. Under positive strain, single average stress - average strain curves are to be defined for hard corners based on plate buckling ($\sigma_{CR4}^{-\epsilon}$).

(i) Plate buckling $\sigma_{CR4}^{-\epsilon}$

$$\sigma_{CR4} = \phi \cdot R_{eH} \frac{\sum_{i=1}^n b_{m,i} \cdot t_i}{\sum_{i=1}^n b_i \cdot t_i}$$

$b_{m,i}$ = Effective breadths of single plate fields [mm] according to Section 4, F.2.2, as applicable, in general based on applicable Load Cases in Table 4.9 and Table 4.10, where the reference degree of slenderness is to be defined as

$$\lambda = \sqrt{\frac{\varepsilon_E}{0,9 \left(\frac{t_i}{b_i} \right)^2 \cdot K}}$$

b_i = Breadth of single plate fields [mm], see also Figure 6.9

t_i = Thickness of single plate fields [mm]

n = Number of plates comprising hard corner

3.2 Ultimate vertical shear criterium

$$|\gamma_{\text{fstat}} \cdot Q_{\text{SW}} + \gamma_{\text{fdyn}} \cdot Q_{\text{WV}}| \leq |Q_U / \gamma_m|$$

$$|\gamma_{\text{fstat}} \cdot Q_{\text{SWf}} + \gamma_{\text{fdyn}} \cdot Q_{\text{WVf}}| \leq |Q_U / \gamma_m|$$

The assumed safety factors correspond to a probability level of $Q = 10^{-8}$.

$$Q_U = \frac{10^{-6}}{\sqrt{3}} \cdot \sum_{i=1}^q \kappa_{\text{ti}} \cdot b_i \cdot t_i \cdot R_{\text{eH},i} \text{ MN}$$

q = Number of shear force transmitting plate fields (in general, these are only the vertical plate fields of the ship's transverse section, e.g. shell and longitudinal bulkhead plate fields)

κ_{ti} = Reduction factor of the i^{th} plate field according to Section 4, F.2.1.

b_i = Breadth of the i^{th} plate field [mm]

t_i = Thickness of the i^{th} plate field [mm]

$R_{\text{eH},i}$ = Minimum nominal yield point of the i^{th} plate field [N/mm²]

4. Hull girder stresses

4.1 Design stresses

Design stresses for the purpose of this rule are global load stresses, which are acting:

- as normal stresses σ_L in ship's longitudinal direction:

- for plates as membrane stresses

- for longitudinal profiles and longitudinal girders in the bar axis

- as shear stresses τ_L in the plate level

The stresses σ_L and τ_L are to be considered in the formulae for dimensioning of plate thicknesses, longitudinal and grillage systems (Section 4) including notch stresses, buckling strength and fatigue strength.

4.1.1 The calculation of these stresses can be carried out by an analysis of the complete hull. In this case f_Q is to be set to 0,75 for ships with a design life of 25 years.

4.1.2 If no complete hull analysis is carried out, the most unfavourable values of the hull girder stresses according to 4.1.3 for intact and damaged conditions

are to be taken for σ_L and τ_L respectively. Following load combinations are to be investigated:

- σ_L and $\Psi \cdot \tau_L$

- $\Psi \cdot \sigma_L$ and τ_L

Ψ = Combination factor according to Section 4, A.2.

= 0,7

4.1.3 Global hull girder stresses

$$\sigma_L = \sigma_{\text{SW}} + f_Q \sqrt{\sigma_{\text{WV}}^2 + \sigma_{\text{WH}}^2}$$

$$\sigma_{\text{Lf}} = \sigma_{\text{SWf}} + f_Q \sqrt{\sigma_{\text{WVf}}^2 + \sigma_{\text{WHf}}^2}$$

$$\tau_L = \tau_{\text{SW}} + f_Q \sqrt{\tau_{\text{WV}}^2 + \tau_{\text{WH}}^2}$$

$$\tau_{\text{Lf}} = \tau_{\text{SWf}} + f_Q \sqrt{\tau_{\text{WVf}}^2 + \tau_{\text{WHf}}^2}$$

$$\sigma_L = \max(\sigma_{\text{Li}}); \tau_L = \max(\tau_{\text{Li}})$$

The stress components (with the proper signs) are to be added such that for σ_L and τ_L extreme values are resulting.

f_Q = Probability factor according to Section 4, A.2., but not less than 0,75 for $Q = 10^{-6}$

For the determination of scantlings for structural parts as described in 4.1 considering the load cases defined in Section 4, A.2., f_Q is to be set to 0,75 for ships with a design life of 25 years.

For structures loaded by compression and/or shear forces, sufficient buckling strength according to Section 4, F, is to be proved.

Shear stress distribution shall be calculated by calculation procedures approved by **BCS**. For ships multicell transverse cross sections (e.g. ships), the use of such a especially with non-uniform the ship's transverse

Note:

As a first approximation σ_L and τ_L may be taken as follows for

- bottom plating

$$\sigma_L = 0,34 \cdot R_{eH} \cdot f_{pL}$$

$$\tau_L = 0$$

- side shell plating

$$\sigma_L = 0,25 \cdot R_{eH} \cdot f_{pL}$$

$$\tau_L = 0,15 \cdot R_{eH} \cdot f_{pL}$$

- deck plating

$$\sigma_L = 0,46 \cdot R_{eH} \cdot f_{pL}$$

$$\tau_L = 0$$

with f_{pL} according to Section 4, B.4.2.

4.2 Structural Design

The required welding details and classifying of notches result from the fatigue strength analysis according to Section 17.

Within the upper and lower hull girder flange, the detail categories for the welded joints (see Section 17, Table 17.3) shall not be less than

$$\Delta\sigma_{Rmin} = \frac{(M_{WVhog} - M_{WVsag}) \cdot |e_z|}{(4825 - 29 \cdot n) \cdot I_y} \quad [N/mm^2]$$

M_{WVhog} , M_{WVsag} = Vertical wave bending moment for hogging and sagging according to C.2.

n = Design lifetime of the ship

$$\geq 25 \text{ [years]}$$

4.3 Normal stresses due to bending moments

4.3.1 Statical from M_{SW} :

$$\sigma_{SW} = \gamma_{fstat} \cdot M_{SW} \cdot e_z / I_y \quad [N/mm^2]$$

M_{SW} = Still water bending moment according to C.1. at the position x/L

I_y = Moment of inertia of the transverse ship section [m^4] around the horizontal axis at the position x/L

e_z = Vertical distance of the structure considered from the horizontal neutral axis [m] (positive sign: above the neutral axis)

4.3.2 Dynamical from M_{WV} :

$$\sigma_{WV} = \gamma_{fdyn} \cdot M_{WV} \cdot e_z / I_y \quad [N/mm^2]$$

4.3.3 Dynamical from M_{WH} :

$$\sigma_{WH} = \pm \gamma_{fdyn} \cdot M_{WH} \cdot e_y / I_z \quad [N/mm^2]$$

M_{WH} = Horizontal wave bending moment according to C. at the position x/L

I_z = Moment of inertia [m^4] section considered around the vertical axis at the position x/L

e_y = Horizontal distance of the structure considered from the vertical neutral axis [m] (positive sign)

t = Thickness of side shell plating considered [mm]

For ships of normal shape and construction, the ratio S_y/I_y determined for the midship section can be used for all cross sections.

4.4.3 dynamical from Q_{WH} :

$$\tau_{wv} = 1000 \cdot \gamma_{fdyn} \cdot Q_{WH} \cdot S_z(y) / I_z \cdot t(y) \quad [N/mm^2]$$

$S_z(y)$ = First moment of the sectional area [m^3], related to the vertical, neutral axis

4.4 Shear stresses due to shear forces

As a first approximation, the distribution of the shear stress in the shell can be calculated with the following formulae:

4.4.1 Statical from Q_{SW} :

$$\tau_{sw} = 0,5 \cdot \gamma_{fstat} \cdot Q_{SW} \cdot S_y(z) / I_y \cdot t \quad [N/mm^2]$$

4.4.2 Dynamical from Q_{wv} :

$$\tau_{wv} = 0,5 \cdot \gamma_{fdyn} \cdot Q_{wv} \cdot S_y(z) / I_y \cdot t \quad [N/mm^2]$$

$S_y(z)$ = First moment of the sectional area considered [m^3], above or below, respectively, the level z considered, and related to the horizontal, neutral axis

$t(y)$ = Sum of thicknesses of relevant deck and bottom plating [mm] at position y

5. Deflection criterion

The permissible elastic deflection of the hull girder may be limited due to its intended purpose. In general, the minimum required moment of inertia of the hull girder cross section considering the partial safety factors corresponding to LCC, as described in Section 4, A.2. is defined as follows:

$$I_{req} = (\gamma_{fstat} \cdot M_{SW} + \gamma_{fdyn} \cdot M_{wv}) \cdot L/4200 \quad \text{for steel structures}$$

$$I_{req} = (\gamma_{fstat} \cdot M_{SW} + \gamma_{fdyn} \cdot M_{wv}) \cdot L/2050 \quad \text{for aluminium alloys}$$

SECTION 7

BOTTOM AND SHELL STRUCTURES

	Page
A. General, Definitions.....	7-2
1. General	
2. Definitions	
3. Design references	
B. Plating	7-2
1. Keel, keel plating	
2. Sheerstrake	
C. Secondary Stiffeners.....	7-3
1. Transverse framing	
2. Longitudinal framing	
3. Struts	
D. Primary Members	7-4
1. Bottom centre girder	
2. Bottom side girders	
3. Margin plates	
4. Floor plates	
5. Web frames and stringers	
E. Appendages and Internals.....	7-6
1. Bilge keel	
2. Bulwark	
3. Sea chests	
4. Bilge wells	
5. Sonar domes	
F. Special Strengthening.....	7-8
1. Strengthening against harbour and tug manoeuvres and berthing impacts	
2. Docking	
3. Beach Contact	

A. General, Definitions**1. General**

The scantlings of plating, secondary and primary members of the bottom, double bottom and shell structures are to be determined according to Section 4, B. and C.

For shell doors the requirements of the Section 22 are to be fulfilled in addition.

The plate thicknesses are to be tapered gradually, if different.

Gradual taper is also to be effected between the thicknesses required for local strengthening.

If applicable (e.g. for double bottom), the requirements of the Sections 8 (decks), 9 (bulkheads) and 10 (tanks) are to be fulfilled.

1.1 Arrangement of double bottom

1.1.1 It is recommended that a double bottom is to be fitted extending from the collision bulkhead to the afterpeak bulkhead, as far as this is practicable and compatible with the design and service of the ship.

1.1.2 If a double bottom is provided the inner bottom is to be extended to the ship's sides as to protect the bottom up to the turn of the bilge.

1.1.3 In fore- and afterpeak a double bottom need not be arranged.

1.1.4 For Tank Landing Ship (LST) and Infantry Landing Craft (LCI) special attention has to be paid to the bottom structure at the rear end (centre of rotation) of the landing ramp because the total weight of tracked vehicles acts there as local load, see also Section 22 and Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 3, F.

2. Definitions

p_{BK} = Design load acting on bilge keels [kN/m²] according to Section 5, C.3.1

p_{SL} = Design impact pressure [kN/m²] forward of $\frac{x}{L} = 0,6$ according to Section 5, C.2.

p_L = Load on decks [kN/m²], according to Section 5, E.

p_s = Total design pressure for the bottom and shell [kN/m²], according to Section 5, C.1.

p_{T1} = Design pressure for tanks [kN/m²] according to Section 5, F.1.

p_{WT} = Total design load on watertight partitions [kN/m²] according to Section 5, D.1.

3. Design references**3.1 Buckling strength**

All elements of the bottom and shell structure are to be examined for sufficient buckling strength according to Section 4, F.

3.2 Minimum thickness

At no point the thickness of bottom and side shell plating shall be less than the values defined in Section 4, Table 4.3.

B. Plating**1. Keel, keel plating****1.1 Design of keel**

For the design of a keel the following operating conditions have to be observed:

- Docking, see also F.2.

- Beach contact, e.g. for landing ships, see also F.3.

$$b = 800 + 5 L \text{ [mm]}$$

$$b_{\max} = 1800 \text{ mm}$$

1.2 Flat keel

1.2.1 A keel plate shall extend over the complete length of the ship. The width of flat plate keel is not to be less than:

$$b = 800 + 5L \text{ [mm]}$$

1.2.2 The thickness of the flat plate keel is not to be less than:

$$t_{FK} = t_B + 1,5 \text{ [mm]}$$

t_B = Thickness of bottom plating [mm] according to Section 4, B.4..

1.3 Box keel

1.3.1 The bottom plate of the box keel shall have a plate thickness not less than the flat keel thickness

$$t_B + 1,5 \text{ mm.}$$

The side (skeg) plates shall have a thickness not less than

$$t_B + 1,0 \text{ mm.}$$

1.3.2 Sufficient shifting brackets (horizontal and/ or vertical) are to be provided at the cross point of the bottom plating and side plating of the boxkeel in way of floors.

1.4 Bar keel

1.4.1 The sectional area A of the bar keel shall not be less than the following:

$$A = 0,5 \cdot L \text{ [cm}^2\text{]}$$

1.4.2 Where a bar keel is arranged, the adjacent garboard strake is to have the scantlings of a flat plate keel.

2. Sheerstrake

2.1 The width of the sheerstrake is not to be less than:

2.2 The thickness of the sheerstrake shall, in general, not be less than the greater of the following two values:

$$t = 0,5 (t_D + t_s) \text{ [mm]}$$

$$t = t_s$$

t_D = Required thickness of strength deck according to Section 4, B.4.

t_s = Required thickness of side shell according to Section 4, B.4.

2.3 Where the connection of the deck stringer with the sheerstrake is rounded, the radius is to be at least 15 times the plate thickness or 150 mm whichever is greater.

2.4 Welds on upper edge of sheerstrake are subject to special approval.

Regarding welding between sheerstrake and deck stringer, see Section 8, B.3.

2.5 Holes for scuppers and other openings are to be smoothly rounded. Notch factors, see Section 4, H.

C. Secondary Stiffeners

1. Transverse framing

1.1 End attachment

1.1.1 The lower bracket attachment to the bottom structure is to be determined on the basis of the frame section modulus.

1.1.2 The upper bracket attachment to the deck structure and/or to the 'tween deck frames is to be determined on the basis of the section modulus of the deck beams or 'tween deck frames whichever is the greater.

1.1.3 Where the bottom is framed longitudinally but the sides are framed transversely, flanged brackets having a thickness of the floors are to be fitted between the plate floors at every transverse frame, extending to the outer longitudinals at the bottom and inner bottom.

1.1.4 Where frames are supported by a longitudinally framed deck, the frames fitted between web frames are to be connected to the adjacent longitudinals by brackets. The scantlings of the brackets are to be determined on the basis of the section modulus of the frames.

1.2 Strengthening in fore and aft body

1.2.1 General

Fore and aft body is to be properly designed considering the hydrodynamic pressure defined in Section 5, C.

1.2.2 Tripping brackets

Between the point of the greatest breadth of the ship at maximum draft and the collision bulkhead tripping brackets are to be fitted if frames are not supported over a distance exceeding 2,6 m.

2. Longitudinal framing

2.1 Longitudinals shall preferably be continuous through floor plates and/or transverses. Attachments of their webs to the floor plates and transverses are to be sufficient to transfer the support forces according to Section 4, Table 4.4.

Forward of $0,1 L$ from **FP** webs of longitudinals are to be connected effectively at both sides to transverse members. If the flare angle α exceeds 40° additional heel stiffeners or brackets are to be arranged.

2.2 Where longitudinals are not continuous at watertight floors and bulkheads, they are to be attached to the floors by brackets of the thickness of plate floors, and with a length of weld at the longitudinals equal to $2 x$ depth of the bottom longitudinals.

2.3 Where necessary, for longitudinals between transverse bulkheads and side transverses additional stresses resulting from the deformation of the side transverses are to be taken into account.

2.4 In the fore body, where the flare angle α exceeds 40° and in the aft body where the flare angle exceeds 75° the unsupported span of the longitudinal located between $T_{\min} - C_0$ and $T + C_0$ must not be larger than 2,6 m. Otherwise tripping brackets are to be arranged.

3. Struts

Struts are elements which connect secondary stiffening members at inner and outer bottom.

The cross sectional area of the struts is to be determined according to Section 4, C.5. analogously. The strut load is to be taken from the direct stress analysis.

D. Primary Members

1. Bottom centre girder

1.1 All ships are to have a centre girder or two longitudinal girders near to each other for docking.

1.2 The centre girder has to be extended as far forward and aft as practicable. It is to be connected to the girders of a non-continuous double bottom or is to be scarphed into the double bottom by two frame spacings.

1.3 Towards the ends the thickness of the web plate as well as the sectional area of the top plate may be reduced by 10 per cent. Lightening holes are to be avoided.

1.4 Lightening holes in the centre girder are generally permitted only outside $0,75 L$ amidships. Their depth is not to exceed half the depth of the centre girder and their lengths are not to exceed the half frame spacing.

1.5 No centre girder is required in way of engine seating in case of centre engine.

1.6 The center girder should be watertight at least for 0,5 L amidships, unless the double bottom is subdivided by watertight side girders.

2. Bottom side girders

2.1 The side girders are to extend as far forward and aft as practicable. They are to be connected to the girders of a non-continuous double bottom or are to be scarphed into the double bottom by two frame spacing.

2.2 Towards the ends, the web thickness and the sectional area of the face plate may be reduced by 10 per cent.

2.3 At least one side girder shall be fitted in the engine room and in way of 0,25 L aft of **FP**. The actual number of bottom side girders in all parts of double bottom has to be arranged at distances following from the overall bottom analyses according to Section 4, C.4.

3. Margin plates

3.1 The margin plate has to be watertight. Brackets in line with floor plates and frames are to be provided to connect the margin plate to the side framing.

3.2 In case of longitudinal framing system stiffening plates are to be provided at the margin plate to connect the margin plate to the longitudinals in the double bottom.

4. Floor plates

4.1 General

4.1.1 For the connection of floor plates with the frames, see Section 15.

4.1.2 Deep floors, particularly in the after peak, are to be provided with buckling stiffeners.

4.1.3 The floor plates are to be provided with limbers to permit the water to reach the pump suction.

4.1.4 In ships having a considerable rise of floor the depth of the floor plate webs at the beginning of the turn of bilge is not to be less than the depth of the frame.

4.1.5 The face plates of the floor plates are to be continuous over their span. If they are interrupted at the centre keelson, they are to be connected to the centre keelson by means of full penetration welding.

4.1.6 Where the longitudinal framing system changes to the transverse framing system, structural continuity or sufficient scarphing is to be provided for.

4.2 Plate floor arrangement

4.2.1 The spacing of plate floors will result from the overall analysis according to Section 4, C.4.

4.2.2 Plate floors are to be fitted:

- In the engine room, as far as necessary
- Under boiler seatings
- Under bulkheads
- Under corrugated bulkheads, see also Section 4, D.3.

4.2.3 Where the longitudinal framing system is adopted, the floor spacing should, in general, not exceed 5 times the longitudinal frame spacing.

4.2.4 In way of strengthening of bottom forward, the plate floors are to be connected to the shell plating and inner bottom by continuous fillet welding.

4.3 Bracket floors

4.3.1 Where plate floors are not required according to 4.2.1 and 4.2.2 bracket floors may be fitted.

4.3.2 Bracket floors consist of bottom frames at the shell plating and reversed frames at the inner bottom, attached to centre girder, side girders and ship's side by means of brackets.

4.4 Floor plates in the peaks

4.4.1 The thickness of the floor plates in the peaks is to be determined according to the direct analysis.

4.4.2 The floor plates in the afterpeak are to extend over the stern tube, see also Section 11, B.

4.4.3 Where propeller revolutions are exceeding 300 rpm (approx.) the peak floors above the propeller are to be strengthened. Particularly in case of flat bottoms additional longitudinal stiffeners are to be fitted above or forward of the propeller.

5. Web frames and stringers

5.1 Side transverses

In the fore body where flare angles α are larger than 40° the web is to be stiffened in the transition zone to the deck transverse.

5.2 Web frames in machinery spaces

5.2.1 In the engine and boiler rooms, web frames suitably spaced are to be fitted. Generally, they should extend up to the uppermost continuous deck.

5.2.2 For combustion engines web frames shall generally be fitted at the forward and aft ends of the engine. The web frames are to be evenly distributed along the length of the engine.

5.2.3 Where combustion engines are fitted aft, stringers spaced 2,6 m apart are to be fitted in the engine room, in alignment with the stringers in the after peak, if any.

E. Appendages and Internals

1. Bilge keel

1.1 Design references

Where applicable, the effects of longitudinal hull girder bending stresses on the bilge keel are to be considered.

1.2 Where bilge keels of profiles are provided

they are to be welded to continuous flat bars, which are connected to the shell plating with their flat side by means of a continuous watertight welded seam, see bottom of Figure 7.1. The ends of the bilge keels are to have smooth transition zones according to Figure 7.1, top. The ends of the bilge keels shall terminate above an internal stiffening element.

1.3 Where boxshaped bilge keels according to Figure 7.2 are provided, the longitudinal plates of the bilge keel are to be connected by full penetration welds in way of the transverse webs. The bilge keel shall be welded to an insert plate of the shell plating.

Other designs may be accepted on the basis of a fatigue strength calculation.

The loads on the bilge keel are defined in Section 5, C.3.1

1.4 The weld connection of bilge keels to the hull structure shall be in accordance with Section 15, C., Table 15.3.

1.5 Any scallops or cut-outs in longitudinal members of bilge keels are to be avoided.

2. Bulwark

2.1 Plating

The thickness of bulwark plating is to be determined according to side shell plating.

Plate bulwarks are to be stiffened at the upper edge by a bulwark rail section.

2.2 Bulwark stays

2.2.1 The bulwark is to be suitably supported by bulwark stays.

2.2.2 The stays are to be fitted above deck beams, beam knees or carlings. It is recommended to provide flat bars in the lower part which are to be effectively connected to the deck plating, see Figure 7.3

2.3 At the ends of a bulwark or at the expansion joints the connection of the bulwark with the hull has to be established in a way to avoid notch effects.

If no expansion joints are provided or if the bulwark transfers stresses from longitudinal hull girder bending these stresses have to be considered in the design.




Figure 7.1 Ends of "profile-type" keels

2.4 For the connection of bulwarks with the sheer strake B.2. is to be observed.

2.5 Bulwarks are to be provided with freeing ports of sufficient size. See also Section 19, E.

3. Sea chests

3.1 The scantlings of sea chests are to be determined according to Section 4, B.4. using the pressure

$$P_{sc} = 100 \cdot p_v \cdot \gamma_{dyn} \text{ [kN/m}^2\text{]}$$

p_v = blow out pressure at the safety valve [bar].

p_v is not to be less than 2 bar, see also Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8

γ_{dyn} = Partial safety factor for dynamic load components, to be set to 1,85.

3.2 The sea-water inlet opening edges in the shell are to be stiffened related to the stress level. The openings are to be protected by gratings.

3.3 A cathodic corrosion protection with galvanic anodes made of zinc or aluminium is to be provided in sea chests with chest coolers. For the suitably coated plates a current density of $30 \mu\text{A/m}^2$ is to be provided and for the cooling area a current density of $180 \mu\text{A/m}^2$. For details see the **BCS** Rules

4. Bilge wells

4.1 Bilge wells shall have a capacity of more than $0,2 \text{ m}^3$. Small compartments may have smaller bilge wells. For the use of manhole covers or hinged covers for the access to the bilge suction, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8. Bilge wells are to be separated from the shell.

4.2 Small wells for drainage of compartments may be arranged in the double bottom, their depth, however, shall be as small as practicable.

5. Sonar domes

The sonar dome in the forward bottom area has to be designed by direct calculation, considering the various load effects summarized in Section 5, C.3.2.

Typical cross section:




Figure 7.2 Boxshaped bilge keels

F. Special Strengthening

1. Strengthening against harbour and tug manoeuvres and berthing impacts

1.1 In those zones of the side shell which may be exposed to concentrated loads due to tug manoeuvres and fenders the plate thickness, the secondary stiffeners and the primary members must be dimensioned accordingly.

It is recommended to specially mark these areas if following formulas are dimensioned for the side shell elements.

The force induced into the hull structure may be determined for known deflection f [m] of fender and/or pile and manoeuvring speed v [m/s] of the ship by the following formula:

$$P_E = \Delta \cdot \frac{v^2}{2 \cdot f} \quad [\text{kN}]$$

$$\Delta_{\max} = 100.000 \text{ t}$$

$$M_b = P_E \cdot \ell / 8 \quad [\text{kNm}]$$

If f and/or v are not known more precisely, the force P_E may approximately be calculated as follows:

$$\begin{aligned} \Delta \leq 2100 \text{ t: } P_E &= 0,08 \cdot \Delta \quad [\text{kN}] \\ 2100 < \Delta \leq 17000 \text{ t: } P_E &= 170 \quad [\text{kN}] \\ \Delta > 17000 \text{ t: } P_E &= 0,01 \Delta \quad [\text{kN}] \end{aligned}$$




Figure 7.3 Inclined bulwark stays

1.2 For tug manoeuvres these zones are mainly the plates in way of the ship's fore and aft shoulder. The exact locations are to be identified in the shell expansion plan. The length of the strengthened areas shall not be less than approximately 5 m. The height of the strengthened areas shall extend from about 0,5 m to 2,0 m above design waterline.

For ships with $L \geq 100$ m at least one strengthened area is to be provided amidships in addition to the two strengthened areas at the ship's shoulders.

1.2.1 The plate thickness in the strengthened areas is to be determined according to Section 4, B.4.3.2.

1.2.2 The side stiffeners in the strengthened areas are to be determined according to Section 4, C.3.2 with following nominal shear force and bending moment:

$$F_S = P_E \quad [\text{kN}]$$

$$\ell = \text{Unsupported span of stiffener [m]}$$

1.2.3 The webs of primary members supporting the stiffeners in these areas are to be examined for sufficient buckling strength. The minimum thickness of web due to the action of the force P_E [kN] is not to be less than:

$$t_s = C \cdot \sqrt{\frac{P_E}{E \cdot R_{eH}}} \quad [\text{mm}]$$

$$C = 32 \text{ in general}$$

$$= 38 \text{ for web frame cutouts with free edges in way of continuous longitudinals}$$

The compressive stress in the web of primary members due to the action of the force P_E [kN] may be determined by the following formula:

$$\sigma_D = P_E / c \cdot t_s \quad [\text{MPa}]$$

$$t_s = \text{Web thickness [mm]}$$

$$c = \text{Vertical length of application of the force } P_E; \text{ if } c \text{ is not known, } c = 0,3 \text{ m may be used as a guidance value}$$

1.2.4 Longitudinally stiffened lower decks and vertically stiffened transverse bulkheads are to be investigated for sufficient buckling strength against loads acting in the ship's transverse direction (see 1.2.3).

1.3 For berthing impacts the height of strengthened area shall extend from 0,5 m below the minimum draught up to 2,0 m above the maximum draught and a waterline breadth exceeding $0,9 \cdot B$.

The areas relevant for pressure transmitted by fenders are mainly midships depending on the situation at naval bases or visited ports.

1.3.1 The side stiffeners in the strengthened areas are to be determined according to Section 4, C.3.2 with following nominal shear force and bending moment:

$$F_S = P_E \quad [\text{kN}]$$

$$M_b = \frac{P_E \cdot \ell}{16} \cdot \left(1 - \frac{\ell_E}{2 \cdot \ell} \right) [\text{kNm}]$$

ℓ = Unsupported length [m]

ℓ_E = Length of application of the force P_E ; if ℓ_E is not known, $\ell_E = 1,0$ m may be used as a guidance value, but is not to be taken greater than ℓ

1.3.2 The thickness t_s of the web of the side transverses, longitudinally stiffened lower decks and vertically stiffened transverse bulkheads in the strengthened areas is to be determined according to 1.2.3.

2. Docking

2.1 General

For ships exceeding 120 m in length, for ships of special design, particularly in the aft body and for ships with a docking load of more than 700 kN/m a special calculation of the docking forces is required.

The proof of sufficient strength can be performed either by a simplified docking calculation or by a direct docking calculation. The number and arrangement of the keel blocks shall comply with the submitted docking plan.

The partial safety factor for material resistance γ_M has to be set according to Table 4.1 LCC.

Direct calculations are required for ships with unusual overhangs at the ends or with inhomogeneous cargo distribution.

2.2 Simplified docking calculation

The local forces of the keel blocks acting on the bottom structures can be calculated in a simplified manner using the nominal keel block load q_0 . Based on these forces sufficient strength must be shown for all structural bottom elements which may be influenced by the keel block forces. The nominal keel block load q_0 is calculated as follows, see also Figure 7.4

$$q_0 = \frac{g \cdot \Delta_{\text{dock}} \cdot C}{L_{KB}} [\text{kN/m}]$$

Δ_{dock} = Ship weight during docking [t]

L_{KB} = Length of the keel block range [m]; i.e. in general the length of the horizontal flat keel

C = Weighting factor

= 1,25 in general

= 2,0 in the following areas:

- Within $0,075 \cdot L_{KB}$ from both ends of the length L_{KB}
- Below the main engine
- In way of the transverse bulkheads along a distance of $2 \cdot e$

e = Distance of plate floors adjacent to the transverse bulkheads [m]; for e no value larger than 1 m needs to be taken.

If a longitudinal framing system is used in the double bottom in combination with a centre line girder it may be assumed that the centre line girder carries 50 % of the force and the two adjacent keel block longitudinals 25 % each.

2.3 Direct docking calculation

If the docking block forces are determined by direct calculation, e.g. by a finite element calculation, considering the stiffness of the ship's body and the weight distribution, the ship has to be assumed as elastically bedded at the keel blocks. The stiffness of the keel blocks has to be determined including the wood layers. If a floating dock is used, the stiffeners of the floating dock are to be taken into consideration

3. Beach Contact

3.1 Global strength

For naval landing ships additional loads on the bottom from the contact with the landing beach at about 30 -50

% of the bottom area from the forward end must be expected. Therefore an investigation of this additional load case is required.

3.2 Local strength

Increasing of local strength in the forward bottom area shall include:

- Bottom plate thickness to be increased by 10%
- Continuous welding of primary structure
- Lugged connections or fully welded collars for longitudinals as shown in Figure 7.5.
- Transverse floors and side girders in relevant distance and sufficient number

3.3 Barwhales

Local strength of the forward bottom structure is endangered by concentrated pressure caused by uneven surface of the beach. The bottom plating can be protected against such loads if longitudinal barwhales are provided in the contact area, which should be of softer material and preferably be bolted to a special fixing structure at the bottom of the ship, see Figure 7.6.

The barwhales are to be free of projections or other discontinuities which could lead to damage of the shell plating. The ends shall be tapered at a relation of at least 1:3.




Figure 7.4 Definition of weighting factor C




Figure 7.5 Recommended connection of longitudinals




Figure 7.6 Fixing of barwhales of softer material

SECTION 8**DECKS AND WALLS**

	Page
A. General	8-2
B. Plating	8-2
C. Secondary Stiffeners.....	8-2
D. Primary Members	8-2
E. Elastic Mounting of Deckhouses.....	8-3
1. General	
2. Design loads	
3. Load cases	
4. Scantlings of rails, mounting elements and substructures	
5. Corrosion addition	
F. Helicopter Deck	8-5
1. General	
2. Design loads	
3. Plating	
4. Secondary stiffeners	
5. Primary members	

A. General

The scantlings of plating, secondary and primary members of the decks and walls are to be determined according to Section 4, B. and C.

Inclined walls with an inclination to the horizontal of less than or equal 45° will be treated as deck, see Section 6, Figure 6.5.

Vertical and horizontal watertight bulkheads and nonwatertight partitions are to be designed in accordance with Section 9.

If applicable, the requirements of Section 10 (tanks) are to be fulfilled.

B. Plating

1. Where a sheathing is used, attention is to be paid that the sheathing does not affect the steel. The sheathing is to be effectively fitted to the deck. Deformations of the deck plating have to be considered.

2. If the thickness of the strength deck plating is less than that of the side shell plating, a stringer plate is to be fitted having the width of the sheerstrake and the thickness of the side shell plating, see Section 7, B.2.

3. The welded connection between strength deck and sheerstrake may be effected by fillet welds according to Section 15, Table 15.3. Where the plate thickness exceeds approximately 25 mm, a double bevel weld connection according to Section 15, B.3.2 shall be provided for instead of fillet welds. Bevelling of the deck stringer to 0,65 times of its thickness in way of the welded connection is admissible. In special cases a double bevel weld connection may also be required, where the plate thickness is less than 25 mm.

4. The deck structure inside line of openings is to

be so designed that the compressive stresses acting in the ship's transverse direction can be safely transmitted. Proof of buckling strength is to be provided according to Section 4, F

5. Areas of structural discontinuities, e.g. at end of superstructures, have to be carefully designed and analysed. The strength deck plating is to be sufficiently extended into a superstructure. As a guidance the thickness of the superstructure side plating as well as the strength deck in a breadth of 0,1 B from the shell are to be strengthened by about 20 per cent. The strengthening shall extend over a region of about twice of the height of the end wall abaft to forward.

C. Secondary Stiffeners

1. Transverse deck beams are to be connected to the frames by brackets according to Section 4, D.4.

2. Deck beams may be attached to girders beside hatch openings by double fillet welds where there is no constraint. The length of weld is not to be less than 0,6 x depth of the section.

3. Where deck beams are to be attached to coamings of large openings and girders of considerable rigidity (e.g. box girders), brackets are to be provided.

4. Regarding the connection of deck longitudinals to transverses and bulkheads, Section 7, C.2. is to be observed.

D. Primary Members

1. Face plates are to be stiffened by tripping brackets. At girders having symmetrical face plates the tripping brackets are to be arranged alternately on both sides of the web.

2. End attachments of primary members in way of supports are to be so designed that the bending moments and shear forces can be transferred. Bulk

head stiffeners under girders are to be sufficiently dimensioned to support the girders.

3. Below strength decks girders are to be fitted in alignment with longitudinal walls of superstructures and deckhouses above, which are to extend at least over three frame spacings beyond the end points of the longitudinal walls. The girders are to overlap with the longitudinal walls by at least two frame spacings.

E. Elastic Mounting of Deckhouses

1. General

1.1 The elastic mountings are to be type approved by **BCS**. The stresses acting in the mountings which been determined by calculation are to be means of prototype testing on testing Determination of the grade of insulation for of vibrations between hull and this type approval.

1.2 The height of the mounting system is to be such that the space between deck and deckhouse bottom remains accessible for repair, maintenance and inspection purposes. The height of this space shall normally not be less than 600 mm.

1.3 For the fixed part of the deckhouse on the weather deck, a coaming height of 380 mm is to be observed, as required for coamings of doors in superstructures which do not have access openings to under deck spaces.

1.4 For pipelines, see the **BCS** Naval Ship Rules for Ship Operation Installations and Auxiliary Systems, Chapter 107, Section 8, U.

1.5 Electric cables are to be fitted in bends in order to facilitate the movement. The minimum bending radius prescribed for the respective cable is to be observed. Cable glands are to be watertight. For further details, see the **BCS** Naval Ship Rules for Electrical Installations Chapter 105, Section 12.

1.6 The following scantling requirements for rails, mountings, securing devices, stoppers and

substructures in the hull and the deckhouse bottom apply to ships in unrestricted service. For special ships and for ships intended to operate in restricted service ranges requirements differing from those given below may be applied.

2. Design loads

For scantling purposes the following design loads apply:

2.1 Weight

2.1.1 The weight G induced loads result from the weight of the fully equipped deckhouse, considering also the acceleration due to gravity and the acceleration due to the ship's movement in the seaway. The weight induced loads are to be assumed to act in the centre of gravity of the deckhouse.

The individual dimensionless accelerations a_z (vertically), a_y (transversely) and a_x (longitudinally) and the dimensionless resultant acceleration are to be determined according to Section 5, B. for $\psi = 1,0$ and $f_0 = 1,0$.

2.1.2 The support forces in the vertical and horizontal directions are to be determined for the various angles. The scantlings are to be determined for the respective maximum values.




Figure 8.1 Support forces

2.2 Water pressure and wind pressure

2.2.1 The water load due to the wash of the sea is assumed to be acting on the front wall in the longitudinal direction only. The design load is:

The water pressure is not to be less than:

- p_s at the lower edge of the front wall
- 0 at the level of the first tier above the deckhouse bottom.

2.2.2 The design wind load acting on the front wall and on the side walls is not to be less than p_w according to Section 5, I.

2.3 Load on the deckhouse bottom

The load on the deckhouse bottom is governed by the load acting on the particular deck on which the deckhouse is located. Additionally, the support forces resulting from the loads specified in 2.1 and 2.2 are to be taken into account.

2.4 Load on deck beams and girders

For designing the deck beams and girders of the deck on which the deckhouse is located the following loads are to be taken:

- Below the deckhouse: load p_u according to the pressure head due to the distance between the supporting deck and the deckhouse bottom [kN/m^2]
- Outside the deckhouse: load p_s
- Bearing forces in accordance with the load assumptions 2.1 and 2.2

3. Load cases

For design purposes the service load cases and extraordinary load cases are to be investigated separately.

3.1 Service load cases

3.1.1 Forces due to external loads acting in longitudinal, transverse and vertical direction are to be taken into account.

3.1.2 For designing the securing devices to prevent the deckhouse from being lifted, the force (in upward direction) is not to be taken less than 0,5 g G.


3.2 Extraordinary load cases

3.2.1 Forces due to collision in longitudinal direction and forces due to static heel of 45° in transverse and vertical direction are to be taken into account.

3.2.2 The possible consequences of a fire for the elastic mounting of the deckhouse are to be examined (e.g. failure of rubber elastic mounting elements, melting of glue). Even in this case, the mounting elements between hull and deckhouse bottom shall be capable of withstanding the horizontal force according to 3.2.1 in transverse direction.

3.2.3 For designing of the securing devices to prevent the deckhouse from being lifted, a force not less than the buoyancy force of the deckhouse resulting from a water level of 2 m above the freeboard deck is to be taken.

Figure 8.2 Design loads due to wind and



4. Scantlings of rails, mounting elements and substructures

4.1 General

4.1.1 The scantlings of those elements are to be determined in accordance with the load cases stipulated in 3. The effect of deflection of main girders need not be considered under the condition that the deflection is so negligible that all elements take over the loads equally.

4.1.2 Strength calculations for the structural elements with information regarding acting forces are to be submitted for approval.

4.2 Permissible stresses

4.2.1 The permissible stresses given in Table 8.1

are not to be exceeded in the rails and the steel structures of mounting elements and in the substructures (deck beams, girders of the deckhouse and the deck, on which the deckhouse is located).

4.2.2 The permissible stresses for designing the elastic mounting elements of various systems will be considered from case to case. Sufficient data are to be submitted for approval.

Table 8.1 Permissible stress in the rails and the steel structures at mounting elements and in the substructures [N/mm²]

Type of stress	Service load cases	Extra-ordinary load cases
Normal stress σ_n	0,6 R _{eH} or 0,4 R _m	0,75 R _{eH} or 0,5 R _m
Shear stress τ	0,35 R _{eH} or 0,23 R _m	0,43 R _{eH} or 0,3 R _m
Equivalent stress: $\sigma_v = \sqrt{\sigma_n^2 + 3 \cdot \tau^2}$	0,75 R _{eH}	0,9 R _{eH}

4.2.3 The stresses in the securing devices to prevent the deckhouse from being lifted are not to exceed the stress values specified in 4.2.1.

4.2.4 In screwed connections, the permissible stresses given in Table 8.2 are not to be exceeded.

4.2.5 Where turnbuckles in accordance with DIN 82008 are used for securing devices, the load per bolt under load conditions 3.1.2 and 3.2.3 may be equal to the proof load (2 times safe working load).

5. Corrosion addition

For the deck plating below elastically mounted deckhouses a minimum corrosion addition of $t_k = 2,0$ mm applies.

Table 8.2 Permissible stress in screwed connections [N/mm²]

Type of stress	Service load cases	Extra-ordinary load cases
Longitudinal tension σ_n	0,5 R _{eH}	0,8 R _{eH}
Bearing pressure p_t	1,0 R _{eH}	1,0 R _{eH}
Equivalent stress from longitudinal tension σ_n , tension τ_t due to tightening torque and shear τ , if applicable: $\sigma_v = \sqrt{\sigma_n^2 + 3 \cdot (\tau^2 + \tau_t^2)}$	0,6 R _{eH}	1,0 R _{eH}

F. Helicopter Deck

If this deck is also used for drone (UAV) operation, the loads would normally be less and therefore not form the critical case.

For take-off and landing decks for fixed wing aircraft compare Section 23, B.4.

1. General

1.1 The starting/landing zone is to be designed for the largest helicopter type expected to use the helicopter deck. For helicopter decks forming a part of the hull girder the requirements of A. - D. are to be considered too.

1.2 The following provisions in principle apply to starting/landing zones on decks or on decks of superstructures and deckhouses, see Section 23, B.3.

Note

For ships of NATO nations reference is made to publication APP2(F)/MPP2(F) "Helicopter Operations from Ships other than Aircraft Carriers (HOSTAC)".

2. Design loads

The loads as defined in Section 5, G.3.2. have to be considered separately.

3. Plating

3.1 The thickness of the plating is to be determined according to Section 4,B.

3.2 Proof of sufficient buckling strength is to be carried out in accordance with Section 4, F. for structural elements subjected to compressive stresses.

4. Secondary stiffeners

Bending moments and shear forces are to be calculated for the most unfavourable position of the helicopter with one or two loads P_E , whichever is possible, distributed on the stiffener, see Section 4,C.3.2.

5. Primary members

Ultimate strength formulations using the theory of plasticity and / or the yield line theory may be used in case of crash landing for the primary structure of the helicopter deck.

If pillars would be part of the support of the helicopter deck the deadweight of the deck and the acceleration components a_x , a_y and a_z as well as the wind load on the deck structure have to be considered for dimensioning.

SECTION 9**WATERTIGHT and NON-WATERTIGHT BULKHEADS**

	Page
A. General	9-2
1. Watertight subdivision	
2. Arrangement of Watertight Bulkheads	
3. Openings in watertight bulkheads	
4. Gastight bulkheads	
B. Scantlings of Single Plate Bulkheads	9-4
1. Design references	
2. Plating	
3. Secondary stiffeners	
4. Primary members	
C. Corrugated Bulkheads	9-5
1. Plating	
2. Section modulus	
D. Shaft Tunnels	9-5
1. General	

A. General**1. Watertight subdivision**

1.1 The watertight subdivision will be determined in general by the damage stability calculations according to Section 2, C.2.3.

1.2 Number and location of transverse bulkheads fitted in addition to those specified in Section 2, C.2.3. are to be selected to ensure sufficient transverse strength of the hull.

2. Arrangement of Watertight Bulkheads**2.1 Collision bulkhead**

2.1.1 If a collision bulkhead is arranged, it shall extend watertight up to the bulkhead deck. Steps or recesses may be permitted if the conditions of Section 2, C.2.3 are observed.

2.1.2 In ships having continuous or long super-structures, the collision bulkhead shall extend to the first deck above the bulkhead deck. The extension need not be fitted directly in line with the bulkhead below, provided the requirements of 2.1.1 are fulfilled and the scantlings of the part of the bulkhead deck which forms the step or recess are not less than required for a collision bulkhead.

Openings with weathertight closing appliances may be fitted above the bulkhead deck in the collision bulkhead and in the aforementioned step and recess. However the number of openings shall be reduced to the minimum compatible with the design and proper working of the ship.

2.1.3 No doors, manholes, access openings, or ventilation ducts are permitted in the collision bulkhead below the bulkhead deck and above the double bottom.

Where pipes are piercing the collision bulkhead below the bulkhead deck, screw down valves are to be fitted directly at the collision bulkhead.

Where such valves are fitted within the forepeak they are to be operable from above the freeboard deck. Where a readily accessible space which is not a hold space is located directly adjacent to the forepeak, e.g. a bow-thruster space, the screw down valves may be fitted within this space directly at the collision bulkhead and need not be operable from a remote position. For different space layouts alternative solution with the safety level may be agreed by **BCS**.

2.2 After peak bulkhead

2.2.1 If an after peak bulkhead is provided, it shall, in general, be so arranged that the stern tube and the rudder trunk for ships with one or three propellers are enclosed in a watertight compartment. The after peak bulkhead should extend to the bulkhead deck or to a watertight platform situated above the design waterline.

2.2.2 Where a complete after peak bulkhead is not practicable, watertight void spaces of moderate size (to be agreed with **BCS**) enclosing the stern tube entrances, providing the possibility for a second watertight sealing may be arranged. The same arrangement can be applied for the rudder trunk.

2.3 Remaining watertight bulkheads

2.3.1 The remaining watertight bulkheads, which are in general depending on the type of the naval ship and the requirements for damage stability defined in Section 2, C., have to be extended to the bulkhead deck. Wherever practicable, they shall be situated in one frame plane, otherwise those portions of decks situated between parts of transverse bulkheads are to be watertight. In horizontal parts of bulkheads the requirements for decks according to Section 8 have to be applied.

2.3.2 Bulkheads shall be fitted separating the machinery spaces from service spaces and accommodation rooms forward and aft and made watertight up to the bulkhead deck.

3. Openings in watertight bulkheads**3.1 General**

3.1.1 Type and arrangement of doors are to be submitted for approval.

3.1.2 Regarding openings in the collision bulkhead see 2.1.2 and 2.1.3.

3.1.3 In the other watertight bulkheads, watertight doors may be fitted.

3.1.4 On ships for which proof of floatability in damaged condition is to be provided, hinged doors are permitted above the most unfavourable damage waterline (equilibrium or intermediate water plane) for the respective compartment only.

3.1.5 Watertight doors are to be sufficiently strong and of an approved design. The thickness of plating is not to be less than the minimum thickness according to B.2.

3.1.6 Openings for watertight doors in the bulkheads are to be effectively framed such as to facilitate proper fitting of the doors and to guarantee perfect water tightness.

3.1.7 Tests

Before being fitted, the watertight bulkhead doors, together with their frames, are to be tested by a head of water corresponding to the bulkhead deck height plus 1,0 meter or corresponding to the most unfavourable damage water line plus 1,0 meter, if that be greater.

After having been fitted, the doors are to be hose-tested for tightness and to be subjected to an operational test. Where a hose test is not practicable because of possible damage to machinery, electrical equipment insulation or outfitting items, it may be replaced by means such as an ultrasonic leak test or an equivalent test.

A permissible leakage rate will be defined by according to test conditions and sealing type door.

3.2 Bulkhead doors**3.2.1 Hinged doors**

Hinged doors are to be provided with rubber or equivalent sealings and toggles or other approved closing appliances which guarantee a sufficient sealing pressure. If the pressure in the sealing profile is declining beyond a certain level, an alarm shall be triggered. The toggles and closing appliances are to be operable from both sides of the bulkhead. Hinges are to have oblong holes if no pneumatic activation of the sealing is provided. Bolts and bearings are to be of corrosion resistant material.

3.2.2 Sliding doors

Sliding doors are to be carefully fitted and are to be properly guided in all positions. Heat sensitive materials are not to be used in systems which penetrate watertight subdivision bulkheads, where deterioration of such systems in the event of fire would impair the watertight integrity of the bulkheads.

The closing mechanism is to be safely operable from each side of the bulkhead and from above the bulkhead deck by a power operated mechanism.

3.2.3 Operation requirements

Power-operated doors are to be capable of being reliably closed against an adverse list of 15°. The closing time, from the time each door begins to move to the time it reaches the completely closed position, shall in no case be less than 20 seconds or more than 40 seconds with the ship in upright position. Being closed from the central operating console all doors shall be in closed position within 60 seconds.

Hand-operated closing appliances are to be so designed that the doors can be closed against a list of 15° and that the closing time with the ship upright will not exceed 90 seconds.

Consideration shall also be given to the forces which may act on either side of the door as may be experienced when water is flowing through the opening

applying a static head equivalent to a water height of at least 1 m above the sill on the centreline of the door.

3.2.4 Control

For doors in watertight bulkheads with a position at or below the equilibrium or intermediate water plane due to an assumed damage, the following measures have to be provided:

Position indicators are to be provided at all remote operating positions as well as locally at both sides of the doors, to show whether the doors are open or closed and, if applicable, with all toggles fully and properly engaged. An indication should be placed locally showing that the door is in remote control mode.

Doors which are to be capable of being remotely closed are to be provided with an audible alarm, distinct from any other alarm in the area, which will sound whenever such a door is remotely closed. In areas with high ambient noise, the audible alarms are to be supplemented by visual signals at both sides of the doors.

Doors which are normally closed at sea but not provided with means of remote closure are to have notices fixed to both sides of the doors stating: "To be kept closed at sea". The use of such doors shall be authorised by the officer of the watch.

Doors which are to be permanently closed at sea are to have notices fixed to both sides stating: "Not be opened at sea". The time of opening such doors in port and closing them before the ship leaves port shall be entered in the logbook.

3.3 Penetrations through watertight bulkheads

3.3.1 Bulkhead fittings at positions at or below the equilibrium or intermediate water plane due to an assumed damage shall normally be welding studs. Fittings penetrating watertight bulkheads, are only permitted in exceptional cases. If this seems necessary, special care is to be taken to maintain water tightness.

3.3.2 For penetrations through the collision bulkhead 2.1.3 is to be observed.

4. Gastight bulkheads

4.1 Gastight bulkheads have to be designed like watertight bulkheads or tank walls, respectively.

4.2 Watertight bulkheads must generally not be gastight. Special additional efforts have to be made for the tightness of the connections of the construction elements.

4.3 Gastight bulkhead penetrations have to be approved by **BCS**. See "Regulations for the Performance of the Type Tests Part 2 - Test Requirements for Sealing Systems of Bulkhead and Deck Penetrations Section 3.D".

4.4 For the final testing of the gas tightness of a bulkhead a special test procedure has to be agreed. This procedure may include the complete space to be gastight or may be concentrated on welding joints of the bulkhead. The regulations of the Naval Authority have to be observed.

B. Scantlings of Single Plate Bulkheads

1. Design references

1.1 The scantlings of plating, secondary and primary members of the bulkheads are to be determined according to Section 4, B. and C.

1.2 For longitudinal bulkheads the design stresses according to Section 6, D.4. and the stresses due to local loads are to be considered.

1.3 For inclined bulkheads with an inclination to the horizontal of less than or equal 45° the requirements according to Section 8 (deck) are to be fulfilled.

1.4 Where spaces are intended to be used as tanks, their bulkheads and walls are also to comply with the requirements of Section 10.

2. Plating

2.1 Stern tube bulkheads are to be provided with a strengthened plate in way of the stern tube.

2.2 In areas where concentrated loads due to ship manoeuvres at naval bases may be expected, the buckling strength of bulkhead plate fields directly attached to the side shell, is to be examined according to Section 7, F.1.

3. Secondary stiffeners

3.1 The end attachment of secondary stiffeners shall comply with Section 4, D.

3.2 Unbracketed bulkhead stiffeners are to be connected to the decks by welding. The length of weld is to be at least 0,6 x depth of the section.

4. Primary members

4.1 The effective width is to be determined according to Section 4, E.

4.2 Frames are to be connected to transverse deck beams by brackets according to Section 4, D,4.

4.3 The transverse structure of superstructures and deckhouses is to be sufficiently dimensioned for stiffness by a suitable arrangement of end bulkheads, web frames, steel walls of cabins and casings, or by other measures.

4.4 For the design of girders and web frames of bulkheads plastic hinges can be taken into account, see Section 4, C.4.1

C. Corrugated Bulkheads.

In addition to B. following requirements are to be considered for corrugated bulkheads:

1. Plating

The greater one of the values b or s [m] according to 2. is to be taken into account for the spacing a.


2. Section modulus

The required section modulus of a corrugated bulkhead element is to be determined by direct calculation. For the spacing a, the width of an element e [m] according to Figure 9.1 is to be taken. For the end attachment see Section 4, D.3.

The actual section modulus of a corrugated bulkhead element is to be assessed according to the following formula (refer also to Figure 9.1):

$$W = t \cdot d \cdot (b + s/3) \quad [\text{cm}^3]$$

For flanges of corrugated elements subject to compressive stresses the effective width according to Section 4, F.2.2 has to be considered.



e	=	width of element	[cm]
b	=	breadth of faceplate	[cm]
s	=	breadth of web plate	[cm]
d	=	distance between face plates	[cm]
t	=	plate thickness	[cm]
α	≥	45°	

Figure 9.1 Dimensions of a corrugated bulkhead element

D. Shaft Tunnels

1. General

1.1 Shaft and stuffing box are to be accessible. Where one or more compartments are situated between

stern tube bulkhead and engine room, a watertight shaft tunnel is to be arranged for ships with one or three propellers. The size of the shaft tunnel is to be adequate for service and maintenance purposes.

1.2 The access opening between engine room and shaft tunnel is to be closed by a watertight sliding door complying with the requirements according to A.3.2.2. For extremely short shaft tunnels watertight doors between tunnel and engine room may be dispensed with subject to special approval.

SECTION 10**TANK STRUCTURES**

	Page
A. General	10-2
1. Subdivision of Tanks	
2. Air, overflow and sounding pipes	
3. Forepeak tank	
4. Separation of oil fuel tanks from tanks for other liquids	
5. Double bottom tanks	
6. Potable water tanks	
7. Cross references	
B. Scantlings	10-3
1. General	
2. Plating	
3. Stiffeners and girders	
C. Detached Tanks	10-3
1. Plating	
2. Arrangement	
D. Testing for Tightness	10-4

A. General

1. Subdivision of Tanks

1.1 In tanks extending over the full breadth of the ship intended to be used for partial filling, (e.g. oil fuel and fresh water tanks), at least one longitudinal bulkhead is to be fitted, which may be a swash bulkhead.

1.2 Where the forepeak is intended to be used as tank, at least one complete or partial longitudinal swash bulkhead is to be fitted, if the tank breadth exceeds 0,5 B or 6 m, whichever is the greater.

When the afterpeak is intended to be used as tank, at least one complete or partial longitudinal swash bulkhead is to be fitted. The largest breadth of the liquid surface should not exceed 0,3 B in the aft peak.

1.3 Peak tanks exceeding 0,06 L or 6 m in length, whichever is greater, shall be provided with a transverse swash bulkhead.

2. Air, overflow and sounding pipes

Each tank is to be fitted with air pipes, overflow pipes and sounding pipes. The air pipes are to be led to above the exposed deck. The arrangement is to be such as to allow complete filling of the tanks. See also Section 19, F.

The sounding pipes are to be led to the bottom of the tanks, see also Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8, R.

3. Forepeak tank

Oil is not to be carried in a forepeak tank.

4. Separation of oil fuel tanks from tanks for other liquids

4.1 Oil fuel tanks are to be separated from tanks for lubricating oil, hydraulic oil and potable water by cofferdams.

4.2 Upon special approval on small ships the arrangement of cofferdams between oil fuel and lubricating oil tanks may be dispensed with provided that:

- The common boundary is continuous, i.e. it does not abut at the adjacent tank boundaries, see Figure 10.1
- Where the common boundary cannot be constructed continuously according to Figure 10.1, the fillet welds on both sides of the common boundary are to be welded in two layers and the throat thickness is not to be less than $0,5 \times t$ (t = plate thickness).
- Stiffeners or pipes do not penetrate the common boundary
- The corrosion addition t_k for the common boundary is not less than 1,0 mm.
- Common boundaries and the above mentioned details are clearly indicated in the drawings submitted for approval.




Figure 10.1 Welding at not continuous tank boundaries

4.3 Oil fuel tanks adjacent to lubricating oil circulation tanks are subject to the provisions of Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8, G. in addition to the requirements stipulated in 4.2 above.

5. Double bottom tanks

5.1 Where practicable, lubricating oil discharge tanks or circulating tanks shall be separated from the shell.

5.2 Manholes for access to fuel oil double bottom tanks situated under cargo oil tanks are not permitted in cargo oil tanks nor in the engine rooms.

6. Potable water tanks

6.1 Potable water tanks shall be separated from tanks containing liquids other than potable water, ballast water, distillate or feed water.

6.2 In no case sanitary arrangement or corresponding piping are to be fitted directly above the potable water tanks.

6.3 Manholes arranged in the tank top are to have sills.

6.4 If pipes carrying liquids other than potable water are to be led through potable water tanks, they are to be fitted in a pipe tunnel.

6.5 Air and overflow pipes of potable water tanks are to be separated from pipes of other tanks.

7. Cross references

7.1 For pumping and piping, see also Chapter 107- Ship Operation Installations and Auxiliary Systems, Section 8. For oil fuel tanks see also Chapter 107 – Ship Operation Installations and Auxiliary Systems, Section 8, G.

7.2 Where tanks are provided with cross flooding arrangements the increase of the pressure head is to be taken into consideration.

B. Scantlings**1. General**

1.1 The scantlings of plating, secondary and primary members of the boundaries of tanks are to be determined according to Section 4, B. and C.

1.2 For longitudinal bulkheads the design stresses according to Section 6, D.4. and the stresses due to local loads are to be considered.

1.3 For inclined bulkheads with an inclination to the horizontal of less than or equal 45° see Section 8.

1.4 If the boundaries of tanks are formed by integrated structural elements of the ship, their dimensioning has to follow the definitions in the Sections for the relevant parts in addition to this Section.

1.5 Detached tanks, which are independent from the ship's structure, are to be designed according to C.

2. Plating

The minimum thickness is 3,0 mm, for the corrosion addition see Section 4, B.3.

3. Stiffeners and girders

3.1 The buckling strength of the webs is to be checked according to Section 4, F.

3.2 The section moduli and shear areas of horizontal stiffeners and girders are to be determined according to Section 4, Table 4.4.

C. Detached Tanks**1. Plating**

1.1 The minimum thickness is 3,0 mm, for the corrosion addition see Section 4, B.3. For stainless steel the minimum thickness can be reduced to 2,5 mm.

1.2 For corrugated tank walls see Section 9, C.

1.3 Special consideration has to be given to the avoidance of vibrations.

2. Arrangement

2.1 Detached tanks are to be adequately secured against forces due to the ship's motions. The forces can be calculated considering the acceleration components given in Section 5, B.

2.2 Detached tanks are to be provided with anti-floatation devices. It is to be assumed that the flooding reaches the design water line, for ships with proven damage stability the extreme damage waterline. The stresses in the anti-floatation devices caused by the floatation forces are not to exceed the material's yield stress.

2.3 Fittings and pipings on detached tanks are to be protected by battens. Gutterways are to be fitted on the outside of tanks for draining any leakage oil.

D. Testing for Tightness

1. Testing of fuel oil, ballast, trimming, feed water, fresh water and anti-rolling tanks is to be effected by a combination of a leak test by means of air pressure and an operational test by means of water or the liquid for which the tank is intended to be used. The air pressure is not to exceed 0,2 bar gauge. The increased risk of accident while the tanks are subjected to the air pressure is to be observed.

2. Where one tank boundary is formed by the ship's shell, the leak test is to be carried out before launching. For all other tanks leak testing may be carried out after launching. Erection welds as well as welds of assembly openings are to be coated **(1)** after the leak test is carried out. This applies also to manual weld connections of bulkheads with the other tanks boundaries and of collaring arrangements at intersections of tank boundaries and e.g. frames, beams, girders, pipes etc. If it is ensured that in adjacent tanks the same type of liquid is carried, e.g. in adjacent ballast tanks, the above mentioned weld connections may be coated **(1)** prior to the leak test.

All other welded connections in tank boundaries may be coated prior to the leak test if it is ensured by suitable means, e.g. by visual examination of the welded connections that the connections are completely welded and the surfaces of the welds do not exhibit cracks or pores.

3. Where the tanks are not subjected to the leak test as per 2. but are leak tested with water the bulk-heads are, in general, to be tested from one side. The testing should be carried out prior to launching or in the dock. Subject to approval by **BCS**, the test may also be carried out after launching. Water testing may be carried out after application of a coating, provided the visual inspection as per 2. above the results are not noted.

4. The maximum test pressure with freshwater at tank top is:

$$p_{\text{test}} = \rho \cdot g \cdot h_2 \text{ [kN/m}^2\text{]}$$

g = Acceleration due to gravity

$$= 9,81 \text{ m/s}^2$$

ρ = Density of liquid [t/m³]

h_2 = Distance [m] from tank top to top of overflow

= Not less than 2,5 m or 10 Δp , respectively

Δp = Additional pressure component [bar] created by overflow systems, replenishment at sea, etc., see Section 5, F.

5. The operational test may be carried out when the ship is afloat or during the trial trip. For all tanks the proper functioning of filling and suction lines and of the valves as well as functioning and tightness of the vent, sounding and overflow pipes are to be tested.

6. For testing procedure of watertight compartments, see **BCS** Rules, Part A, Chapter Section 3,E.

(1) Shop primers are not regarded as a coating within the scope of these requirements.

SECTION 11**STEM AND STERNFRAME STRUCTURES**

	Page
A. Plate Stem and Bulbous Bow	11-2
B. Stern frame.....	11-2
1. Stern tube	
2. Aft structure	
C. Propeller Brackets	11-2
1. General	
2. Symbols and definitions	
3. Double arm propeller brackets	
4. Single arm propeller brackets	
5. Intermediate struts	
6. Boss	

A. Plate Stem and Bulbous Bow

1. The thickness of welded plate stems is not to be less than:

$$t = 16,3 \cdot a_B \cdot \sqrt{\frac{p \cdot \gamma_m}{f_p R_{eH}}} + t_K \quad [\text{mm}]$$

$$p = 3,5 \left(0,3 \cdot v_0 + 0,6 \cdot \sqrt{L} \right)^2 \quad [\text{kPa}]$$

a_B = Spacing of fore-hooks [m]

The plate thickness must not be less than the required thickness according to Section 7.

The extension ℓ of the stem plate from its trailing edge aftwards must not be smaller than:

$$\ell = 70 \cdot \sqrt{L} \quad [\text{mm}]$$

2. Starting from 600 mm above the load water-line up to $T + c_0$, the thickness may gradually be reduced to $0,8 t$ or the thickness according to Section 7, whichever is greater.

3. Plate stems and bulbous bows shall be stiffened as shown in Fig. 11.1.

Note

Large bulbous bows may be subjected to horizontal dynamic pressure p_{Sdyn} , acting from one side only, see Section 5, C.1..

For the effective area of p_{Sdyn} , the projected area of the z-x-plane from forward to the collision bulkhead may be assumed.

B. Stern frame

1. Stern tube

The stern tube is to be sufficiently supported by the ship's stern structure.




Figure 11.1 Arrangement of fore hooks and cant frames at the bow

2. Aft structure

The plate thickness shall not be less than the required thickness according to Section 7.

The aft structure in way of the propeller has to be investigated for the enforced vibrations by the propeller.

C. Propeller Brackets

1. General

The strut axes should intersect in the axis of the propeller shaft as far as practicable. The angle between the two struts shall be in the range of 60° to

120°. An angle of approximately 90° is recommended where 3- or 5-bladed propellers are fitted or approximately 70° or 110° in case of 4-bladed propeller, respectively.

The struts are to be extended through the shell plating and are to be attached in an efficient manner to the frames and plate floors respectively. The construction in way of the shell is to be carried out with special care.

A watertight compartment of moderate size is to be provided within the strut structure inside the shell to reduce the effect of flooding in case of damage.

In case of welded connection, the struts are to have a weld flange or a thickened part or are to be connected with the shell plating in another suitable manner. The requirements of Section 15, B.4.3 are to be observed.

Welds between propeller brackets and bottom plate are to be tested by NDT adequately.

The struts are to be well rounded at fore and aft end at the transition to the hull as well as at the boss.

If propulsion system elements will be fastened to the hull by means of a cast-resin, fitting is to be carried out according to the specification by the cast-resin manufacturer and in the presence of a representative of manufacturer or an authorized person as well as the **BCS** Surveyor.

2. Symbols and definitions

If applicable, the corresponding drawing shall consist following information for each type of propeller bracket:

P_w = Rated power in kW

n = Shaft speed at rated power, in min^{-1}

d_a = Actual outer propeller shaft diameter, in mm

d_i = Actual inner shaft diameter, in mm

L_0 = Distance between propeller and aft bearing, in m

L_1 = Distance between bearings, in m

l = Distance between centreline of shaft boss and hull support, in m

Δl = Distance between centreline of shaft boss and the intersection of the strut axes, in m

β = Angle between centreline of shaft and strut axis, in degree

3. Double arm propeller brackets

3.1 The scantlings of solid or welded double arm shaft struts each are to be determined by following formulas:

t = Strut thickness [mm]

$$= \frac{c_1 \cdot d_a}{\sin \beta}$$

A = Area of strut section [cm^2]

$$= \frac{c_2 \cdot d_0^2}{100} \sqrt{2 \cos 2\beta} \cdot \left(1,0 + \frac{\Delta l}{2 \cdot l} \right)$$

c_1 = 0,32 for steel

= 0,54 for aluminium alloys

c_2 = 0,30 for steel

= 0,86 for aluminium alloys

$$d_0 = \sqrt[3]{\frac{d_a^4 - d_i^4}{d_a}}, \text{ but not less than}$$

$$110 \cdot \sqrt[3]{\frac{P_w}{n \cdot \left(1 - \left(\frac{d_i}{d_a} \right)^4 \right) (R_m + 160)}}$$

The thickness of the plating of constructed propeller brackets shall not be less than:

$$t_{\min} = 0,1 \cdot d_a \text{ [mm]}$$

4. Single arm propeller brackets

4.1 In addition to 3.1 the section modulus shall not be less than:

W = Section modulus of strut [cm³]

$$= \frac{c \cdot l}{1000} \cdot d_0^{2,5} \sqrt{n_0} \cdot \frac{L}{L_1}$$

n_0 = n , but is not to be taken less than 350 min⁻¹

L = $L_0 + L_1$

c_3 = 0,102 for welded steel connection

= 0,291 for welded aluminium connection

Built-up (welded construction) shaft struts should not be used for single arm struts.

For cast resin foundation the value of factor c_3 may be reduced to

c_3' = 0,076 for steel struts which are not welded in way of foundation

= 0,262 for aluminium struts which are not welded in way of foundation

An increased strut length l (in comparison with welded strut joints) is generally to be taken into account for cast resin foundations.

For propeller brackets consisting of one strut only a vibration and fatigue analysis has to be carried out and submitted for approval.

A crack detection of the propeller brackets shall be employed every time when the ship is in dry-dock or on a slipway.

5. Intermediate struts

5.1 The scantlings of intermediate struts may be determined by following formulas:

$$t = \frac{c_1 \cdot d_a}{\sin \beta} \cdot \sqrt{\frac{L_0}{L_1}} \quad [\text{mm}]$$

$$A = \frac{c_2 \cdot d_0^2}{110} \sqrt{2 + \cos(2\beta)} \cdot \left(1,0 + \frac{\Delta l}{2 \cdot l} \right) \cdot \frac{L_0}{L_1} \quad [\text{cm}^2]$$

5.2 and in addition for single struts:

$$W = \frac{c_3}{1150} \cdot l \cdot d_0^{2,5} \sqrt{n_0} \cdot \frac{L \cdot L_0}{L_1^2} \quad [\text{cm}^3]$$

6. Boss

The length of the boss is determined by the necessary length of the bearing for the propeller shaft according to Chapter 104, Section 5, D.5.

The wall thickness of the boss shall not be less than $0,2 \cdot d_a$.

SECTION 12

RUDDER AND MANOEUVRING ARRANGEMENT

	Page
A. General, Definitions.....	12-2
1. Scope	
2. Manoeuvring arrangement	
3. Structural details	
4. Size of rudder area	
5. Materials	
6. Definitions	
B. Rudder Force and Torque.....	12-4
1. Rudder force and torque for normal rudders	
2. Rudder force and torque for rudder blades with cut-outs (semi-spade rudders)	
C. Scantlings of the Rudder Stock.....	12-6
1. Rudder stock diameter	
2. Strengthening of rudder stock	
3. Analysis	
4. Rudder trunk	
D. Rudder Horn of Semi Spade Rudders.....	12-10
E. Rudder Couplings	12-12
1. General	
2. Horizontal couplings	
3. Cone couplings	
F. Rudder Body, Rudder Bearings	12-15
1. Strength of rudder body	
2. Rudder plating	
3. Transmitting of the rudder torque	
4. Rudder bearings	
5. Pintles	
6. Guidance values for bearing clearances	
G. Design Yield Moment of Rudder Stock.....	12-18
H. Stopper, Locking Device.....	12-18
1. Stopper	
2. Locking device	
I. Fin Stabilizers	12-19
1. General	
2. Integration into the ship's structure	

A. General, Definitions

1. Scope

Rudder stock, rudder horn, rudder coupling, rudder bearings and the rudder body are dealt with in this Section. The steering gear is to comply with Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 2.

2. Manoeuvring arrangement

2.1 Each naval ship is to be provided with a manoeuvring arrangement which will guarantee sufficient manoeuvring capability.

2.2 The manoeuvring arrangement includes all parts from the rudder and steering gear to the steering position necessary for steering the ship.

For special types of manoeuvring systems, like cycloidal propellers, azimuthing propulsors, etc. see Chapter 104 - Propulsion Plants, Section 7. Regarding the integration of the foundations for azimuthing propulsors into the hull see Section 14, B.2.4.

2.3 The steering gear compartment shall be readily accessible and, as far as practicable, separated from the machinery space.

2.4 For ice-strengthening see Section 13.

2.5 Rudders and manoeuvring arrangements are to be built in a shock safe way if Class Notation **SHOCK** shall be assigned.

3. Structural details

3.1 Effective means are to be provided for supporting the weight of the rudder body without excessive bearing pressure, e.g. by a rudder carrier attached to the upper part of the rudder stock. The hull structure in way of the rudder carrier is to be

suitably strengthened.

3.2 Suitable arrangements are to be provided to prevent the rudder from lifting.

3.3 The rudder stock is to be carried through the hull either enclosed in a watertight trunk, or glands are to be fitted above the deepest load waterline, to prevent water from entering the steering gear compartment and the lubricant from being washed away from the rudder carrier. If the top of the rudder trunk is below the deepest waterline two separate stuffing boxes are to be provided.

Note:

The following measures are recommended regarding:

Profile selection:

- *Use the appropriate profile shape and thickness.*
- *Use profiles with a sufficiently small absolute value of pressure coefficient for moderate angles of attack (below 5°). The pressure distribution around the profile should be possibly smooth. The maximum thickness of such profiles is usually located at more than 35 % behind the leading edge.*
- *Use a large profile nose radius for rudders operating in propeller slips.*
- *Computational Fluid Dynamic (CFD) analysis for rudder considering the propeller and ship wake can be used.*

Rudder sole cavitation:

- *Round out the leading edge curve at rudder sole.*

Propeller hub cavitation:

- *Fit a nacelle (body of revolution) to the rudder at the level of the propeller hub. This nacelle functions as an extension of the propeller hub.*

Cavitation at surface irregularities:

- Grind and polish all welds.
- Avoid changes of profile shape. Often rudders are built with local thickenings (bubbles) and dents to ease fitting of the rudder shaft. Maximum changes in profile shape should be kept to less than two percent of profile thickness.

Gap cavitation:

- Round out all edges of the part around the gap.
- Gap size should be as small as possible.
- Place gaps outside of the propeller slipstream.

4. Size of rudder area

The size of the total movable area of the rudder A has to be chosen in order to achieve sufficient manoeuvring capability according to the priority tasks of the naval ship.

For semi-spade rudders 50 % of the projected area of the rudder horn may be included into the rudder area A .

When estimating the rudder area A , the requirements specified in B. 1. should be taken into consideration.

5. Materials

5.1 For materials for rudder stock, pintles, coupling bolts etc. see **BCS** Rules Part A, Chapter Materials.

5.2 In general materials having a minimum yield stress R_{eH} of less than 200 N/mm² and a minimum tensile strength of less than 400 N/mm² or more than 900 N/mm² shall not be used for rudder stocks, pintles, keys and bolts. The requirements of this Section are based on a material's minimum yield stress R_{eH} of 235 N/mm². If material is used having a R_{eH} differing from 235 N/mm², the material factor k_r is to be determined as follows:

$$k_r = \left[\frac{235}{R_{eH}} \right]^{0,75} \quad \text{for } R_{eH} > 235 \text{ N/mm}^2$$

$$k_r = \frac{235}{R_{eH}} \quad \text{for } R_{eH} \leq 235 \text{ N/mm}^2$$

R_{eH} = Minimum yield stress of material used [N/mm²], see Section 3

R_{eH} = Is not to be taken greater than 0,7 · R_m or 450 N/mm², whichever is less. Steels with higher strength properties may be used if the C-content is less than 0,23 %

R_m = Tensile strength of the material used [N/mm²] according to Section 3.

5.3 Before significant reductions in rudder stock diameter due to the application of steels with R_{eH} exceeding 235 N/mm² are granted, **BCS** may require the evaluation of the elastic rudder stock deflections. Large deflections should be avoided in order to avoid excessive edge pressures in way of bearings.

5.4 The permissible stresses given in F.1. are applicable for normal strength hull structural steel. When higher strength steels are used, higher values may be used which will be fixed in each individual case.

6. Definitions




Figure 12.1 Rudder area

C_R = Rudder force [kN]

$$C_R = 0,132 \cdot A \cdot v^2 \cdot \kappa_1 \cdot \kappa_2 \cdot \kappa_3 \cdot \kappa_t \quad [\text{kN}]$$

Q_R = Rudder torque [kNm]

κ_1 = Coefficient, depending on the aspect ratio Λ

A = Total movable area of the rudder [m^2],

= $(\Lambda + 2)/3$, where Λ need not be taken greater than 2

A_t = A + area of a rudder horn, if any [m^2]

κ_2 = Coefficient, depending on the type of the rudder and the rudder profile according to Table 12.1

A_f = Portion of rudder area located ahead of the rudder stock axis [m^2]

b = Mean height of rudder area [m]

κ_3 = Coefficient, depending on the location of the rudder

c = Mean breadth of rudder area [m], see Figure. 12.1

= 0,8 for rudders outside the propeller jet

Λ = Aspect ratio of rudder area A_t

= 1,0 elsewhere, including also rudders within the propeller jet

$$\Lambda = \frac{b^2}{A_t}$$

v = v_0 for ahead condition [kn], but need not to be taken greater than $2/3 (v_0 + 2 \sqrt{L})$


$$= \frac{v_0 + 20}{3} \quad \text{if } v_0 \text{ is less than } 10 \text{ kn}$$

= v_a for astern condition

v_a = As defined in Section 1,B.; if the astern speed v_a is less than $0,4 \cdot v_0$ or 6 kn, whichever is less, determination of rudder force and torque for astern condition is not required. For greater astern speeds special evaluation of rudder force and torque as a function of the rudder angle may be required. If no limitations for the rudder angle at astern condition are stipulated, the factor κ_2 is not to be taken less than given in Table 12.1 for astern condition.

γ_m = Partial safety factor for structural resistance, see Section 4, Table 4.1

Table 12.1 Coefficient κ_2 for different types of rudder profiles

Type of rudder/ profile	κ_2	
	Ahead condition	Astern condition
NACA-00 serie Göttingen profiles 	1,1	1,4
flat side profiles 	1,1	1,4
hollow profiles 	1,35	1,4
high lift rudders 	1,7	to be specially considered; if not known: 1,7
mixed profiles (e. g. HSVA)	1,21	1,4

B. Rudder Force and Torque

1. Rudder force and torque for normal rudders

1.1 The rudder force is to be determined according to the following formula:

κ_t = coefficient depending on the thrust load coefficient C_{Th} , see Chapter 104 - Propulsion Plants, Section 7, C.

= 1,0 normally

In special cases for thrust load coefficients $C_{Th} > 1,0$, determination of κ_t according to the following formula may be required:

$$\kappa_t = \frac{C_R (C_{Th})}{C_R (C_{Th} = 1,0)}$$

1.2 The rudder torque is to be determined by the following formula:

$$Q_R = C_R \cdot r \text{ [kNm]}$$

$$r = c (\alpha - k_b) \text{ [m]},$$

$$\alpha = 0,33 \text{ for ahead condition,}$$

$$= 0,66 \text{ for astern condition (general),}$$

$$= 0,75 \text{ for astern condition (hollow profiles).}$$

For parts of a rudder behind a fixed structure such as a rudder horn:

$$\alpha = 0,25 \text{ for ahead condition,}$$

$$= 0,55 \text{ for astern condition.}$$

For high lift rudders α is to be specially considered. If not known, $\alpha = 0,4$ may be used for the ahead condition

k_b = Balance factor as follows:

$$k_b = \frac{A_f}{A}$$

$$= 0,08 \text{ for unbalanced rudders,}$$

$$r_{min} = 0,1 \cdot c \text{ [m] for ahead condition.}$$

Effects of the provided type of rudder / profile on choice and operation of the steering gear are to be observed.

2. Rudder force and torque for rudder blades with cut-outs (semi-spade rudders)

2.1 The total rudder force C_R is to be calculated according to 1.1. The pressure distribution over the rudder area, upon which the determination of rudder

torque and rudder blade strength are to be based, is to be derived as follows:

The rudder area may be divided into two rectangular or trapezoidal parts with areas A_1 and A_2 , see Figure 12.2.

The resulting force of each part may be taken as:

$$C_{R1} = C_R \frac{A_1}{A} \text{ [kN]}$$

$$C_{R2} = C_R \frac{A_2}{A} \text{ [kN]}$$

2.2 The resulting torque of each part may be taken as:

$$Q_{R1} = C_{R1} \cdot r_1 \text{ [kNm]}$$

$$Q_{R2} = C_{R2} \cdot r_2 \text{ [kNm]}$$

$$r_1 = c_1 (\alpha - k_{b1}) \text{ [m]}$$

$$r_2 = c_2 (\alpha - k_{b2}) \text{ [m]}$$

$$k_{b1} = \frac{A_{1f}}{A_1}$$

$$k_{b2} = \frac{A_{2f}}{A_2}$$

A_{1f}, A_{2f} see Figure 12.2

$$c_1 = \frac{A_1}{b_1}$$

$$c_2 = \frac{A_2}{b_2^2}$$

b_1, b_2 = mean heights of the partial rudder areas A_1 and A_2 , (see Figure 12.2).

2.3 The total rudder torque is to be determined according to the following formulae:

$$Q_R = Q_{R1} + Q_{R2} \text{ [kNm] or}$$

$$Q_{Rmin} = Q_R \cdot r_{1,2min} \text{ [kNm]}$$

$$r_{1,2min} = \frac{0,1}{A} (c_1 \cdot A_1 + c_2 \cdot A_2) \text{ [m]}$$

for ahead condition

The greater value is to be taken.




Figure 12.2 Rudder areas

C. Scantlings of the Rudder Stock

1. Rudder stock diameter

1.1 The diameter of the rudder stock for transmitting the rudder torque is not to be less than:

$$D_t = 4,2 \sqrt[3]{Q_R \cdot k_r} \quad [\text{mm}]$$

Q_R = rudder moment, see B.1.2, B.2.2 and B.2.3

k_r = see A.5.2

The related torsional stress is:

$$\tau = \frac{68}{k_r} \quad [\text{N/mm}^2]$$

1.2 The steering gear is to be determined according to Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 2 for the rudder torque Q_R as required in B.1.2, B.2.2 or B.2.3 and under consideration of the frictional losses at the rudder bearings.

1.3 In case of mechanical steering gear the diameter of the rudder stock in its upper part which is only intended for transmission of the torsional moment from the auxiliary steering gear may be 0,9 D_t . The length of the edge of the quadrangle for the auxiliary tiller must not be less than 0,77 D_t and the height not less than 0,8 D_t .

1.4 The rudder stock is to be secured against axial sliding. The degree of the permissible axial clearance depends on the construction of the steering engine and on the bearing.

2. Strengthening of rudder stock

If the rudder is so arranged that additional bending stresses occur in the rudder stock, the stock diameter has to be suitably increased. The increased diameter is, where applicable, decisive for the scantlings of the coupling.

For the increased rudder stock diameter the equivalent stress of bending and torsion is not to exceed the following value:

$$\sigma_v = \sqrt{\sigma_b^2 + 3\tau^2} \leq \frac{118}{k_r} \quad [\text{N/mm}^2]$$

Bending stress:

$$\sigma_b = \frac{1,02 \cdot M_b}{D_1^3} 10^7 \quad [\text{N/mm}^2]$$

M_b = Bending moment at the neck bearing in [kNm],

Torsional stress:

$$\tau = \frac{5,1 \cdot Q_R}{D_1^3} 10^6 \quad [\text{N/mm}^2]$$

D_1 = Increased rudder stock diameter [mm]

The increased rudder stock diameter may be determined by the following formula:

$$D_1 = D_t \sqrt[6]{1 + \frac{4}{3} \left[\frac{M_b}{Q_R} \right]^2}$$

Q_R = rudder moment, see B.1.2, B.2.2 and B.2.3

D_t = see 1.1.

Note:

Where a double-piston steering gear is fitted, additional bending moments may be transmitted from the steering gear into the rudder stock. These additional bending moments are to be taken into account for determining the rudder stock diameter.

3. Analysis

$$p_{R20} = \frac{C_{R1}}{\ell_{20}} \quad [\text{kN/m}]$$

3.1 General

The evaluation of bending moments, shear forces and support forces for the system rudder - rudder stock may be carried out for some basic rudder types as shown in Figures 12.3 and 12.4 as outlined in 3.2 - 3.3.

C_R, C_{R1}, C_{R2} see B.1 and B.2.

Z = spring constant of support in the rudder horn

$$Z = \frac{1}{f_b + f_t} \quad [\text{kN/m}]$$

f_b = unit displacement of rudder horn [m] due to a unit force of 1 kN acting in the centre of support

$$f_b = 0,21 \frac{d^3}{I_n} \quad [\text{kN/m}]$$

(guidance value for steel)

3.2 Data for the analysis

$\ell_{10} - \ell_{50}$ = lengths of the individual girders of the system [m]

$I_{10} - I_{50}$ = moments of inertia of these girders [cm^4]

Load on rudder body (general):

$$p_R = \frac{C_R}{\ell_{10}} \quad [\text{kN/m}]$$

I_n = moment of inertia of rudder horn around the x-axis at $d/2$ [cm^4], see also Figure 12.3

Load on semi-spade rudders:

$$p_{R10} = \frac{C_{R2}}{\ell_{10}} \quad [\text{kN/m}]$$

f_t = unit displacement due to a torsional moment of the amount $1 \cdot e$ [kNm]




Figure 12.3 Semi-spade rudder




Figure 12.4 Spade-rudder

$$f_t = \frac{d \cdot e^2}{G \cdot J_t}$$

$$f_t = \frac{d \cdot e^2 \cdot \sum u_i / t_i}{3,17 \cdot 10^8 \cdot F_T^2} \quad [\text{m/kN}] \quad \text{for steel}$$

G = Modulus of rigidity

G = $7,92 \cdot 10^7$ kN/m² for steel

J_t = Torsional moment of inertia [m⁴]

F_T = Mean sectional area of rudder horn [m²]

u_i = Breadth [mm] of the individual plates forming the mean horn sectional area

t_i = Plate thickness within the individual breadth u_i [mm]

e, d = Distances [m] according to Figure 12.3

3.3 Moments and forces to be evaluated

3.3.1 The bending moment M_R and the shear force Q_1 in the rudder body, the bending moment M_b in the neck bearing and the support forces B_1, B_2, B_3 are to be evaluated, $B_1 - B_3$: see Figures 12.3 and 12.4.

The so evaluated moments and forces are to be used for the stress analyses required by 2. and F.1. of this Section and for the calculation of the rudder horn, see D.

3.3.2 For spade rudders the moments and forces may be determined by the following formulae:

$$M_b = C \ell_R \left[\frac{1}{20} + \frac{\ell_{10}(2x_1 + x_2)}{3(x_1 + x_2)} \right] \quad [\text{k Nm}]$$

$$B_3 = \frac{M_b}{\ell_{30}} \quad [\text{kN}]$$

$$B_2 = C_R + B_3 \quad [\text{kN}]$$

4. Rudder trunk

4.1 Where the rudder stock is arranged in a trunk in such a way that the trunk is stressed by forces due to rudder action, the scantlings of the trunk are to be as such that the equivalent stress due to bending and shear does not exceed $0,35 \cdot R_{eH}$ of the material used.

For the calculation of the bending stress, the span to be considered is the distance between the mid-height of the lower rudder stock bearing and the point where the trunk is clamped into the shell or the bottom of the skeg.

4.2 The weld at the connection between the rudder trunk and the shell or the bottom of the skeg is to be full penetration.

Non destructive tests are to be conducted for all welds.

4.3 The minimum thickness of the shell or the bottom of the skeg is to be 0,4 times the wall thickness of the trunk at the connection.

The fillet shoulder radius is to be ground. The radius is to be as large as practicable but not less than 0,7 times the wall thickness of the trunk at the connection, if the wall thickness is greater than 50 mm. In case of smaller wall thickness, the radius shall be not less than 35 mm.

4.4 Alternatively a fatigue strength calculation based on the structural stress (hot spot stress) (see Section 17, A.2.6) can be carried out.

4.4.1 In case the rudder trunk is welded directly into the skeg bottom or shell, hot spot stress has to be determined acc. to Section 17, C.

In this case FAT class $\Delta\sigma_R = 100$ has to be used, see Section 17, C.3.

4.4.2 In case the trunk is fitted with a weld flange, the stresses have to be determined within the radius. FAT class $\Delta\sigma_R$ for the case E 2 or E 3 acc. to Section 17, Table 17.3 has to be used. In addition sufficient fatigue strength of the weld has to be verified e.g. by a calculation acc. to 4.4.1.

Note

The radius may be obtained by grinding. If disk grinding is carried out, score marks are to be avoided in the direction of the weld.

The radius is to be checked with a template for accuracy. Four profiles at least are to be checked. A report is to be submitted to the Surveyor.

Before welding is started, a detailed welding procedure specification is to be submitted to **BCS** covering the preparation, welding positions, welding parameters, consumables, preheating, post weld heat inspection procedures. This welding supported by approval tests in applicable requirements of the rules.

The manufacturer has to maintain records of welding, subsequent heat treatment and inspections traceable to the welds. These records are to be submitted to the Surveyor.

Non destructive tests are to be conducted at least 24 hours after completion of the welding. The welds are to be 100 % magnetic particle tested and 100 % ultrasonic tested.

D. Rudder Horn of Semi Spade Rudders

1. The distribution of the bending moment, shear force and torsional moment is to be determined according to the following formulae:

- bending moment: $M_b = B_1 \cdot z$ [kNm]

$$M_{bmax} = B_1 \cdot d \quad [\text{kNm}]$$

- shear force: $Q = B_1$ [kN]

- torsional moment: $M_T = B_1 \cdot e(z)$ [kNm]

For determining preliminary scantlings the flexibility of the rudder horn may be ignored and the supporting force B_1 be calculated according to the following formula:

$$B = \frac{C_R \cdot b}{c} \quad [\text{kN}]$$

b, c, d, e (z) and z see Figures 12.5 and 12.6.

b = results from the position of the centre of gravity of the rudder area.

2. The section modulus of the rudder horn in transverse direction related to the horizontal x-axis is to be designed according to Section 17 for the stress range spectrum B and for 10^8 load cycles.

3. At no cross section of the rudder horn the shear stress due to the shear force Q is to exceed the value:

$$\tau = 0,25 \cdot \frac{R_{eH}}{\gamma_m} \quad [\text{N/mm}^2]$$

The shear stress is to be determined by following formula:

$$\tau = \frac{B_1 \cdot 10^3}{A_h} \quad [\text{N/mm}^2]$$

A_h = effective shear area of rudder horn in y-direction [mm²]

4. The equivalent stress at any location z of the rudder horn shall not exceed the following value:

$$\sigma_v = \sqrt{\sigma_b^2 + 3 \cdot (\tau^2 + \tau_T^2)} = \frac{0,5 \cdot R_{eH}}{\gamma_m} \quad [\text{N/mm}^2]$$

$$\sigma_b = \frac{M_b \cdot 10^3}{W_x} \quad [\text{N/mm}^2]$$

$$\tau_T = \frac{M_T \cdot 10^6}{2 \cdot A_T \cdot t_h} \quad [\text{N/mm}^2]$$

A_T = sectional area [mm²] surrounded by the rudder horn at the location examined

t_h = thickness of the rudder horn plating [mm]




Figure 12.5 Parameters for semi spade-rudders

5. When determining the thickness of the rudder horn plating the provisions of 2. - 4. are to be complied with. The thickness is, however, not to be less than:

$$t_{\min} = 36 \cdot \sqrt{\frac{L \cdot \gamma_m}{R_{eH}}} \quad [\text{mm}]$$




Figure 12.6 Forces on the rudder horn

6. The rudder horn plating is to be effectively connected to the aft ship structure, e.g. by connecting the plating to longitudinal girders, in order to achieve a proper transmission of forces, see Figure 12.7.

7. Transverse webs of the rudder horn are to be led into the hull up to the next deck in a sufficient number and must be of adequate thickness.

Figure 12.7 Connection of rudder horn to the aft ship structure

8. Strengthened plate floors are to be fitted in line with the transverse webs in order to achieve a sufficient connection with the hull. The thickness of these plate floors is to be increased by 50 per cent above the Rule values as required by Section 17.

9. The centre line bulkhead (wash-bulkhead) in the afterpeak is to be connected to the rudder horn.

10. Where the transition between rudder horn and shell is curved, about 50 % of the required total section modulus of the rudder horn is to be formed by the webs in a Section A - A located in the centre of the transition zone, i.e. 0,7 r above the beginning of the transition zone, see Figure 12.8.




Figure 12.8 Transition between the rudder horn and the curved shell

E. Rudder Couplings**1. General**

1.1 The couplings are to be designed in such a way as to enable them to transmit the full torque of the rudder stock.

1.2 The distance of bolt axis from the edges of the flange is not to be less than 1,2 the diameter of the bolt. In horizontal couplings, at least 2 bolts are to be arranged forward of the stock axis.

1.3 The coupling bolts are to be fitted bolts. The bolts and nuts are to be effectively secured against loosening.

1.4 For spade rudders horizontal couplings according to 2. are permissible only where the required thickness of the coupling flanges t_f is less than 50 mm, otherwise cone couplings according to 3. are to be applied. For spade rudders of the high lift type, only cone couplings according to 3. are permitted.

1.5 If a cone coupling is used between the rudder stock or pintle, as the case can be, and the rudder blade or steering gear (see 3.), the contact area between the mating surfaces is to be demonstrated to the Surveyor by blue print test and should not be less than 70 % of the theoretical contact area (100 %). Noncontact areas should be distributed widely over the theoretical contact area. Concentrated areas of noncontact in the forward regions of the cone are especially to be avoided. The proof has to be demonstrated using the original components and the assembling of the components has to be done in due time to the creation of blue print to ensure the quality of the surfaces. In case of storing over a longer period, sufficient preservation of the surfaces is to be provided for.

If alternatively a male/female calibre system is used, the contact area between the mating surfaces is to be checked by blue print test and should not be less than 80 % of the theoretical contact area (100 %) and needs to be certified. After ten applications or five years the blue print proof has to be renewed.

2. Horizontal couplings

2.1 The diameter of coupling bolts is not to be less than:

$$d_b = 0,62 \sqrt{\frac{D^3 \cdot k_b}{k_r \cdot n \cdot e}} \quad [\text{mm}]$$

D = rudder stock diameter according to C. [mm]

n = total number of bolts, which is not to be less than 6

e = mean distance of the bolt axes from the centre of bolt system [mm]

k_r = material factor for the rudder stock as given in A.5.2

k_b = material factor for the bolts in analogues form to k_r in A.5.2.

2.2 The thickness of the coupling flanges is not to be less than determined by the following formula:

$$t_f = 0,62 \sqrt{\frac{D^3 \cdot k_f}{k_r \cdot n \cdot e}}$$

t_{fmin} = 0,9 d_b

k_f = material factor for the coupling flanges analogue to k_r in A.5.2.

The thickness of the coupling flanges clear of the bolt holes is not to be less than 0,65 t_f .

The width of material outside the bolt holes is not to be less than 0,67 · d_b .

2.3 The coupling flanges are to be equipped with a fitted key according to DIN 6885 or equivalent standard for relieving the bolts.

The fitted key may be dispensed with if the diameter of the bolts is increased by 10 %.

2.4 Horizontal coupling flanges shall either be forged together with the rudder stock or be welded to the rudder stock as outlined in Section 15, B.4.4.3.

2.5 For the connection of the coupling flanges with the rudder body see Section 15, B.4.4

3. Cone couplings

3.1 Cone couplings with key

3.1.1 Cone couplings should have a taper c on diameter of 1:8-1:12.




Figure 12.9 Cone coupling

The accuracy of the cone shapes must be controlled by a colour print. The nut is to be carefully secured, e.g. by a securing plate as shown in Figure 12.9.

3.1.2 The coupling length ℓ should, in general, not be less than $1,5 \cdot d_o$.

3.1.3 For couplings between stock and rudder a key is to be provided, the shear area of which is not to be less than:

$$a_s = \frac{1,6 \cdot Q_F}{d_k \cdot R_{eH1}^4} 10 \quad [\text{cm}^2]$$

Q_F = design yield moment of rudder stock [kNm] according to G.

d_k = diameter of the conical part of the rudder stock [mm] at the key

R_{eH1} = minimum yield stress of the key material [N/mm²]

3.1.4 The effective surface area of the key (without rounded edges) between key and rudder stock or cone coupling is not to be less than:

$$a_k = \frac{5000 Q_F}{d_k \cdot R_{eH2}} [\text{cm}^2]$$

R_{eH2} = minimum yield stress of the key, stock or coupling material [N/mm²], whichever is less

3.1.5 The dimensions of the slugging nut are to be as follows:

$$h_n = 0,6 \cdot d_g$$

- Outer diameter (the greater value to be taken):

$$d_n = 1,2 \cdot d_u \text{ or } d_n = 1,5 \cdot d_g$$

- External thread diameter:

$$d_g = 0,65 \cdot d_o$$

See Figure 12.9.

3.1.6 It is to be proved that 50 % of the design yield moment will be solely transmitted by friction in the cone couplings. This can be done by calculating the required push-up pressure and push-up length according to 3.2.3 for a torsional moment $Q'_F = 0,5 \cdot Q_F$.

3.2 Cone couplings with special arrangements for mounting and dismounting the couplings

3.2.1 Where the stock diameter exceeds 200 mm the press fit is recommended to be effected by a hydraulic pressure connection. In such cases the cone should be more slender, $c \approx 1:12$ to $\approx 1:20$.

3.2.2 In case of hydraulic pressure connections the nut is to be effectively secured against the rudder stock or the pintle. A securing plate for securing the nut

against the rudder body is not to be provided, see Figure 12.10.

Note:

A securing flat bar will be regarded as an effective securing device of the nut, if its shear area is not less than:

$$A_s = \frac{P_s \sqrt{d_1}}{R_{eH}} \left[\text{mm}^2 \right]$$

P_s = shear force

$$= \frac{P_e \cdot \mu_1 \left[d_1 - 0,6 \right]}{2 \cdot d_g} \left[\text{N} \right]$$

P_e = push-up force according to 3.2.3.2 [N]

μ_1 = frictional coefficient between nut and rudder body, normally $\mu_1 = 0,3$

d_1 = mean diameter of the frictional area between nut and rudder body

d_g = thread diameter of the nut

R_{eH} = minimum yield stress [N/mm²] of the securing flat bar material

3.2.3 For the safe transmission of the torsional moment by the coupling between rudder stock and rudder body the push-up length and the push-up pressure are to be determined by the following formulae.

3.2.3.1 Push-up pressure

The push-up pressure is not to be less than the greater of the two following values:

$$p_{\text{rep1}} = \frac{2 \cdot Q_F \cdot 10^6}{d_m^2 \cdot \ell \cdot \pi \cdot \mu_0} \left[\text{N/mm}^2 \right]$$

$$p_{\text{rep2}} = \frac{6 \cdot M_b \cdot 10^6}{\ell_2 \cdot d_m} \left[\text{N/mm}^2 \right]$$

Q_F = Design yield moment of rudder stock according to G. [kNm]

d_m = Mean cone diameter [mm]

ℓ = Cone length [mm]

μ_0 ≈ 0,15 (frictional coefficient)

M_b = Bending moment in the cone coupling, e.g. in case of spade rudders [kNm]

It has to be proved that the push-up pressure does not exceed the permissible surface pressure in the cone. The permissible surface pressure is to be determined by the following formula:

$$p_{\text{perm}} = 0,8 \cdot R_{eH} \frac{1 - \alpha^2}{\sqrt{3 + \alpha^4}} \left[\text{N/mm}^2 \right]$$

R_{eH} = minimum yield stress [N/mm²] of the material of the gudgeon

$\alpha = d_m/d_a$, see Figure 12.9

The outer diameter of the gudgeon should not be less than:

$$d_a = 1,5 \cdot d_m \text{ [mm]}$$




Figure 12.10 Cone coupling with special arrangements for mounting and dismounting

3.2.3.2 Push-up length

The push-up length is not to be less than:

$$\Delta \ell_1 = \frac{p_{\text{req}} \cdot d_m}{E \frac{1-\alpha^2}{2} c} + 0,8 \cdot \frac{R_m}{c} \quad [\text{mm}]$$

R_m = Mean roughness [mm]

$$\approx 0,01 \text{ mm}$$

c = Taper on diameter according to 3.2.1

E = Modulus of elasticity

$$= 2,06 \cdot 10^5 \text{ N/mm}^2$$

The push-up length is, however, not to be taken greater than:

$$\Delta \ell_2 = \frac{1,6 \cdot R_{eH} \cdot d_m}{\sqrt{3 + \alpha^4 E \cdot c}} + 0,8 \cdot \frac{R_m}{c} \quad [\text{mm}]$$

Note:

In case of hydraulic pressure connections the required push-up force P_e for the cone may be determined by the following formula:

$$P_e = p_{\text{req}} \cdot d_m \cdot \pi \cdot \ell \left(\frac{c}{2} + 0,002 \right) [N]$$

The value 0,02 is a reference for the friction coefficient using oil pressure. It varies and depends on the mechanical treatment and roughness of the details to be fixed.

Where due to the fitting procedure a partial push-up effect caused by the rudder weight is given, this may be taken into account when fixing the required pushup length, subject to approval by **BCS**.

3.2.4 The required push-up pressure for pintle bearings is to be determined by the following formula:

$$p_{\text{req}} = 400 \frac{B_1 \cdot d_o}{d_m \cdot \ell} \left[\frac{\text{N}}{\text{mm}^2} \right]$$

B_1 = supporting force in the pintle bearing [kN],
see also Figure 12.3

d_m, ℓ = see 3.2.3

d_o = pintle diameter [mm] according to Figure 12.9.

F. Rudder Body, Rudder Bearings

1. Strength of rudder body

1.1 The rudder body is to be stiffened by horizontal and vertical webs in such a manner that the rudder body will be effective as a beam. The rudder should be additionally stiffened at the aft edge.

1.2 The strength of the rudder body is to be proved by direct calculation according to C.3.

1.3 For rudder bodies without cut-outs the permissible stress are limited to:

bending stress due to M_R :

$$\sigma_b = 110 \text{ N/mm}^2$$

shear stress due to Q_1 :

$$\tau = 50 \text{ N/mm}^2$$

equivalent stress due to bending and shear:

$$\sigma_v = \sqrt{\sigma_b^2 + 3 \tau^2} = 120 \text{ N/mm}^2$$

M_R, Q_1 see C.3.3 and Figure 12.3

In case of openings in the rudder plating for access to cone coupling or pintle nut the permissible stresses according to 1.4 apply. Smaller permissible stress values may be required if the corner radii are less than $0,15 \cdot h$, where h = height of opening.

1.4 In rudder bodies with cut-outs (semi-spade rudders) the following stress values are not to be exceeded:

bending stress due to M_R :

$$\sigma_b = 90 \text{ N/mm}^2$$

shear stress due to Q_1 :

$$\tau = 50 \text{ N/mm}^2$$

torsional stress due to M_t :

$$\tau_t = 50 \text{ N/mm}^2$$

equivalent stress due to bending and shear and
equivalent stress due to bending and torsion:

$$\sigma_{v1} = \sqrt{\sigma_b^2 + 3 \tau^2} = 120 \text{ N/mm}^2$$

$$\sigma_{v2} = \sqrt{\sigma_b^2 + 3 \tau_t^2} = 100 \text{ N/mm}^2$$

$$M_R = C_{R2} \cdot f_1 + B_1 \frac{f_2}{2} \text{ kNm}$$

$$Q_1 = C_{R2} \text{ [kN]}$$

f_1, f_2 = see Figure 12.11.

The torsional stress may be calculated in a simplified manner as follows:

$$\tau_t = 500 \frac{M_t}{\ell \cdot h \cdot t} \text{ [N/mm}^2\text{]}$$

$$M_t = C_{R2} \cdot e \text{ [kNm]},$$

C_{R2} = Partial rudder force in [kN] of the partial rudder area A_2 below the cross section under consideration

e = Lever for torsional moment [m]

= Horizontal distance between the centre of effort of area A_2 and the centre line a-a of the effective cross sectional area under consideration, see Figure 12.11. The centre of effort is to be assumed at $0,33 \cdot c_2$ aft of the forward edge of area A_2 , where c_2 = mean breadth of area A_2

h, ℓ, t = [cm], see Figure 12.11.

The distance ℓ between the vertical webs should not exceed $1,2 \cdot h$.

The radii in the rudder plating are not to be less than 4-5

times the plate thickness, but in no case less than 50 mm.




Fig. 12.11 Geometry of a semi-spade rudder

Note:

It is recommended to keep the natural frequency of the fully immersed rudder and of local structural components at least 10 % above the exciting frequency of the propeller (number of revolutions x number of blades) or if relevant above higher order.

2. Rudder plating

2.1 The thickness of the rudder plating is to be determined according to Section 4, B. using the pressure p_R and $t_k = 1,0$ mm.

$$p_R = 10 \cdot (T - z) + \text{Max} \left(\frac{C_R}{A}, p_{Sdyn} \right) \text{ [kN/m}^2\text{]}$$

p_{Sdyn} = Dynamic pressure from external sea loads [kN/m²] according to Section 5, C.1.

Regarding welding see Section 15, B.

2.2 For connecting the side plating of the rudder to the webs tenon welding is not to be used. Where application of fillet welding is not practicable, the side plating is to be connected by means of slot welding to flat bars which are welded to the webs.

2.3 The thickness of the webs is not to be less than 70 % of the thickness of the rudder plating according to 2.1.

3. Transmitting of the rudder torque

3.1 For transmitting the rudder torque, the rudder plating according to 2.1 is to be increased by 25 % in way of the coupling. A sufficient number of vertical webs is to be fitted in way of the coupling.

3.2 If the torque is transmitted by a prolonged shaft extended into the rudder, the latter must have the diameter D_t or D_1 , whichever is greater, at the upper 10 % of the intersection length. Downwards it may be tapered to 0,6 D_t , in spade rudders to 0,4 times the strengthened diameter, if sufficient support is provided for.

4. Rudder bearings

4.1 In way of bearings liners and bushes are to be fitted. Their minimum thickness is:

$t_{\min} = 8 \text{ mm}$ for metallic and synthetic-materials

$t_{\min} = 22 \text{ mm}$ for lignum materials

4.2 An adequate lubrication is to be provided.

4.3 The bearing forces result from the direct calculation mentioned in C.3. As a first approximation the bearing force may be determined without taking account of the elastic supports. This can be done as follows:

- Normal rudder with two supports:

The rudder force C_R is to be distributed to the supports according to their vertical distances from the centre of gravity of the rudder area.

- Semi-spade rudders:

- Support force in the rudder horn:

$$B_1 = C_R \cdot \frac{b}{c} \quad [\text{kN}]$$

- Support force in the neck bearing:

$$B_2 = C_R - B_1 \quad [\text{kN}]$$

For b and c see Figure 12.5.

4.4 The projected bearing surface A_b (bearing height x external diameter of liner) is not to be less than

$$A_b = \frac{B}{q} 10^3 \quad [\text{mm}^2]$$

B = Support force [kN]

q = Permissible surface pressure according to Table 12.2

4.5 Stainless and wear resistant steels, bronze and hot-pressed bronze-graphit materials have a considerable difference in potential to non-alloyed steel. Respective preventive measures are required.

4.6 The bearing height shall be equal to the bearing diameter, however, is not to exceed 1,2 times the bearing diameter. Where the bearing height is less than the bearing diameter, higher specific surface pressures may be allowed.

5. Pintles

5.1 Pintles are to have scantlings complying with the conditions given in 4.4 and 4.6. The pintle diameter is not to be less than:

$$d = 11,07 \cdot \sqrt{B_1 \cdot k_r} \quad [\text{mm}]$$

B_1 = Support force [kN]

k_r = see A.5.2.

5.2 The thickness of any liner or bush shall not be less than:

$$t = \sqrt{0,1 \cdot B_1} \quad [\text{mm}]$$

or the values in 4.1 respectively.

5.3 Where pintles are of conical shape, they are to comply with the following

taper on diameter 1 : 8 to 1 : 12
if keyed by slugging nut

taper on diameter 1 : 12 to 1 : 20
if mounted with oil injection and
hydraulic nut

Table 12.2 Permissible surface pressure for different bearing materials

Bearing material	Surface pressure q [MPa]
Lignum vitae	2,5
White metal, oil lubricated	4,5
Synthetic material (1)	5,5
Steel (2), bronze and hot-pressed bronze-graphit materials	7,0
(1) Synthetic materials to be of approved type. Surface pressures exceeding 5,5 N/mm² may be accepted in accordance with bearing manufacturer's specification and tests, but not more than 10 N/mm². (2) Stainless and wear resistant steel in an approved combination with stock liner. Higher surface pressures than 7 N/mm² may be accepted if verified by tests.	

5.4 The pintles are to be arranged in such a manner as to prevent unintentional loosening and falling out.

For nuts and threads the requirements of E.3.1.5 and E.3.2.2 apply accordingly.

6. Guidance values for bearing clearances

6.1 For metallic bearing material the bearing clearance should generally not be less than:

$$\frac{d_b}{1000} + 1,0 \quad [\text{mm}]$$

d_b = inner diameter of bush

6.2 If non-metallic bearing material is applied, the bearing clearance is to be specially determined considering the material's swelling and thermal expansion properties.

6.3 The clearance is not to be taken less than 1,5 mm on diameter. In case of self lubricating bushes, going down below this value can be agreed to on the basis of the manufacturer's specification.

G. Design Yield Moment of Rudder Stock

The design yield moment of the rudder stock is to be determined by the following formula:

$$Q_F = 26,64 \cdot 10^6 \frac{D_t^3}{k_r} [\text{kNm}]$$

D_t = stock diameter [mm] according to C.1.

k_r = see A.5.2.

Where the actual diameter D_{ta} is greater than the calculated diameter D_t , the diameter D_{ta} is to be used. However, D_{ta} need not be taken greater than $1,145 \cdot D_t$.

H. Stopper, Locking Device

1. Stopper

The motions of quadrants or tillers are to be limited on either side by stoppers. The stoppers and their foundations connected to the ship's hull are to be of strong construction so that the yield point of the applied materials is not exceeded at the design yield moment of the rudder stock.

2. Locking device

Each steering gear is to be provided with a locking device in order to keep the rudder fixed at any position. This device, as well as the foundation in the ship's hull are to be of strong construction so that the yield point of the applied materials is not exceeded at the design yield moment of the rudder stock as specified in G. Where the ship's speed exceeds 12 kn, the design yield moment need only be calculated for a stock diameter based on a speed $v = 12$ kn.

3. Regarding stopper and locking device see also Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 2, B.3.6 and B.3.7.

I. Fin Stabilizers**1. General**

The hydrodynamic effects of fin stabilizers on the rolling behaviour of the ship are not part of the classification procedure. The classification however includes the integration of the system into the hull structure.

For the mechanical, electrical and hydraulic part of the drive system see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 2, C. – J.

2. Integration into the ship's structure

2.1 The complete bearing system and the drive unit directly mounted at the fin stock are to be situated within an own watertight compartment at the ship's side or bottom. If this watertight compartment is flooded the bulkhead deck shall not be submerged. For installation purposes, inspection and maintenance watertight closable openings (with safeguards that they can be opened only during docking) have to be provided in suitable number and size.

For retractable fins a recess of sufficient size to harbour the complete fin has to be provided in addition at the ship's shell.

2.2 At the penetration of the fin stock and at the slot of retractable fins, the shell has to be strengthened in a sufficient way.

2.3 The watertight boundaries of the fin recess, if applicable, and of the drive compartment have to be dimensioned according to Section 7. Special attention has to be given to the transmission of the fin support forces from the stock bearings into the ship's structure.

The local reinforcements and the overall transmission of the forces by girders, web frames, etc. have to be defined by direct calculations considering fatigue strength and have to be included in the hull drawings submitted.

2.4 If the fin body extends over the maximum breadth of the ship, the location of non-retractable fins should be marked on the shell.

SECTION 13**STRENGTHENING FOR NAVIGATION IN ICE**

	Page
A. General	13-2
1. Ice Class Notation ICE-B	

A. General**1. Ice Class Notation ICE-B**

1.1 The hull structure of naval ships for navigation in drift ice in the mouth of rivers and in coastal regions may be strengthened. The requirements to assign the Notation ICE -B are given in the **BCS** Rules, Chapter 1, Hull, Section 14.

1.2 Measures for other conditions of navigation in ice

1.2.1 The requirements for ice classes ICE-B1, ICE-B2, ICE-B3 and ICE-B4 are equivalent to those for the relevant Finnish- Swedish ice classes IC, IB, IA and IA super and are defined in **BCS** Rules for Hull , Section 14.

1.2.2 Class Notations PC1 to PC7 for polar class ships may be assigned if the requirements which are defined in Part C, Chapter 33 , **BCS** Rules for Polar Class Ships, are fulfilled.

1.2.3 The additional requirements for special deck and machinery equipment necessary for operation in ice are defined in Chapter 107 , **BCS** Rules for Ship Operation Installations and Auxiliary Systems , Section 19.

Ships meeting these requirements may be assigned the Class Notation ICEOPS affixed to their Character of Classification.

1.2.4 Measures for conditions of navigation in ice, different from the conditions relevant for 1., and 1.2.1 to 1.2.3 may be agreed with **BCS** case by case.

SECTION 14

FOUNDATIONS, HATCHWAYS AND HATCHCOVERS

	Page
A. General	14-2
1. Scope	
2. Definitions	
B. Foundations	14-2
1. General	
2. Foundations for main propulsion engines	
3. Foundations for auxiliary engines	
4. Foundations for deck machinery and mooring equipment	
5. Foundations for weapons and sensors	
C. Hatchways.....	14-7
1. Application	
2. Hatchways on freeboard and super-structure decks	
3. Hatchways on lower decks and within superstructures	
4. Hatchway	
D. Hatch Covers	14-8
1. Application	
2. Design assumptions	
3. Locking and securing of hatchway covers	
4. Tightness test, trials	
E. Strength And Securing of Small Hatches on The Exposed Fore Deck	14-9
1. General	
2. Application	
3. Strength	
4. Primary securing devices	
5. Requirements for primary securing	
6. Secondary securing device	
F. Engine Room Hatchways.....	14-12
1. Deck openings	
2. Engine room casings	
3. Doors in engine and boiler room casings	
G. Miscellaneous Openings in Freeboard and Superstructure Decks.....	14-12

A. General**Note:****1. Scope**

This Section covers only the standard forms of foundations, hatchways and hatch covers, having a wide spread application in naval ships. Exceptional types and forms will be especially considered.

It is to be proven that the natural frequencies of the foundation are not within the range of the critical excitation frequencies of the equipment mounted on the foundation. The judgement of the result of the analysis shall consider the requirements of Section 16.

2. Definitions

For the definitions of Positions 1 and 2 as well as of the standard height of superstructures see Section 1, B.

The natural frequencies of the bearings of the framing are to be coordinated with the manufacturer of the equipment mounted on the framing.

t_k = Corrosion addition according to Section 4, B.3.

The shock loads are to be determined for the foundations of equipment with at least shock safety classes A and B, see Section 16.

To reduce the influence of shock loads as well as to avoid the transmission of structure-borne noise between equipment and the ship's structure intermediate foundation framing is recommendable. For the requirements on the mounting of such double elastic foundations, see Section 16.

B. Foundations**1. General****1.2 Methods of analysis and design principles****1.1 Application**

Foundations for all types of equipment on board of naval ships are fulfilling the following tasks:

- Transmission of static/dynamic forces and moments created by the equipment itself as well as created by ship motions to the hull structure
- Reduction of transmission of dynamic peak loads and vibrations to the ship's structure
- Reduction of structure-borne noise transmitted from the machinery mounted on the foundation
- Reduction of shock forces created by underwater explosions and acting on the equipment.

1.2.1 Methods of analysis

1.2.1.1 Foundations have to be analyzed together with their structural integration. In general a static structural analysis of the foundations may be sufficient. In special cases, however, a dynamic analysis may be required. Regarding groups of similar foundations and substructures it is sufficient to examine one representative unit.

1.2.1.2 It has to be verified that the foundation has the stiffness required in the equipment specification and that the deflections are within the permissible range.

1.2.2 Design details

Foundations fitted on decks and walls in highly stressed areas of the hull girder have to be designed with respect to sufficient fatigue strength.

1.3 Screw connections

Screws are to be designed according to proven and acknowledged principles, see also Chapter 104 - Propulsion Plants, Section 2, B.4.

2. Foundations for main propulsion engines

2.1 General

2.1.1 The following requirements apply to foundations of diesel engines, gears, gas turbines and generators.

2.1.2 The rigidity of the engine seating and the surrounding bottom structure must be adequate to keep the deformations of the system within the permissible limits. In special cases, proof of deformations and stresses may be required.

Note

If in special cases a direct calculation of engine seating may become necessary, the following is to be observed, unless other limitations are defined by Naval Authority or the manufacturer of the propulsion plant:

- *For seatings of elastically mounted medium speed four-stroke diesel engines the total deformation Δf shall be not greater than:*

$$\Delta f = f_u + f_o \leq 0,2 \cdot \ell_M \text{ [mm]}$$

$$\ell_M = \text{Length of motor [m]}$$

$$f_u = \text{Maximum vertical deformation of the seating downwards within the length } \ell_M$$

$$f_o = \text{Maximum vertical deformation of the seating upwards within the length } \ell_M \text{ [mm]}$$

- *The individual deformations f_u and f_o shall not be greater than:*

$$f_{u \max}, f_{o \max} = 0,7 \cdot \Delta f$$

For the calculation of the deformations the maximum static and wave induced internal and external differential loads due

to local loads and the longitudinal hull girder bending moments as well as the rigidity of the motor are to be considered.

- *For seatings of non-elastically mounted medium speed four-stroke diesel engines the deformation values shall not exceed 50 % of the defined values.*

2.1.3 Due regard is to be paid to a smooth flow of forces in transverse and longitudinal direction.

2.1.4 The foundation bolts for fastening the engine at the seating shall be spaced no more than $3 \cdot d$ apart from the longitudinal foundation girder. Where the distance of the foundation bolts from the longitudinal foundation girder is greater, proof of equivalence is to be provided.

d = Diameter of the foundation bolts

2.1.5 In the whole speed range of main propulsion installations for continuous service resonance vibrations with inadmissible vibration amplitudes must not occur; if necessary structural modifications have to be provided for avoiding resonance frequencies. Otherwise, a barred speed range has to be fixed. Within a range of -10 % to +5 % related to the rated speed no barred speed range is permitted. **BCS** may require a vibration and, if deemed necessary, vibration

2.2 Longitudinal girders

2.2.1 The thickness of the longitudinal girders above the inner bottom for 4-stroke internal combustion engines is not to be less than:

$$t = \left[\frac{P}{n \cdot e_1 \cdot c} + \frac{G}{280} \right] \cdot \frac{3,75}{\ell_m} \text{ [mm]}$$

$$c = 1 - \frac{1}{0,025\sqrt{P}} \quad 0,2 \leq c \leq 0,5$$

$$t_{\min} = 0,4 \cdot t_p \text{ [mm]}$$

$$t_p = \text{Thickness of top plate, see 2.2.4}$$

$$P = \text{Rated driving power of the engine [kW]}$$

$$n = \text{Rated speed at output [1/min]}$$

G = Weight of engine [kN]

ℓ_m = Bolted length of engine on foundation [m] e₁

= Distance of the longitudinal girders [m]

The web thickness of longitudinal girders for elastically mounted four-stroke internal combustion engines may be reduced to

$$t_{red} = 0,4 \cdot t$$

if brackets are provided below the mountings, besides each bolt.

The web thickness may be reduced to

$$t_{red} = 0,9 \cdot t$$

if two longitudinal girders are provided at each side of an internal combustion engine.

2.2.2 The thickness of the longitudinal girders above the inner bottom or deck for gears or generators is not to be less than:

$$t = \sqrt{P/200} + 2 \quad [\text{mm}]$$

but not less than 0,4. t_p

P = Rated output of gear or generator [kW]

t_p = Thickness of top plate, see 2.2.4

2.2.3 For the thickness of the longitudinal girders for gas turbines above the inner bottom, the manufacturer's requirements have to be considered additionally.

2.2.4 The sizes of the top plate (width and thickness) shall be sufficient to attain efficient attachment and seating of the engine and - depending on seating height and type of engine - adequate transverse rigidity.

The thickness of the top plate shall be not less than:

$$t_p = 0,9 \cdot d \quad [\text{mm}]$$

d = Diameter of the foundation bolts [mm]

The cross sectional area of the top plate is not to be less than:

$$A_T = P/15 + 30 \quad [\text{cm}^2] \text{ for } P \leq 750 \text{ kW}$$

$$= P/75 + 70 \quad [\text{cm}^2] \text{ for } P > 750 \text{ kW}$$

P = see 2.2.1

2.2.5 For elastically mounted high speed engines (n > 1000 min⁻¹) the cross sectional area of the top plate may be reduced to:

$$A_T = P/40 + 14 \quad [\text{cm}^2] \text{ for } P \leq 750 \text{ kW}$$

$$= P/200 + 29 \quad [\text{cm}^2] \text{ for } P > 750 \text{ kW}$$

2.2.6 Where twin engines are fitted, a continuous top plate is to be arranged in general if the engines are coupled to one propeller shaft.

2.2.7 Top plates are preferably to be connected to longitudinal and transverse girders thicker than approx. 15 mm by means of a double beveling butt joint (K butt joint), see also Section 15.

2.3 Transverse support of longitudinal girders

2.3.1 The sectional modulus and the cross sectional area of the floor plates between longitudinal girders are not to be less than:

$$W = \left(\frac{120 \cdot P}{n} + e_1 \cdot G \right) \cdot \frac{7 \cdot a}{\ell_m} \quad [\text{cm}^3]$$

$$A_s = \frac{0,35 \cdot a \cdot G}{\ell_m} \quad [\text{cm}^2]$$

a = Distance of the floor plates [m]

For all other parameters see 2.2.1.

2.3.2 The longitudinal girders of the engine seating are to be supported transversely by means of web frames or wing bulkheads. The scantlings of web frames are to be determined according to Section 7.

2.4 Azimuthing propulsors

The space where the azimuthing propulsor unit is connected to the ship hull in general has to be surrounded by longitudinal and transverse watertight bulkheads. Suitable watertight access openings to the space have to be provided.

2.4.1 Loads

2.4.1.1 The following loads have to be considered for the determination of the scantlings of the supporting structure:

- Maximum transient thrust, torque and other forces and moments experienced during all envisaged operating modes as permitted by the steering and propulsor drive control systems.
Refer also to the Chapter 104, **BCS** Rules Propulsion Plants, Section 7,G.
- Self weight in water under consideration of the ship's pitch and heave motion and flooded volume, where applicable, see Section 5, B.
- Propulsor to propulsor and/or propulsor to ship hydrodynamic interference effects and effects of ship manoeuvring and of ship motions.

2.4.1.2 Special account is to be taken of any manoeuvring conditions that are likely to give rise to high mean or vibratory loadings.

2.4.2 Support structure

2.4.2.1 A system of primary structural members is to be provided in order to support the main slewing bearing of the propulsor unit and to transfer the maximum design loads into the ship's hull without undue deflection.

2.4.2.2 The hull support structure in way of the slewing bearing shall be sufficiently stiff that the bearing

manufacturer's limits on seating flatness are not exceeded due to hull flexure considering the loads defined under 2.4.1. For the verification of the structural design direct calculation is required, see 2.4.3.

2.4.2.3 Propulsors should be supported where practical within a double bottom structure. Generally a system of primary members including a pedestral girder directly supporting the slewing ring and bearing is to be provided. The pedestral girder is to be integrated with the ship's structure by means of radial girders and transverses aligned to their outer ends with the ship's bottom girders and transverses. Alternative arrangements have to provide an equivalent degree of strength and rigidity.

2.4.2.4 The shell envelope plating and tank top plating in way of the aperture for the propulsor are to be increased by 50% over the rule minimum thickness over an extent of at least the radial girders acc. to 2.4.2.3. In any case the thickness of the plating is not to be less than the actual fitted thickness of the surrounding shell or tank top plating.

2.4.2.5 The scantlings of the primary members of the support structure are to be based on the design stresses defined in 2.4.3.3. Primary member scantlings are not to be less than those required by Section 7.

2.4.2.6 The web thickness of the pedestral girder shall not be less than the required shell envelope minimum rule thickness at that position.

2.4.2.7 Full penetration welds are to be applied at the pedestral girder boundaries and in way of the end connections between the radial girders and the pedestral girder.

2.4.3 Direct Calculations

2.4.3.1 The mesh geometry and the element size has to be able to reflect the stiffness of the supporting structure as well as the deformations with sufficient accuracy. For vibration analysis the model has to be able to reflect the expected frequency range.

2.4.3.2 The loads applied to the mathematical model, refer to 2.4.1., are to include the self weight, dynamic acceleration due to ship motion, hydrodynamic loads, hydrostatic pressure, propeller forces and shaft bearing support forces. In situations where a propulsor can operate in the flooded conditions or where flooding of a propulsor unit adds significant mass to that unit, details are to be included.

2.4.3.3 Based on the most unfavourable combination of normal service conditions, the following stresses are not to be exceeded:

Shear stress: $0,38 \cdot f_{pL} \cdot R_{eH}$

Bending stress: $0,64 \cdot f_{pL} \cdot R_{eH}$

Equivalent v. Mises stress: $0,77 \cdot f_{pL} \cdot R_{eH}$

Localised v. Mises peak stress: R_{eH}

With f_{pL} the material factor according to Section 4, B.4.2.

If the design is based on extreme or statistically low probability loads, proposals to use alternative acceptance stress criteria may be considered.

2.4.3.4 Where a fatigue assessment is provided, details of cumulative load history and stress range together with the proposed acceptance criteria are to be submitted for consideration. See also Section 17.

2.4.3.5 For cast structures, the localised von Mises stress should not exceed 0,6 times the nominal 0,2 % proof or yield stress of the material for the most unfavourable design condition.

3. Foundations for auxiliary engines

For mechanical and electrical installations the loads on the foundations are created by their weight, and all reaction forces and moments resulting from the most unfavorable operating conditions have to be considered in addition. The cross sectional area of the top plate may be determined according to 2.2.5.

4. Foundations for deck machinery and mooring equipment

4.1 For deck machinery, like anchor windlasses, mooring winches, boat davits, etc. the most critical operation status has to be considered for an analysis.

4.2 For the supporting structure under windlasses and chain stoppers, the following permissible stresses are to be observed:

bending stress : $\sigma_{bb} = 200/kk$ [N/mm²]

shear stress : $\tau\tau = 120/kk$ [N/mm²]

equivalent stress: $\sigma_{eq} = \sqrt{\sigma_{bb}^2 + 3\tau\tau^2} = 220/kk$ [N/mm²]

The acting forces are to be calculated for 80 % and 45 % respectively of the rated breaking load of the chain cable, i.e.:

for chain stoppers 80 %

for windlasses 80 %, where chain stoppers are not fitted.
45 %, where chain stoppers are fitted..

4.3 See also Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 5, A. and the **BCS** Rules Part A, Chapter 2 - Materials, Section 10 Equipment, Table 10.11.

5. Foundations for weapons and sensors

5.1 Types of foundations

Naval ships may be equipped with standardized functional units, especially for weapons, sensors and electronic equipment. Containers with an upper deck flange hanging downwards from the main or super-structure decks, as well as containers and pallets standing on lower decks of the ship's structure may be used.

5.2 Weapon containers

Weapon modules normally consist of a module cover connected to a surrounding stiff foundation and the containers below, hanging through the deck. The containerised room below has to have adequate strength to carry all supporting systems for this weapon, like computer, ammunition feeding, air conditioner, energy distribution, etc.

The containers are to be bedded onto the upper flange of the respective hatchway considering the exact alignment to the ship's axes. A plastic resin compound, which shall be of the quick hardening, high loadability, heat-resistant type, should be used to transfer static and dynamic loads evenly into the ship's structure. The fastening of the module cover to the flange of the hatch coaming shall be provided by high-strength, pre-stressed screw connections, which are to be locked properly. The detailed design of the flanges on the coaming as well on the cover has to consider the shock aspects defined in 1.1.

5.3 Units for electronic equipment

Electronic units normally consist of containers or of pallets for bigger floor areas. Both types of units are to be fitted on intermediate foundations which are shock mounted. Thus the need of shock mounting of all single parts of the equipment can be avoided to a considerable extent. The lower flange of the intermediate foundation shall be connected to the deck structure by screw connections properly locked.

C. Hatchways

1. Application

Hatchways for the following purposes on board of naval ships are considered in this Section:

- Loading and unloading of military equipment
- Installation and removal of equipment for repair and maintenance

- Change of equipment for modernization
- Openings for engine rooms and miscellaneous duties

2. Hatchways on freeboard and super-structure decks

2.1 In general hatchways are to have coamings with a minimum height above the deck as follows:

- In position 1: 600 mm
- In position 2: 450 mm

BCSy accept lesser heights of coamings if alternative solutions with equivalent level of safety are and recognized. In this case agreement with Authority may become necessary.

2.2 On exposed decks lower coamings may be accepted if an equivalent level of tightness/safety can be achieved.

3. Hatchways on lower decks and within superstructures

3.1 Coamings are not required for hatchways below the freeboard deck or within weathertight closed superstructures unless they are required for strength purposes.

3.2 Where within hatch casings no hatch covers are arranged at the deck level, covers and their supports below are to be strengthened corresponding to the greater load.

4. Hatchway

4.1 Hatchway coamings which are exposed to the wash of sea shall comply analogously with the requirements for walls of deckhouses as per Sections 8. They are to be adequately supported and stiffened.

4.2 Coamings with 600 mm or more in height are to be stiffened in their upper part above deck or in their lower part below deck by a horizontal stiffener.

Flush deck hatches have to be specially considered case by case.

4.3 The connection of the coamings to the deck at the hatchway corners is to be carried out with special care.

For rounding of hatchway corners, see also Section 4, H.3.

D. Hatch Covers

1. Application

It is assumed that on board of naval ships all hatch covers are made of metal (steel or aluminium) having integrated girder elements in form of box girders or, alternatively, that the hatch covers are of the pontoon type, etc.

2. Design assumptions

2.1 The loads have to be applied as for decks at the same height z above base line. The breadth of the hatchway b' has to be considered by applying the coefficient n_2 , see Section 5, C.1.

2.2 The hatch cover stiffeners/girders have to be regarded as simply supported at both ends.

2.3 Hatch covers are to be designed on the basis of direct calculations. In general the requirements of Section 4 regarding strength are to be applied.

The deflection of hatch covers shall not exceed :

$$f = \ell / 350.$$

2.4 Structural elements of hatch covers are to be examined for sufficient buckling strength according to Section 4, F.

2.5 Proof of fatigue strength according to Section 17 may be required for hatch cover supports.

3. Locking and securing of hatchway covers

3.1 For the design of the securing devices against shifting according to 3.5 the mass forces in the ship's longitudinal and transverse direction are to be calculated. For this purpose the acceleration components according to Section 5, B. are to be used with $f_Q = 1,0$.

3.2 The hatch covers are to be locked to the hatch coamings. The net cross-sectional area of the securing devices is not to be less than:

$$A = \frac{890 \cdot s}{R_{eH} + R_m} \quad [\text{cm}^2]$$

s = spacing between securing devices [m], not to be taken less than 2 m

Rods or bolts are to have a net diameter not less than 19 mm for hatchways exceeding 5 m² in area. The spacing of securing devices shall generally not exceed 6 m. Due attention is to be given to the stiffness of hatch cover edges between the securing devices.

3.3 Between cover and coaming and at cross joints a packing line pressure sufficient to obtain weathertightness is to be maintained by the securing devices. For packing line pressures exceeding 5 N/mm, the cross-sectional area is to be increased indirect proportion. The packing line pressure is to be specified.

3.4 The cover edge stiffness is to be sufficient to maintain adequate sealing pressure between securing devices. The moment of inertia of edge elements is not to be less than:

$$I = 6 \cdot p \cdot s^4 \quad [\text{cm}^4]$$

p = Packing line pressure [N/mm], minimum 5 N/mm

s = Spacing [m] of securing devices

3.5 Securing devices are to be of reliable construction and effectively attached to the hatchway coamings, decks or covers. Individual securing devices on each cover are to have approximately the same stiffness characteristics.

3.6 Where rod cleats are fitted, resilient washers or cushions are to be incorporated.

3.7 Where hydraulic cleating is adopted, a positive means is to be provided to ensure that it remains mechanically locked in the closed position in the event of failure of the hydraulic system.

3.8 The scantlings of the securing devices are to be such as to prevent lifting and shifting of the hatch covers.

3.9 Hatch covers, which are intended to carry cargo, are to be additionally secured against shifting in the longitudinal and transverse direction due to the horizontal mass forces specified in 3.1.

3.10 Closing appliances are to be provided at each corner of the hatch cover. This applies also to hatch covers consisting of several parts.

3.11 The packing material is to be suitable for all expected service conditions of the ship and is to be compatible with the military cargoes to be transported. The packing material is to be selected with regard to dimensions and elasticity in such a way that probable deformations can be carried. Forces are to be carried by the steel structure only.

The packing is to be compressed so as to give the necessary tightness effect. International standards, like ISO, etc. are to be observed.

Special consideration shall be given to the packing arrangement in ships with large relative movements between hatch covers and coamings or between hatch cover sections.

3.12 At cross-joints of multi-panel covers vertical guides (male/female) are to be fitted to prevent excessive relative vertical deflections between loaded/unloaded panels.

3.13 To prevent damage to hatch covers and ship structure, the location of stoppers is to be compatible with the relative movements between hatch covers and ship structure. The number should be as small as practically possible.

3.14 For hydraulic equipment to close and open hatch covers see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 14, B.

4. Tightness test, trials

4.1 The self-tightening steel hatch covers on weather decks and within open superstructures are to be hose tested.

The water pressure shall not be less than 2 bar and the hose nozzle shall be held at a distance of not more than 1,5 m from the hatch cover to be tested (the nozzle diameter shall not be less than 12 mm). During frost periods equivalent tightness tests may be carried out to the satisfaction of the **BCS** Surveyor.

4.2 Upon completion of the hatchway cover system trials for proper functioning are to be carried out in presence of the **BCS** Surveyor.

E. Strength And Securing of Small Hatches on The Exposed Fore Deck

1. General

1.1 The strength of, and securing devices for, small hatches fitted on the exposed fore deck over the forward 0,25 L are to comply with the following requirements.

1.2 Small hatches in this context are hatches designed for access to spaces below the deck and are capable to be closed weathertight or watertight, as applicable. Their opening is normally 2,5 square meters or less.

1.3 Hatches designed for emergency escape need not comply with the requirements according methods A and B in 4.1, 5.3 and 6.

1.4 Securing devices of hatches designed for emergency escape are to be of a quick-acting type (e.g. one action wheel handles are provided as central locking devices for latching/unlatching of hatch cover) operable from both sides of the hatch cover.

2. Application

All types of sea going ships, where the height of the exposed deck in way of the hatch is less than 0,1 L or 22 m above the summer load waterline, whichever is the lesser.

3. Strength

3.1 For small rectangular steel hatch covers, the plate thickness, stiffener arrangement and scantlings are to be in accordance with Table 14.1 and Figure 14.1. Stiffeners, where fitted, are to be aligned with the metal-to-metal contact points, required in 5.1, see Figure 14.1. Primary stiffeners are to be continuous. All stiffeners are to be welded to the inner edge stiffener, see Figure 14.2.

Table 14.1 Scantlings for small steel hatch covers on the fore deck

Nominal size [mm x mm]	Cover plate thickness [mm]	Primary stiffeners	Secondary stiffeners
		Flat bar [mm x mm] ; number	
630 x 630	8	-	-
630 x 830	8	100 x 8 ; 1	-
830 x 630	8	100 x 8 ; 1	-
830 x 830	8	100 x 10 ; 1	-
1030 x 1030	8	120 x 12 ; 1	80 x 8 ; 2
1330 x 1330	8	150 x 12 ; 1	100 x 10 ; 2
For ships with $L < 80$ m the cover scantlings may be reduced by the factor $0,11 \cdot \sqrt{L} \geq 0,75$			

3.2 The upper edge of the hatchway coamings is to be suitably reinforced by a horizontal section normally not more than 170 mm to 190 mm from the upper edge of the coamings. The minimum size of the reinforcing profile should be reinforcing profile should be flat iron 180 x 8 and has to be enlarged according to the size of the hatch.

3.3 For small hatch covers of circular or similar shape, the cover plate thickness and reinforcement is to be specially considered.

3.4 For small hatch covers constructed of materials other than steel, the required scantlings are to provide equivalent strength.

4. Primary securing devices

4.1 Small hatches located on exposed fore deck subject to the application according to 2.2 are to be fitted with primary securing devices such that their hatch covers can be secured in place and weathertight by means of a mechanism employing any one of the following methods:

- method A: butterfly nuts tightening onto forks (clamps)
- method B: quick acting cleats
- method C: central locking device

4.2 Dogs (twist tightening handles) with wedges are not acceptable.

5. Requirements for primary securing

5.1 The hatch cover is to be fitted with a gasket of elastic material. This is to be designed to allow a metal to metal contact at a designed compression and to prevent over-compression of the gasket by green sea forces that may cause the securing devices to be loosened or dislodged. The metal-to-metal contacts are to be arranged close to each securing device in accordance with Figure 14.1 and of sufficient capacity to withstand the bearing force.

5.2 The primary securing method is to be designed and manufactured such that the designed compression pressure is achieved by one person without the need of any tools.

5.3 For a primary securing method using butterfly nuts, the forks (clamps) are to be of robust design. They are to be designed to minimize the risk of butterfly nuts being dislodged while in use; by means of curving the forks upward, a raised surface on the free end, or a similar method. The plate thickness of unstiffened steel forks is not to be less than 16 mm. An example arrangement is shown in Figure 14.2.




Figure 14.1 Arrangement of stiffeners

- ① : butterfly nut
- ② : bolt
- ③ : pin
- ④ : center of pin
- ⑤ : fork (clamp) plate
- ⑥ : hatch cover
- ⑦ : gasget
- ⑧ : hatch coaming
- ⑨ : bearing pad welded on the bracket of a toggle bolt for metal to metal contact
- ⑩ : stiffener
- ⑪ : inner edge stiffener




Figure 14.2 Example of a primary securing method

5.4 For small hatch covers located on the exposed deck forward, the hinges are to be fitted such that the predominant direction of green sea will cause the cover to close. This would mean that the hinges are to be placed on the fore edge or outboard edge according to the local situation.

6. Secondary securing device

Small hatches on the fore deck are to be fitted with an independent secondary securing device e.g. by means of a sliding bolt, a hasp or a backing bar of slack fit, which is capable of keeping the hatch cover in place, even in the event that the primary securing device became loosened or dislodged. It is to be fitted on the side opposite to the hatch cover hinges.

Fall arresters against accidental closing are to be provided.

F. Engine Room Hatchways

1. Deck openings

1.1 The openings above engine rooms shall not be larger than necessary. In way of these rooms sufficient transverse strength is to be ensured.

1.2 Engine room openings are to be well rounded at their corners, and if required, to be provided with strengthening, unless proper distribution of the longitudinal stresses is ensured by the side walls of super structures or deckhouses. See also Section 4,H.3.

2. Engine room casings

2.1 Engine room openings on weather decks and inside open superstructures are to be protected by casings of sufficient height.

2.2 The scantlings of stiffeners, plating and covering of exposed casings are to comply with the requirements for longitudinal and transverse walls according to Sections 8.

2.3 Inside open superstructures the casings are to have stiffeners and plates as required for an aft end bulkhead according to Section 8.

2.4 The coaming plates are to be extended to the lower edge of the deck beams.

3. Doors in engine and boiler room casings

3.1 The doors in casings on exposed decks and within open superstructures are to be of steel, well stiffened and hinged, and capable of being closed from both sides and secured weathertight by toggles and rubber sealings.

3.2 The doors are to be at least of the same strength as the casing walls in which they are fitted.

3.3 The height of the doorway sills is to be 600 mm above decks in pos. 1 and 380 mm above decks in pos. 2.

BCS may accept lesser heights of sills if alternative with equivalent level of safety are provided and

Such an alternative solution could be e.g. the arrangement of a lock of moderate size behind the outside side door. Also in this case both doors are to be fitted with convenient coamings.

G. Miscellaneous Openings in Freeboard and Superstructure Decks

1. Manholes and small flush deck hatches in decks in pos. 1 and 2 or in open superstructures are to be closed watertight.

2. If not bolted watertight, they are to be of substantial steel construction with bayonet joints or screws. The covers are to be hinged or to be permanently attached to the deck by a chain to be agreed by **BCS**.

3. Openings in freeboard decks other than hatchways and machinery space openings may only be arranged in weathertight closed superstructures or

deckhouses or in weathertight closed companionways of the same strength.

4. Companionways on exposed parts of freeboard decks, on decks of closed superstructures and in special cases on the deck of deckhouses are to be of solid construction. The height of the doorway sills is to be 600 mm above decks in pos. 1 and 380 mm above decks in pos. 2. **BCS** may accept lesser heights of coamings if alternative solutions with equivalent level of safety are provided and recognized.

5. The doors of the companion ways are to be capable of being operated and secured from both sides. They are to be closed weathertight by rubber sealings and toggles.

6. Access hatchways shall have a clear width of at least 600 x 600 mm.

SECTION 15**WELDED JOINTS**

	Page
A. General	15-2
1. Information contained in manufacturing documents	
2. Materials, weldability	
3. Manufacture and testing	
B. Design	15-3
1. General design principles	
2. Design details	
3. Weld shapes and dimensions	
4. Welded joints of particular components	
C. Stress Analysis	15-14
1. General analysis of fillet weld stresses	
2. Determination of stresses	

A. General

*The content of this Section is an excerpt of the **BCS Rules Part A, Chapter 3 - Welding**, Section 12 - Welding of Structures .. Because of re-issues of these Rules Section at different times, some temporary*

1. Information contained in manufacturing documents

1.1 The shapes and dimensions of welds and, where proof by calculation is supplied, the requirements applicable to welded joints (the weld quality grade, detail category) are to be stated in drawings and other manufacturing documents (parts lists, welding and inspection schedules). In special cases, e. g. where special materials are concerned, the documents shall also state the welding method, the welding consumables used, heat input and control, the weld build-up and any post-weld treatment which may be required.

1.2 Symbols and signs used to identify welded joints shall be explained if they depart from the symbols and definitions contained in the relevant standards (e.g. DIN standards). Where the weld preparation (together with approved methods of welding) conforms both to normal shipbuilding practice and to these Rules and recognized standards, where applicable, no special description is needed.

2. Materials, weldability

2.1 Only base materials of proven weldability, see Section 3, may be used for welded structures. Any approval conditions of the steel or of the procedure qualification tests and the steel maker's recommendations are to be observed.

2.2 For normal strength hull structural steel grades A, B, D and E which have been tested by **BCS**, weldability is considered to have been proven. The suitability of these base materials for high efficiency welding processes with high heat input

shall be verified.

2.3 Higher strength hull structural steel grades AH/DH/EH/FH which have been approved by **BCS** in accordance with the relevant requirements of the BCSles, Part A, Chapter 2 and 3 - Materials and Welding, have had their weldability examined and, provided their handling is in accordance with normal shipbuilding practice, may be considered to be proven. The suitability of these base materials for high efficiency welding processes with high heat input shall be verified.

2.4 High strength (quenched and tempered) fine grain structural steels, low temperature steels, stainless and other (alloyed) structural steels require special approval by **BCS**. Proof of weldability of the respective steel is to be presented in connection with the welding procedure and the welding consumables.

2.5 Steel castings and forgings shall comply with the Rules for Materials and shall have been tested by **BCS**. The carbon content of components made from carbon and carbon -manganese steels/castings for welded structures shall not exceed 0,23 % C at ladle analysis (piece analysis max. 0,25 % C).

2.6 Light metal alloys must have been tested by **BCS** in accordance with the Rules for Materials. Their weldability must have been verified in combination with welding processes and welding consumables. It can generally be taken for granted in the case of the alloys mentioned in the Rules for Materials.

2.7 Welding consumables used are to be suitable for the parent metal to be welded and are to be approved by **BCS**. Where filler materials having properties deviating (downwards) from metal are used (upon special agreement has to be taken into account when welded joints.

3. Manufacture and testing

3.1 The manufacture of welded structural

components may only be carried out in workshops or plants that have been approved. The requirements that have to be observed in connection with the fabrication of welded joints are laid down in the **BCS Rules**, Part Chapter 3 - Welding.

3.2 The weld quality grade of welded joints without proof by calculation, see 2.1, depends on the significance of the welded joint for the total structure and on its location in the structural element (location to the main stress direction) and on its stressing. For details concerning the type, scope and manner of testing, see **BCS Rules**, Part A, Chapter 3- Welding, Section 12- Welding of Hull Structures. Where proof of fatigue strength is required, in addition the requirements of Section 17 apply.

B. Design

1. General design principles

1.1 During the design stage welded joints are to be planned such as to be accessible during fabrication, to be located in the best possible position for welding and to permit proper welding sequence.

1.2 Both the welded joints and the sequence of welding involved are to be so planned as to enable residual welding stresses to be kept to a minimum in order that no excessive deformation occurs. Welded joints should not be over dimensioned, see also 3.3.3.

1.3 When planning welded joints, it shall first be established that the type and grade of weld envisaged, such as full root weld penetration in the case of HV or DHV (K) weld seams, can be perfectly executed under the conditions set by the limitations of the manufacturing process applied. If this is not the case, a simpler type of weld seam shall be selected and its possibly lower load bearing capacity taken into account in the dimensioning of the component.

1.4 Highly stressed welded joints - which, therefore, are generally subject to examination - are to be so designed that the most suitable method of testing for faults can be used (radiography, ultrasonic, surface

crack testing methods) in order that a reliable examination may be carried out.

1.5 Special characteristics peculiar to the material, such as the lower strength values of rolled material in the thickness direction (see 2.5.1) or the softening of cold worked aluminium alloys as a result of welding, are factors which have to be taken into account when designing welded joints. Clad plates where the efficiency of the bond between the base and the clad material is proved may generally be treated as solid plates (up to medium plate thicknesses where mainly fillet weld connections are used).

1.6 In cases where different types of material are paired and operate in sea water or any other electrolytic medium, for example welded joints made between unalloyed carbon steels and stainless steels in the wear-resistant cladding in rudder nozzles or in the cladding of rudder shafts, the resulting differences in potential greatly increase the susceptibility to corrosion and must, therefore, be given special attention.

Where possible, such welds are to be positioned in locations less subject to the risk of corrosion (such as on the outside of tanks) or special protective countermeasures are to be taken (such as the provision of a protective coating or cathodic protection).

2. Design details

2.1 Stress flow, transitions

2.1.1 All welded joints on primary supporting members shall be designed to provide as smooth a stress profile as possible with no major internal or external notches, no discontinuities in rigidity and no obstructions to strains, see Section 4, H.

2.1.2 This applies in analogous manner to the welding of subordinate components on to primary supporting members whose exposed plate or flange edges should, as far as possible, be kept free from notch effects due to welded attachments. Regarding the in-admissibility of weldments to the upper edge of the sheer strake, see Section 8, B.3. This applies similarly to weldments to the upper edge of continuous side coamings of large openings.

2.1.3 Butt joints in long or extensive continuous structures such as bilge keels, fenders, crane rails, slop coamings, etc. attached to primary structural members are therefore to be welded over their entire crosssection.

2.1.4 Wherever possible, joints (especially site joints) in girders and sections shall not be located in areas of high bending stress. Joints at the knuckle of flanges are to be avoided.

2.1.5 The transition between differing component dimensions shall be smooth and gradual. Where the depth of web of girders or sections differs, the flanges or bulbs are to be bevelled and the web slit and expanded or pressed together to equalize the depths of the members. The length of the transition should be at least equal twice the difference in depth.

2.1.6 Where the plate thickness differs at joints perpendicularly to the direction of the main stress, differences in thickness greater than 3 mm must be accommodated by bevelling the proud edge in the manner shown in Figure 15.1 at a ratio of at least 1 : 3 or according to the notch category. Differences in thickness of 3 mm or less may be accommodated within the weld.




Figure 15.1 Accommodation of differences of thickness

2.1.7 For the welding on of plates or other relatively thin-walled elements, steel castings and forgings should be appropriately tapered or provided with integrally cast or forged welding flanges in accordance with Figure 15.2.

2.1.8 For the connection of shaft brackets to the boss and shell plating, see 4.3 and Section 11, C.; for

the connection of horizontal coupling flanges to the rudder body, see 4.4. For the required thickened rudderstock collar required with build-up welds and for the connection of the coupling flange, see 2.7 and Section 12, E.2.4. Rudderstock and the coupling flange are to be connected by full penetration weld, see 4.4.3..




Figure 15.2 Welding flanges on steel castings of forgings

2.2 Local clustering of welds, minimum spacing

2.2.1 The local clustering of welds and short distances between welds are to be avoided. Adjacent butt welds should be separated from each other by a distance of at least:

$$50 \text{ mm} + 4 \times \text{plate thickness}$$

Fillet welds should be separated from each other and from butt welds by a distance of at least:

$$30 \text{ mm} + 2 \times \text{plate thickness}$$

The width of replaced or inserted plates (strips) should, however, be at least 300 mm or ten times the plate thickness, whichever is the greater.

2.2.2 Reinforcing plates, welding flanges, mountings and similar components socket-welded into plating should be of the following minimum size:

$$D_{\min} = 170 + 3(t - 10) \geq 170 \text{ mm}$$

$$D = \text{diameter of round or length of side of angular weldments [mm]}$$

$$t = \text{plating thickness [mm]}$$

The corner radii of angular socket weldments should be $5t$ [mm] but at least 50 mm. Alternatively the "longitudinal seams" are to extend beyond the "transverse seams". Socket weldments are to be fully welded to the surrounding plating.

Regarding the increase of stress due to different thickness of plates see also Section 17, B.1.3.

2.3 Welding cut-outs

2.3.1 Welding cut-outs for the (later) execution of butt or fillet welds following the positioning of transverse members should be rounded (minimum radius 25 mm or twice the plate thickness, whichever is the greater) and should be shaped to provide a smooth transition on the adjoining surface as shown in Figure 15.3 (especially necessary where the loading is mainly dynamic).




Figure 15.3 Welding cut-outs

2.3.2 Where the welds are completed prior to the positioning of the crossing members, no welding cutouts are needed. Any weld reinforcements present are to be machined off prior to the location of the crossing members or these members are to have suitable cut-outs.

2.4 Local reinforcements, doubling plates

2.4.1 Where platings (including girder plates and tube walls) are subjected locally to increased stresses, thicker plates should be used wherever possible in preference to doubling plates. Bearing bushes, hubs etc. shall invariably take the form of thicker sections welded into the plating, see

2.2.2.

2.4.2 Where doublings cannot be avoided, the thickness of the doubling plates should not exceed twice the plating thickness. Doubling plates whose width is greater than approximately 30 times their thickness shall be plug welded to the underlying plating in accordance with 3.3.11 at intervals not exceeding 30 times the thickness of the doubling plate.

2.4.3 Along their (longitudinal) edges, doubling plates shall be continuously fillet welded with a throat thickness "a" of $0,3 \times$ the doubling plate thickness. At the ends of doubling plates, the throat thickness "a" at the end faces shall be increased to $0,5 \times$ the doubling plate thickness but shall not exceed the plating thickness (see Figure 15.4).

The welded transition at the end faces of the doubling plates to the plating should form with the latter an angle of 45° or less.




Figure 15.4 Welding at the ends of doubling plates

2.4.4 Where proof of fatigue strength is required, see Section 17, the configuration of the end of the doubling plate must conform to the selected detail category.

2.4.5 Doubling plates are not permitted in tanks for flammable liquids except collar plates and small doublings for fittings like tank heating fittings or fittings for ladders.

2.5 Intersecting members, stress in the thickness direction

2.5.1 Where, in the case of intersecting members, plates or other rolled products are stressed

in the thickness direction by shrinking stresses due to the welding and/or applied loads, suitable measures shall be taken in the design and fabrication of the structures to prevent lamellar tearing (stratified fractures) due to the anisotropy of the rolled products.

2.5.2 Such measures include the use of suitable weld shapes with a minimum weld volume and a welding sequence designed to reduce transverse shrinkage. Other measures are the distribution of the stresses over a larger area of the plate surface by using a build-up weld or the joining together of several "fibres" members stressed in the thickness direction as exemplified by the deck stringer/sheer strake joint shown in Figure 15.12.

2.5.3 In case of very severe stresses in the thickness direction due, for example, to the aggregate effect of the shrinkage stresses of bulky single or double-bevel butt welds plus high applied loads, plates with guaranteed through thickness properties (extra high-purity material and guaranteed minimum reductions in area of tensile test specimens taken in thickness direction) are to be used.

2.6 Welding of cold formed sections, bending radii

2.6.1 Wherever possible, welding should be avoided at the cold formed sections with more than 5 % permanent elongation **(1)** and in the adjacent areas of structural steels with a tendency towards strain ageing.

2.6.2 Welding may be performed at the cold formed sections and adjacent areas of hull structural steels and comparable structural steels (e.g. those in quality groups S... J... and S... K... to

(1) Elongation ε in the outer tensile-stressed zone 100

$$\varepsilon = \frac{100}{1 + 2 r/t} \quad [\%]$$

r = inner bending radius [mm]

t = plate thickness [mm]

DIN-EN 10025) provided that the minimum bending radii are not less than those specified in Table 15.1.

Table 15.1 Minimum inner bending radii for cold formed sections

Plate thickness t	Minimum inner bending radius r
to 4 mm	1,0 x t
to 8 mm	1,5 x t
to 12 mm	2,0 x t
to 24 mm	3,0 x t
over 24 mm	5,0 x t

Note:

The bending capacity of the material may necessitate a larger bending radius.

2.6.3 For other steels and other materials, where applicable, the necessary minimum bending radius shall, in case of doubt, be established by test. Proof of adequate toughness after welding may be stipulated for steels with minimum yield stress of more than 355 N/mm² and plate thicknesses of 30 mm and above which have undergone cold forming resulting in 2 % or more permanent elongation.

2.7 Build-up welds on rudder stocks and pintles

2.7.1 Wear resistance and/or corrosion resistant build-up welds on the bearing surfaces of rudder-stocks, pintles etc. shall be applied to a thickened collar exceeding by at least 20 mm the diameter of the adjoining part of the shaft.

2.7.2 Where a thickened collar is impossible for design reasons, the build-up weld may be applied to the smooth shaft provided that relief-turning in accordance with 2.7.3 is possible (leaving an adequate residual diameter).

2.7.3 After welding, the transition areas between the welded and non-welded portions of the shaft shall be relief-turned with large radii, as shown in Figure 15.5, to remove any base material whose structure

close to the concave groove has been altered by the welding operation and in order to effect the physical separation of geometrical and metallurgical "notches".




Figure 15.5 Build-up welds applied to rudderstocks and pintles

3. Weld shapes and dimensions

3.1 Butt joints

3.1.1 Depending on the plate thickness, the welding method and the welding position, butt joints shall be of the square, V or double-V shape conforming to the relevant standards (e.g. EN 22553/ISO 2533, ISO 9692-1, -2, -3 or -4). Where other weld shapes are applied, these are to be specially described in the drawings. Weld shapes for special welding processes such as single-side or electrogas welding must have been tested and approved in the context of a welding procedure test.

3.1.2 As a matter of principle, the rear sides of butt joints shall be grooved and welded with at least one capping pass. Exceptions to this rule, as in the case of submerged-arc welding or the welding processes mentioned in 3.1.1, require to be tested and approved in connection with a welding procedure test. The effective weld thickness shall be deemed to be the plate thickness, or, where the plate thicknesses differ, the lesser plate thickness. Where proof of fatigue strength is required, see Section 17, the detail category depends on the execution (quality) of the weld.

3.1.3 Where the aforementioned conditions cannot be met, e.g. where the welds are accessible from one side only, the joints shall be executed as lesser bevelled welds with an open root and an

attached or an integrally machined or cast, permanent weld pool support (backing) as shown in Figure 15.6.




Figure 15.6 Single-side welds with permanent weldpool supports (backings)

3.1.4 The weld shapes illustrated in Figure 15.7 shall be used for clad plates. These weld shapes shall be used in analogous manner for joining clad plates to (unalloyed and low alloyed) hull structural steels.




Figure 15.7 Weld shapes for welding of clad plates

3.2 Corner, T and double-T (cruciform) joints

3.2.1 Corner, T and double-T (cruciform) joints with complete union of the abutting plates shall be made as

single or double-bevel welds with a minimum shown in Figure 15.8 and with grooving of the root and capping from the opposite side.




Figure 15.8 Single and double-bevel welds with full root penetration

The effective weld thickness shall be assumed as the thickness of the abutting plate. Where proof of fatigue strength is required, see Section 17, the detail category depends on the execution (quality) of the weld.

3.2.2 Corner, T and double-T (cruciform) joints with a defined incomplete root penetration, as shown in Figure 15.9, shall be made as single or double-bevel welds, as described in 3.2.1, with a back-up weld but without grooving of the root.

The effective weld thickness may be assumed as the thickness of the abutting plate t , where f is the incomplete root penetration of $0,2 t$ with a maximum of 3 mm, which is to be balanced by equally sized double fillet welds on each side. Where proof of fatigue strength is required, see Section 17, these welds are to be assigned to type D1.




Figure 15.9 Single and double-bevel welds with defined incomplete root penetration

3.2.3 Corner, T and double-T (cruciform) joints with both an unwelded root face c and a defined incomplete

root penetration f shall be made in accordance with Figure 15.10.




Fig. 15.10 Single and double-bevel welds with unwelded root face and defined incomplete root penetration

The effective weld thickness shall be assumed as the thickness of the abutting plate t minus $(c + f)$, where f is to be assigned a value of $0,2 t$ subject to a maximum of 3 mm. Where proof of fatigue strength is required, see Section 17, these welds are to be assigned to types D2 or D3.

3.2.4 Corner, T and double-T (cruciform) joints which are accessible from one side only may be made in accordance with Figure 15.11 in a manner analogous to the butt joints referred to in 3.1.3 using a weld pool support (backing), or as single-side, single bevel welds in a manner similar to those prescribed in 3.2.2.

The effective weld thickness shall be determined by analogy with 3.1.3 or 3.2.2, as appropriate. Wherever possible, these joints should not be used where proof of fatigue strength is required, see Section 17.




Figure 15.11 Single-side welded T joints

3.2.5 Where corner joints are flush, the weld shapes shall be as shown in Figure 15.12 with bevelling of at least 30° of the vertically drawn plates to avoid the danger of lamellar tearing. A similar procedure is to be followed in the case of fitted T joints (uniting three plates) where the abutting plate is to be socketed between the aligned plates.




Figure 15.12 Flush fitted corner joints

3.2.6 Where, in the case of T joints, the direction of the main stress lies in the plane of the horizontal plates (e.g. the plating) shown in Figure 15.13 and where the connection of the perpendicular (web) plates is of secondary importance, welds connecting three plates may be made in accordance with Figure 15.13 (with the exception of those subjected mainly to dynamic loads).




Figure 15.13 Three plate connection

The effective thickness of the weld connecting the horizontal plates shall be determined in accordance with 3.2.2. The requisite "a" dimension is determined by the joint uniting the vertical (web) plates and shall, where necessary, be determined in accordance with Table 15.3 or by calculation as for fillet welds.

The following table shows reference values for the design of three plate connections at rudders, steering nozzle, etc.

Plating thickness t_0 [mm]	≤ 10	12	14	16	18	≥ 20
min. weld gap x [mm]	6	7	8	10	11	12
min. web thickness t_s [mm]	10	12	14	16	18	20

3.3 Fillet weld connections


3.3.1 In principle fillet welds are to be of the double fillet weld type. Exceptions to this rule (as in the case of closed box girders and mainly shear stresses parallel to the weld) are subject to approval in each individual case. The throat thickness "a" of the weld (the height of the inscribed isosceles triangle) shall be determined in accordance with Table 15.3 or by calculation according to C. The leg length of a fillet weld is to be not less than 1,4 times the throat thickness "a". For fillet welds at doubling plates, see 2.4.3; for the welding of the deck stringer to the sheer strake, see Section 8, B.3 and for bracket joints, see C.2.7.

3.3.2 The relative fillet weld throat thicknesses specified in Table 15.3 relate to normal and higher strength hull structural steels and comparable structural steels. They may also be generally applied to high strength structural steels and non-ferrous metals provided that the "tensile shear strength" of the weld metal used is at least equal to the tensile strength of the base material. Failing this, the "a" dimension shall be increased accordingly and the necessary increment shall be established during the welding procedure test (see **BCS** Rules, Part A, Chapter 3-Welding, Section 12 Welding of Hull Structures, F). Alternatively proof calculation taking account of the properties of the metal may be presented.

Note:

In the case of higher-strength aluminium alloys (e.g. AlMg4,5Mn), such an increment may be necessary for

cruciform joints subject to tensile stresses, as experience shows that in the welding procedure tests the tensile-shear strength of fillet welds (made with matching filler metal) often fails to attain the tensile strength of the base material. See also *BCS Rules, Part A, Chapter 3 – Welding, Section 12-Welding of Hull Structures F.5.*



3.3.3 The throat thickness of fillet welds shall not exceed 0,7 times the lesser thickness of the parts to be connected (generally the web thickness). The minimum throat thickness is defined by the expression:

$$a_{\min} = \sqrt{\frac{t_1 + t_2}{3}} \quad [\text{mm}]$$

but not less than 2,5 mm

t_1 = thinner (e.g. the web) plate thickness [mm]

t_2 = thicker (e.g. the flange) plate thickness [mm]

A smaller minimum fillet weld throat thickness may be agreed to if its faultless execution is demonstrated by means of a welding procedure test.

3.3.4 It is desirable that the fillet weld section shall be flat faced with smooth transitions to the base material. Where proof of fatigue strength is required, see Section 17, machining of the weld (grinding to remove notches) may be required depending on the notch category. The weld should penetrate at least close to the theoretical root point.

3.3.5 Where mechanical welding processes are used which ensure deeper penetration extending well beyond the theoretical root point and where such penetration is uniformly and dependably maintained under production conditions, approval may be given for this deeper penetration to be allowed for in determining the throat thickness. The effective dimension:

$$a_{\text{deep}} = a + \frac{2 \min e}{3} \quad [\text{mm}]$$

shall be ascertained in accordance with Figure 15.14 and by applying the term "min e" to be established for each welding process by a welding procedure test. The throat thickness shall not be less than the minimum throat thickness related to the theoretical root point.

Figure 15.14 Fillet welds with increased penetration

3.3.6 When welding on top of shop primers which are particularly liable to cause porosity, an increase of the "a" dimension by up to 1 mm may be stipulated depending on the welding process used. This is specially applicable where minimum fillet weld throat thicknesses are employed. The size of the increase shall be decided on a case by case basis considering the nature and severity of the stressing following the test results of the shop primer in accordance with the Rules, Part A, Chapter 3. Section 13 to 16. Steam Boilers, Pressure Vessels, Machinery Components, F. This manner to welding processes made for inadequate root

3.3.7 Strengthened fillet welds continuous on both sides are to be used in areas subjected to severe dynamic loads (e.g. for connecting the longitudinal and transverse girders of the engine base to top plates close to foundation bolts, see Table 15.3), unless single or double-bevel welds are stipulated in these locations. In these areas the "a" dimension shall equal 0,7 times the lesser thickness of the parts to be welded.

3.3.8 Intermittent fillet welds in accordance with Table 15.3 may be located opposite one another (chain intermittent welds, possibly with scallops) or may be staggered (see Figure 15.15). In case of small sections other types of scallops may be accepted.

In water and cargo tanks, in the bottom area of fuel oil tanks and of spaces where condensed or sprayed water may accumulate and in hollow components

(e.g. rudders) threatened by corrosion, only continuous or intermittent fillet welds with scallops shall be used. This applies accordingly also to areas, structures or spaces exposed to extreme environmental conditions or which are exposed to corrosive cargo.

There shall be no scallops in areas where the plating is subjected to severe local stresses (e.g. in the bottom section of the fore ship) and continuous welds are to be preferred where the loading is mainly dynamic.




Figure 15.15 Scallop, chain and staggered welds

3.3.9 The throat thickness a_u of intermittent fillet welds is to be determined according to the selected pitch ratio b/ℓ by applying the formula:

$$a_u = 1,1 \cdot a \left[\frac{b}{\ell} \right] [\text{mm}]$$

a = required fillet weld throat thickness [mm] for a continuous weld according to Table 15.3 or determined by calculation

b = pitch = $e + \ell$ [mm]

e = interval between the welds [mm]

ℓ = length of fillet weld [mm]

The pitch ratio b/ℓ should not exceed 5. The maximum

unwelded length ($b - \ell$ with scallop and chain welds, or $b/2 - \ell$ with staggered welds) should not exceed 25 times the lesser thickness of the parts to be welded. The length of scallops should, however, not exceed 150 mm.

3.3.10 Lap joints should be avoided wherever possible and are not to be used for heavily loaded components. In the case of components subject to low loads lap joints may be accepted provided that, wherever possible, they are orientated parallel to the direction of the main stress. The width of the lap shall be $1,5 t + 15$ mm (t = thickness of the thinner plate). Except where another value is determined by calculation, the fillet weld throat thickness " a " shall equal 0,4 times the lesser plate thickness, subject to the requirement that it shall not be less than the minimum throat thickness required by 3.3.3. The fillet weld must be continuous on both sides and must meet at the ends.

3.3.11 In the case of plug welding, the plugs should, wherever possible, take the form of elongated holes lying in the direction of the main stress. The distance between the holes and the length of the holes may be determined by analogy with the pitch " b " and the fillet weld length " ℓ " in the intermittent welds covered by 3.3.8. The fillet weld throat thickness " a_u " may be established in accordance with 3.3.9. The width of the holes shall be equal to at least twice the thickness of the plate and shall not be less than 15 mm. The ends of the holes shall be semi-circular. Plates or sections placed underneath should at least equal the perforated plate in thickness and should project on both sides to a distance of $1,5 \times$ the plate thickness subject to a maximum of 20 mm. Wherever possible only the necessary fillet welds shall be welded, while the remaining void is packed with a suitable filler. Lug joint welding is not allowed.

4. Welded joints of particular components

4.1 Welds at the ends of girders and stiffeners

4.1.1 As shown in Figure 15.16, the web at the end of intermittently welded girders or stiffeners is to be continuously welded to the plating or the flange plate, as applicable, over a distance at least equal to the depth

"h" of the girder or stiffener subject to a maximum of 300 mm. Regarding the strengthening of the welds at the ends, extending normally over $0,15 \cdot \ell$ of the span, see Table 15.3.




Figure 15.16 Welds at the ends of girders and stiffeners

4.1.2 The areas of bracket plates should be continuously welded over a distance at least equal to the length of the bracket plate. Scallop is to be located only beyond a line imagined as an extension of the free edge of the bracket plate.

4.1.3 Wherever possible, the free ends of stiffeners shall abut against the transverse plating or the webs of sections and girders so as to avoid stress concentrations in the plating. Failing this, the ends of the stiffeners are to be sniped and continuously welded over a distance of at least $1,7 h$ subject to a maximum of 300 mm.

4.1.4 Where butt joints occur in flange plates, the flange shall be continuously welded to the web on both sides of the joint over a distance at least equal to the width of the flange.

4.2 Joints between section ends and plates

4.2.1 Welded joints connecting section ends and plates may be made in the same plane or lapped. Where no design calculations have been carried out or stipulated for the welded connections, the joints may be analogously to those shown in Figure 15.17.

4.2.2 Where the joint lies in the plane of the plate it may conveniently take the form of a single-bevel butt weld with fillet. Where the joint between the plate and the section end overlaps, the fillet weld must be continuous on both sides and must meet at the ends

The necessary "a" dimension is to be calculated in accordance with C.2.6. The fillet weld throat thickness is not to be less than the minimum specified in 3.3.3.

4.3 Welded propeller bracket joints

4.3.1 Unless cast in one piece or provided with integrally cast welding flanges analogous to those prescribed in 2.1.7, see Fig. 15.18, strut barrel and struts are to be connected to each other and to the shell plating in the manner shown in Fig. 15.19.

4.3.2 In the case of single-strut brackets no welding is to be performed on the arm or close to the position of constraint. Such components must be provided with integrally forged or cast welding flanges.




Figure 15.17 Joints uniting section ends and plates





Figure 15.18 Propeller bracket with integrally cast welding flanges



t = Plating thickness in accordance with Section 6, F. in [mm]

$$t' = \frac{d}{3} + 5 \text{ [mm]} \quad \text{where } d < 50 \text{ mm.}$$

$$t' = 3 \sqrt{d} \text{ [mm]} \quad \text{where } d \geq 50 \text{ mm.}$$

For shaft brackets of elliptically shaped cross section d may be substituted by $2/3 d$ in the above formulae.


Figure 15.19 Propeller bracket without integrally cast welding flanges

4.4 Rudder coupling flanges

4.4.1 Unless forged or cast steel flanges with integrally forged or cast welding flanges in conformity with 2.1.7 are used, horizontal rudder coupling flanges are to be joined to the rudder body by plates of graduated thickness and full penetration single or double-bevel welds as prescribed in 3.2.1, see Figure 15.20. See also Section 12, E.1.4 and E.2.4.

4.4.2 Allowance shall be made for the reduced strength of the coupling flange in the thickness direction, see 1.5 and 2.5. In case of doubt, proof by calculation of the adequacy of the welded connection shall be produced.

4.4.3 The welded joint between the rudder stock (with thickened collar, see 2.1.8) and the flange shall be made in accordance with Figure 15.21.



t = plating thickness [mm] see Section 12, F.3.1

t_f = Actual flange thickness in [mm]

$$t' = \frac{t_f}{3} + 5 \text{ [mm]} \quad \text{where } t_f < 50 \text{ mm.}$$

$$t' = 3 \sqrt{t_f} \text{ [mm]} \quad \text{where } t_f \geq 50 \text{ mm.}$$

Fig. 15.20 Horizontal rudder coupling flanges




Figure 15.21 Welded joint between rudder stock and coupling flange

C. Stress Analysis**1. General analysis of fillet weld stresses****1.1 Definition of stresses**

For calculation purposes, the following stresses in a fillet weld are defined (see also Figure 15.22):

$\sigma_{\perp}$ = Normal stresses acting vertically to the direction of the weld seam

$\tau_{\perp}$ = Shear stress acting vertically to the direction of the weld seam

$\tau_{\parallel}$ = Shear stress acting in the direction of the weld seam

Normal stresses acting in the direction of the weld seam need not be considered.

For calculation purposes the weld seam area is $a \cdot \ell$.

Due to equilibrium conditions the following applies to the flank area vertical to the shaded weld seam area:

$$\tau_{\perp} = \sigma_{\perp}$$

The equivalent stress is to be calculated by the following formula:

$$\sigma_v = \sqrt{\sigma_{\perp}^2 + \tau_{\perp}^2 + \tau_{\parallel}^2}$$




Figure 15.22 Definition of stresses in a fillet weld

1.2 Definitions

a = Throat thickness [mm]

ℓ = Length of fillet weld [mm]

P = Single force [N]

M = Bending moment at the position considered [Nm]

Q = Shear force at the point considered [N]

S = First moment of the cross sectional area of the flange connected by the weld to the web in relation to the neutral beam axis [cm³]

I = Moment of inertia of the girder section [cm⁴]

W = Section modulus of the connected section [cm³]

2. Determination of stresses**2.1 Fillet welds stressed by normal and shear forces**

Flank and frontal welds are regarded as being equal for the purposes of stress analysis (LCC). In view of this, normal and shear stresses are calculated as follows:

$$\sigma = \tau = \frac{P}{\sum a \cdot \ell} \quad [\text{N/mm}^2]$$

Joint as shown in Fig. 15.23:




Figure 15.23 Fillet weld joint with normal and shear forces

- Stresses in frontal fillet welds:

$$\tau_{\perp} = \frac{P_1}{2 \cdot a (\ell_1 + \ell_2)} \quad [\text{N/mm}^2]$$

$$\tau_{\parallel} = \frac{P_2}{2 \cdot a (\ell_1 + \ell_2)} \pm \frac{P_2 \cdot e}{2 \cdot a \cdot F_t} \quad [\text{N/mm}^2]$$

$$F_t = (\ell_1 + a) \cdot (\ell_2 + a) \quad [\text{N/mm}^2]$$

- Stresses in flank fillet welds:

$$\tau_{\perp} = \frac{P_2}{2 \cdot a (\ell_1 + \ell_2)} \quad [\text{N/mm}^2]$$

$$\tau_{\parallel} = \frac{P_1}{2 \cdot a (\ell_1 + \ell_2)} \pm \frac{P_2 \cdot e}{2 \cdot a \cdot F} \quad [\text{N/mm}^2]$$

ℓ_1, ℓ_2, e in [mm]

- Equivalent stress for frontal and flank fillet welds:

$$\sigma_v = \sqrt{\tau_{\perp}^2 + \tau_{\parallel}^2}$$

Joint as shown in Figure 15.24




Figure 15.24 Fillet weld joint with normal and shear forces

$$\tau_{\perp} = \frac{P_2}{2 \cdot \ell \cdot a} + \frac{3 \cdot P_1 \cdot e}{\ell^2 \cdot a} \quad [\text{N/mm}^2]$$

$$\tau_{\parallel} = \frac{P_1}{2 \cdot \ell \cdot a} \quad [\text{N/mm}^2]$$

Equivalent stress:

$$\sigma_v = \sqrt{\tau_{\perp}^2 + \tau_{\parallel}^2}$$

2.2 Fillet weld joints stressed by bending moments and shear forces

The stresses at the fixing point of a girder are calculated as follows (in Figure 15.25 a cantilever beam is given as an example):




Figure 15.25 Fixing point of a cantilever beam

- Normal stress due to bending moment:

$$\sigma_{\perp(z)} = \frac{M}{I_s} z \quad [\text{N/mm}^2]$$

$$\sigma_{\perp \max} = \frac{M}{I_s} e_u \quad [\text{N/mm}^2] \quad \text{if } e_u > e_0$$

$$\sigma_{\perp \max} = \frac{M}{I_s} e_0 \quad [\text{N/mm}^2] \quad \text{if } e_u < e_0$$

- Shear stress due to shear force:

$$\tau_{\parallel(z)} = \frac{Q \cdot S_s(z)}{10 \cdot I_s \cdot \sum a} \quad [\text{N/mm}^2]$$

$$\tau_{\parallel \max} = \frac{Q \cdot S_{s \max}}{20 \cdot I_s \cdot a} \quad [\text{N/mm}^2]$$

I_s = moment of inertia of the welded joint related to the x-axis [cm⁴]

$S_s(z)$ = the first moment of the connected weld section at the point under consideration [cm³]

z = distance from the neutral axis [cm]

- Equivalent stress:

It has to be proved that neither $\sigma_{\perp \max}$ in the region of the flange nor $\tau_{\parallel \max}$ in the region of the neutral axis nor the equivalent stress $\sigma_v = \sqrt{\sigma_{\perp}^2 + \tau_{\parallel}^2}$ exceed the permitted limits given in 2.8 at any given point. The equivalent stress σ_v should always be calculated at the web-flange connection.

2.3 Fillet welded joints stressed by bending and torsional moments and shear forces

Regarding the normal and shear stresses resulting from bending, see 2.2. Torsional stresses resulting from the torsional moment M_T are to be calculated:

$$\tau_T = \frac{M_T \cdot 10^3}{2 \cdot a \cdot A_m} \quad [\text{N/mm}^2]$$

M_T = torsional moment [Nm]

A_m = sectional area [mm²] enclosed by the weld seam

The equivalent stress composed of all three components (bending, shear and torsion) is calculated by means of the following formulae:

$$\sigma_v = \sqrt{\sigma_{\perp}^2 + \tau_{\parallel}^2 + \tau_T^2} \quad [\text{N/mm}^2]$$

where $\tau_{\parallel}$ and τ_T have not the same direction

$$\sigma_v = \sqrt{\sigma_{\perp}^2 + (\tau_{\parallel} + \tau_T)^2} \quad [\text{N/mm}^2]$$

where $\tau_{\parallel}$ and τ_T have the same direction

2.4 Continuous fillet welded joints between web and flange of bending girders

The stresses are to be calculated in way of maximum shear forces. Stresses in the weld's longitudinal direction need not to be considered. In the case of continuous double fillet weld connections the shear stress is to be calculated as follows:

$$\tau_{\parallel} = \frac{Q \cdot S}{20 \cdot I \cdot a} \quad [\text{N/mm}^2]$$

The fillet weld thickness required is:

$$a_{\text{req}} = \frac{Q \cdot S}{20 \cdot I \cdot \tau_{\text{per}}} \quad [\text{mm}]$$

2.5 Intermittent fillet welded joints between web and flange of bending girders

Shear stress:

$$\tau_{\parallel} = \frac{Q \cdot S \cdot \alpha}{20 \cdot I \cdot a} \left(\frac{b}{\ell} \right) \quad [\text{N/mm}^2]$$

b = pitch

α = 1,1 stress concentration factor which takes into account increases in shear stress at the ends of the fillet weld seam " ℓ "

The fillet weld thickness required is

$$a_{\text{req}} = \frac{Q \cdot S \cdot 1,1}{20 \cdot I \cdot \tau_{\text{zul}}} \left(\frac{b}{\ell} \right) \quad [\text{N/mm}^2].$$




Figure 15.26 Intermittant fillet welded joints

2.6 Fillet weld connections on overlapped profile joints

2.6.1 Profiles joined by means of two flank fillet welds (see Figure 15.27):

$$\tau_{\perp} = \frac{Q}{2 \cdot a \cdot d} \quad [\text{N/mm}^2]$$

$$\tau_{\parallel} = \frac{M \cdot 10^3}{2 \cdot a \cdot c \cdot d} \quad [\text{N/mm}^2]$$

The equivalent stress is:

$$\sigma_v = \sqrt{\tau_{\perp}^2 + \tau_{\parallel}^2} \quad [\text{N/mm}^2]$$

c, d, ℓ_1 , ℓ_2 , r [mm] see Figure 15.27

$$c = r + \frac{3 \ell_1 - \ell_2}{4} \quad [\text{mm}]$$




Figure 15.27 Fillet flank welds for profile joints

As the influence of the shear force can generally be neglected, the required fillet weld thickness may be determined by the following formula:

$$a_{\text{req}} = \frac{W \cdot 10^3}{1,5 \cdot c \cdot d} \quad [\text{mm}].$$

2.6.2 Profiles joined by means of two flank and two frontal fillet welds (all round welding as shown in Figure 15.28):

$$\tau_{\perp} = \frac{Q}{a (2d + \ell_1 + \ell_2)} \quad [\text{N/mm}^2]$$

$$\tau_{\parallel} = \frac{M \cdot 10^3}{a \cdot c (2d + \ell_1 + \ell_2)} \quad [\text{N/mm}^2]$$

The equivalent stress is:

$$\sigma_v = \sqrt{\tau_{\perp}^2 + \tau_{\parallel}^2}$$

$$a_{\text{req}} = \frac{W \cdot 10^3}{1,5 \cdot c \cdot d \left(1 + \frac{\ell_1 + \ell_2}{2d} \right)} \quad [\text{mm}]$$




Figure 15.28 Flank and frontal fillet welds for profile joints

2.7 Bracket joints

Where profiles are joined to brackets as shown in Figure 15.29, the average shear stress is:

$$\tau = \frac{3 \cdot M \cdot 10^3}{4 \cdot a \cdot d^2} + \frac{Q}{2 \cdot a \cdot d} \quad [\text{N/mm}^2]$$

d = length of overlap [mm]

The required fillet weld thickness is to be calculated from the section modulus of the profile as follows:

$$a_{\text{req}} = \frac{1000 \cdot W}{d^2} \quad [\text{mm}].$$

(The shear force Q has been neglected.)




Figure 15.29 A bracket joint with idealized stress distribution resulting from the moment M and shear force Q

2.8 Permissible stresses

The permissible stresses for various materials under mainly static loading conditions are given in Table 15.2. The values listed for high strength steels, austenitic stainless steels and aluminium alloys are based on the assumption that the strength values of the weld metal used are at least as high as those of the parent metal. If this is not the case, the "a"-value calculated shall be increased accordingly (see also B.3.3.2).

Table 15.2 Permissible stresses in fillet weld seams

Material		R_{eH} or $R_{p0,2}$ [N/mm ²]	Permissible stresses [N/mm ²] equivalent stress, shear stress σ_{vp} , τ_p
normal strength hull structural steel	BCS-A/B/D/E	235	115
higher strength structural steels	BCS-A/D/E/F 32	315	145
	BCS-A/D/E/F 36	355	160
	BCS-A/D/E/F 40	390	175
high strength steels	S 460	460	200
	S 690	685	290
austenitic and austenitic-ferritic stainless steels	1.4306/304 L	180	110
	1.4404/316 L	190	
	1.4435/316 L	190	
	1.4438/317 L	195	
	1.4541/321	205	
	1.4571/316 Ti	215	
	1.4406/316 LN	280	130
	1.4429/316 LN	295	
	1.4439/317 LN	285	
	1.4462/318 LN	480	205
aluminium alloys	AlMg3/5754	80 (1)	35
	AlMg4,5Mn0,7/5083	125 (1)	56
	AlMgSi/6060	65 (2)	30
	AlSi1MgMn/6082	110 (2)	45
(1) Plates, soft condition (2) Sections, cold hardened			

Table 15.3 Fillet weld connections

Structural parts to be connected	Basic thickness of fillet welds a/t_0 (1) for double continuous fillet welds (2)	Intermittent fillet welds permissible (3)
Bottom structures Transverse and longitudinal girders to each other - to shell and inner bottom Center girder to flat keel and inner bottom Transverse and longitudinal girders and stiffeners including shell plating in way of bottom strengthening forward Machinery space Transverse and longitudinal girders to each other - to shell and inner bottom Inner bottom to shell Sea chests, water side inside	0,35 0,20 0,40 0,30 0,35 0,30 0,40 0,50 0,30	x x
Machinery foundation Longitudinal and transverse girders to each other and to the shell - to inner bottom and face plates - to top plates - in way of foundation bolts - to brackets and stiffeners longitudinal girders of thrust bearing to inner bottom	0,40 0,40 0,50 (4) 0,70 (4) 0,30 0,40	
Decks to shell (general) Deck stringer to sheerstrake (see also Section 8, B.3)	0,40 0,50	
Frames, stiffeners, beams etc. general in peak tanks bilge keel to shell	0,15 0,30 0,15	x x
Transverses, longitudinal and transverse girders general within 0,15 of span from supports cantilevers pillars to decks	0,15 0,25 0,40 0,40	x
Bulkheads, tank boundaries, walls of superstructures and deckhouses - to decks, shell and walls	0,40	
Hatch coamings - to deck - to longitudinal stiffeners	0,40 0,30	
Hatch covers general watertight or oiltight fillet welds	0,15 0,30	x (5)
Rudder plating to webs	0,25	x
Stem plating to webs	0,25	x
(1) t_0 = thickness of the thinner plate. (2) In way of large shear forces larger throat thicknesses may be required on the bases of calculations according to C. (3) For intermittent welding in spaces liable to corrosion B.3.3.8 is to be observed. (4) For plate thicknesses exceeding 15 mm single or double bevel butt joints with, full penetration or with defined incomplete root penetration according to Fig. 15.8 to be applied. (5) Excepting hatch covers above holds provided for ballast water		

SECTION 16**NOISE, VIBRATION AND SHOCK CONSIDERATIONS**

	Page
A. General	16-2
1. Noise, vibration and shock aspects as part of the survivability of a naval ship	
2. Application	
B. Acoustics	16-3
1. Definitions	
2. Applicable standards	
3. Acoustic signatures	
4. Noise measurements	
C. Vibration	16-15
1. General	
2. Applicable standards	
3. Habitability	
4. Vibration induced fatigue of hull structures	
5. Vibration of mast mounted electronic equipment	
6. Vibration of main/auxiliary machinery and equipment	
D. Shock Strength	16-22
1. Shock loads from underwater explosion	
2. Proof of shock safety	
3. Shock strength of the hull	
4. Protection of the equipment	

A. General

1. Noise, vibration and shock aspects as part of the survivability of a naval ship

1.1 The elements of survivability are specified in detail in Section 1, C.3.

Noise and vibration are main components determining susceptibility, shock behaviour determines vulnerability.

Noise, vibration and shock requirements have to be agreed upon between Naval Authority and shipyard in each individual case according to the concept of operation. Recommendations given in this Section in general form may be only regarded as a guideline for establishing the actual building specification between Naval Authority and shipyard.

1.2 Theoretical examinations and / or approval of noise, vibration and shock related aspects are not part of the classification process. Additional services can be offered by **BCS**, if desired.

Note:

*Please note that **BCS** is offering a wide range of services like Computation of Fluid Dynamics (and Vibration Analysis by Finite techniques ,shock simulations ,noise*

2. Application

2.1 Acoustics

2.1.1 Naval ships have to maintain certain tactical tasks which normally include the concept of signature of the vessel. The acoustic signature as part of the concept of signature is described in B.3.

2.1.2 Requirements for the acoustic signature have to be agreed upon between Naval Authority and shipyard in each individual case.

2.1.3 Depending on the requirements which were agreed upon measures have to be foreseen with the aim to keep the specified noise limits onboard as well as radiated-noise level limits defined for the surrounding environment (sea and air) of the vessel.

2.1.4 Depending on the characteristic of noise level spectra and the exposure time noise may diminish the crew's and ship's readiness for action e.g. as follows:

- Increasing of detection range of targets
- Reduction of efficiency of the own sonar sensor system
- Reduction of observation of underwater signals and of signals above the sea surface
- Diminution of speech interference level for receiving and giving orders
- Reduction of crew's performance and concentration ability
- Negative influence on the crew's health
- Impairment of the recreation possibilities for the crew in messes, living quarters and cabins

2.2 Vibration

2.2.1 Vibration affect the fulfilment of the ship's tactical tasks in various ways. Typical adverse vibration is:

- Vibration at weapon and sensor foundations originating from the propulsion plant or gun firing
- Vibration at the foundations of electronic devices and equipment mounted at exposed positions, like masts
- Vibration affecting habitability and, in severe cases, the health of the crew

2.2.2 Therefore measures to realize sufficiently low vibration levels to ensure trouble-free operation of the naval ship have to be established.

2.3 Shock

2.3.1 Naval ships are exposed to shock forces created by air or underwater explosions. Under the expression "shock" a very short time, high frequent (in relation to the basic natural frequency of the ship's hull) transmission of kinetic energy to the hull shall be

understood. In comparison with an "impact" such a shock is characterized by a much more complex time history.

2.3.2 In the underwater explosion a superheated gas bubble under high pressure is created. This gas bubble causes a pressure wave exciting strong low frequency vibration of the hull girder (so called whipping vibration), which even can be magnified due to resonance with the gas bubble contraction and expansion frequency. These Rules cover the case of large distance detonations only, i.e. it is assumed that there is no direct contact between gas bubble and hull.

2.3.3 Shock loads may adversely affect the ship's capability to fulfil its tactical task in various ways:

- Destroying main structural elements of the hull due to direct effects of the shock wave
- Causing malfunctions of main or auxiliary equipment connected rigidly or elastically to the ship structure
- Harming operational capability or health of crew members

B. Acoustics

1. Definitions

1.1 Airborne noise, sound pressure level

The acoustic performance emitted as airborne noise is defined as sound pressure level on a logarithmic scale given by:

$$L = 20 \log \left(\frac{p}{p_0} \right) \text{ [dB]}$$

p = rms value of the measured sound pressure between 16 Hz and 16 000 Hz

p_0 = Reference level

$$= 2 \cdot 10^{-5} \text{ Pa}$$

1.2 A-weighted sound pressure level

The A-weighted equivalent continuous sound pressure level is measured by using the frequency weighting "A" as specified in IEC Publication 61672-1: 2002.

1.3 Boom, booming

Booming is a deep, hollow resonant sound, low frequency sound in the frequency range between 16 Hz and 125 Hz and is mainly caused due to one or more discrete tonal components which have significantly greater amplitudes than those of adjacent spectrum levels and are to be felt subjectively annoying. Discrete tonal components are to be frequently measured in airborne noise spectra on board ships but they are not annoying in each case. Booming can only be subjectively detected.

1.4 N-weighted sound pressure level

The N-weighting has to be executed with the Noise Rating Curves (NRC) according to ISO-Standard R 1996-1967. The noise rating number is found by plotting the 1/1 octave band levels via the NRC-curves to which the spectrum is tangent.

1.5 Sonar self noise level

The disturbance level for the ship's own sensor system is depending on the ambient noise and the self noise level of the vessel e.g. structure-borne noise emitted by machinery and other equipment as well as on hydrodynamic effects at the appendages of the hull. Special boundary conditions have to be defined in the building specification.

1.6 Steady noise with audible discrete tones

This type of noise has components at one or more discrete frequencies which have significantly greater amplitudes than those of adjacent spectrum level. Audible discrete tonal components of noise (tonality and/or booming) can occur in the whole audible frequency range between 16 Hz and 16 000 Hz.

1.7 Steady noise without audible discrete tones

When the level fluctuations of the indicating pointer or the display on the sound level meter are equal or less than ± 3 decibels. This type of noise is frequently referred as "broad-band" noise. Obvious tonal components of noise (tonality and/or booming) in the whole audible frequency range between 16 Hz and 16 000 Hz are absent or negligibly small.

1.8 Speech interference level

To judge an airborne sound spectrum in relation to speech clarity, the speech interference level (SIL) is to be determined by forming the arithmetic average of the 1/1 octave band level of the frequencies at 500, 1 000, 2 000 and 4 000 Hz. Then the limit value is defined by the following formula:

$$SIL = \frac{1}{4} \cdot (L_{oct500} + L_{oct1000} + L_{oct2000} + L_{oct4000}) [dB]$$

L_{oct} = 1/1 octave bend level [dB]

1.9 Vibration velocity level (structure-borne noise)

The structure-borne noise in a structure or on its surface is created by oscillating excitation forces transmitted to the structure. The structure-borne noise is defined as vibration velocity level as follows:

$$L = 20 \log \left(\frac{v}{v_0} \right) [dB]$$

v = rms value of the measured vibration velocity between 10 Hz and 16 000 Hz

v_0 = reference velocity

= 10^{-9} m/s acc. to ISO 1683-1983

1.10 Vibration acceleration level (structure - borne noise)

The structure-borne noise is measured as vibration acceleration level as follows:

$$L = 20 \log \left(\frac{a}{a_0} \right) [dB]$$

a = rms value of the measured vibration acceleration between 10 Hz and 16 000 Hz

a_0 = Reference acceleration

= 10^{-6} m/s² acc. to ISO 1683-1983

1.11 Underwater noise

Underwater noise is defined as a sound pressure level:

$$L = 20 \cdot \log \left(\frac{p_w}{p_{w0}} \right) [dB]$$

p_w = rms value of the measured underwater sound pressure between 1 Hz and 16 000 Hz

p_{w0} = Reference pressure

= 10^{-6} Pa (1 μ Pa) (international)

1.12 Radiated-noise

Here: Noise radiated into the water by a naval surface ship. The radiated-noise can be used by passive listening sonar to detect the presence of a vehicle at a considerable distance. The radiated-noise level limit curves mainly depend on the underwater noise measuring range (shallow or deep water), corresponding operational conditions of the vessel and conversion procedures to 1Hz bandwidth and / or 1m etc. The radiated-noise limits have to be agreed on in detail between Naval Authority and shipyard for the individual vessel. In these Rules the radiated-noise level has to be given and to be measured as third-octave band levels, re 1 μ Pa.

1.13 Concept of signatures

All relevant single signatures which can be caused by the system ship are collected in the concept of signatures of the vessel. In general, single signatures are not independent from each other.

1.14 Single signature

A single signature of a vessel describes the behaviour of the vessel specifically related to physical subjects, e.g. radar, optic, acoustic, magnetic etc.

- ISO 31/VII, "Quantities and units of acoustics"

- DIN EN 61 260, "Octave, half-octave and third-octave band filters intended for the analyses of sound and vibration"

1.15 Acoustic signature

Noise requirements e.g. airborne noise, structure-borne noise and radiated-noise level limit curves, corresponding operating conditions etc. as well as for the sonar system are to be collected and defined in the "acoustic signature" of the vessel. In general, single noise limit values, see 3. are not independent from each other, see also A. 1.1.

- DIN EN 60 804, "Integrating/averaging sound level meters"

- DIN EN 61 672-1 (IEC 61 672-1 :2002), "Sound level meters – Part 1"

– DIN EN 61 672 (IEC 60 942 : 2003), "Sound calibrators"

1.16 Mechanical ventilation

Air supply and exhaust systems are to be foreseen for engine rooms, stores, workshops, technical rooms, etc.

- ISO 717/1, "Acoustics - Rating of sound insulation in buildings and of building elements -Part 1: Airborne sound insulation in buildings and interior elements"

- ISO 717/2, "Acoustics - Rating of sound insulation in buildings and of building elements -Part 2: Impact sound insulation"

1.17 HVAC-systems

Heating, venting and air-conditioning systems are to be foreseen for accommodation and work spaces of the crew and officers.

- ISO 140/4, "Acoustic - Measurement of sound insulation in buildings and of building elements Part 4: Field measurements of airborne sound insulation between rooms"

1.18 SAT: Sea acceptance trials**1.19 FAT: Factory acceptance tests**

- ISO 140/7, "Acoustics - Measurements of sound insulation in buildings and of building elements - Part 7: Field measurements of impact sound insulations of floors"

1.20 HAT: Harbour acceptance tests**2. Applicable standards**

2.1 For the definition of basic principles of acoustic procedures and measurements, as well as details of the devices and methods, it is necessary to rely on well proven national and international standards. Unless a particular standard edition is referred to explicitly, the latest edition of the following standards is to be applied:

- ISO 1996, "Acoustics - Description and measurement of environmental noise, Part 1 - 3"

- ISO 1999, "Acoustics - Determination of exceptional noise exposure and estimation of noise-induced hearing impairment"

2.2 International standards

- ISO 2923, "Acoustics - Measurement of Noise on Board Vessels"

- DIN 45681, "Detection of tonal components of noise and determination of a tone adjustment for the assessment of noise emission"

2.3 Additional standards and regulations defined by the Naval Authority

Other standards and regulations to be included in each individual case on demand of the Naval Authority shall be discussed and mutually agreed upon with the shipyard and **BCS**.

3. Acoustic signatures

3.1 General

Table 16.1 summarises the qualitative acoustic criteria on naval ships concerning the sound components:

- Structure-borne noise
- Airborne noise
- Radiated-noise

3.2 Permissible sound pressure levels for accommodation and work spaces of the crew

3.2.1 The values of the permissible sound pressure and speech interference levels have to be defined by the Naval Authority for each individual building program. If this is not possible because of certain circumstances the values given in Table 16.2 may be used.

3.2.2 Special regulations

3.2.2.1 If relevant noise sources are operating only up to 4 hours within 24 hours, the permissible sound pressure limit in dB(A) according to Table 16.2 can be increased by 5 dB. Excepted from this regulation are item nos. 1.1, 1.2, 1.3, 3.2, 3.4 shown in Table 16.2.

3.2.2.2 If relevant noise sources are operating only up to 10 minutes within 24 hours, the permissible sound pressure limit in dB(A) according to Table 16.2 can be increased by 10 dB. Excepted from this regulation are item nos. 1.1, 1.2, 1.3, 3.2, 3.4, 4.1, 4.2 and 4.5 shown in Table 16.2.

3.2.2.3 Sound limit values concerning sound and impact insulation in the accommodation and work spaces of the crew are to be agreed upon Naval Authority, shipyard and **BCS** for the individual Measurements shall be conducted according

3.2.3 Noise abatement measures

3.2.3.1 With the aim to maintain the noise limit values specified suitable noise abatement measures are to be installed in relevant accommodation and work spaces of the crew.

3.2.3.2 Permissible airborne and structure-borne noise limit curves are to be defined for relevant machinery for onboard situations and test bed foundations of suppliers. The noise limit curves can be used as criteria to judge the acoustic quality of shipboard equipment and effectiveness of noise reduction measures. FAT should be contractually agreed on.

3.2.4 Tolerances (airborne noise)

The following aspects have to be considered:

- Based on sound pressure levels which have been taken in each accommodation space respectively each cabin of the crew the power averaged sound pressure level has to be calculated for each individual deck. These average levels shall not exceed the noise limits as specified in Table 16.2 for individual spaces.
- The noise limits specified for the accommodation of the crew and officers (Table 16.2, item nos. 4.1, 4.2) may be exceeded by maximum 5 dB(A). After comparing the measured 1/1 octave band sound pressure spectra with the corresponding NR-curve, will decide whether the exceeding of the limit may still be accepted. The number of exceeding is limited to the whole naval ship.

- Other limit values as stated in Table 16.2 may be exceeded by maximum 3 dB(A) - except item nos. 1.1, 1.2, 1.3, 3.1, 3.2, 4.3, 4.4, 5.2. After comparing the measured 1/1 octave band sound pressure spectra with the corresponding NR-curve, **BCS** will decide whether the exceeding and the total number of exceeding the noise limits may still be accepted.

3.3 Permissible radiated-noise

3.3.1 Radiated-noise limit curves have to be defined for different operating conditions. These limit curves and boundary conditions are normally included in the confidential part of the building specification.

3.3.2 Based on the radiated-noise limit curves structure-borne noise limit curves should be estimated by the shipyard for the wetted shell structure and foundations of relevant shipboard equipment. In the next step structure-borne noise limit curves should be computed for each relevant noise sources for onboard situations and test bed foundations of suppliers.

3.3.3 At the end of the definition and detailed design phase of the ship the computed values for radiated-noise and applied methods have to be presented by the shipyard. The shipyard has to explain the procedure and estimations made to ensure that the radiated-noise limit curves are met.

3.4 Permissible sonar self noise

If the naval ship is equipped with an active or passive sonar sensor system, limit curves for the permissible sonar self noise level are to be defined by the Naval Authority and included in the confidential part of the building specification.

4. Noise measurements

4.1 General

4.1.1 Aim of measurements

The aim of noise measurements are to ensure that the

specified acoustic signatures can be maintained. Special tasks have to be agreed on between Naval Authority, shipyard and **BCS**.

Measurements and their evaluation will be organised and executed by the shipyard or carried out by experienced engineers employed by a specialized sub-contractor, which has to be accepted by **BCS**. **BCS** will survey the whole measurement procedure. If desired by the Naval Authority or the shipyard, **BCS** can participate in measurements and their evaluation with own experts.

4.1.2 Treatment of ship series, conversions

In a series of ships of the same family/class the required noise measurements have to be conducted for the first ship of the series. The measurement program can be reduced for each further vessel of the series if the program has been agreed upon between Naval Authority and shipyard.

After modifications/conversions influencing the noise situation of the vessel **BCS** will decide which measurements have to be repeated.

4.1.3 Noise Survey Program

4.1.3.1 Establishment of the program

The shipyard has to establish the complete Noise Survey Program according to Technical -Tactical Requirements (TTF). The Program has to be agreed on with the Naval Authority and **BCS**. The main parts of the Noise Survey Program are normally already the confidential part of the building specification

4.1.3.2 Parts of the program

The program will normally consist of the following parts:

4.1.3.2.1 Airborne and structure-borne noise measurements are to be conducted at relevant noise sources in the test field of the manufacturer or sub-contractor (FAT).

Table 16.1 Acoustic criteria for naval ships

Type of noise	Noise level	Frequency composition	Duration of action
Structure-borne noise:	The levels are to be kept low to avoid impermissible noise aboard and to avoid that via excitation of the ship's structure and shell an impermissible radiated-noise occurs.	Discrete tones are to be avoided (e.g. tones caused by unbalanced masses, working frequencies), because they are significant in radiated-noise and may lead to an identification of the ship by the enemy.	Short time noise events (impacts, stopping hits, hydraulic impulses) are to be avoided, because of its remarkable characteristics in the radiated-noise.
Airborne noise:	The noise level is to be kept low, to avoid health damage to the crew's hearing and other organs, as well as to avoid early tiring and prolonged reaction times. In addition speech identification and recreation of the crew in the living quarters should be ensured. Finally the contribution to the emission of radiated-noise shall be reduced.	Tones should not be included, because discrete tones may shift the limit of annoyance to lower levels. Discrete tones may have a spectral line effect in the radiated-noise. Booming effects have to be avoided.	With increasing exposure time of noise, the danger of health damage to the hearing of the crew is also increasing.
Radiated-noise:	High levels have to be avoided, because they would limit the effectiveness of the ship's own sonar sensors. In addition the detection range of targets will be increased.	Discrete tones are to be avoided, because spectral lines e.g. can be used for identification and detection of the ship. In addition discrete tones in the frequency range of the own sonar may be disturbing.	Impact and short time emissions of noise have to be avoided, because they get a higher degree of attention for the enemy sonar systems and disturb the own sonar system.

Table 16.2 Proposal for permissible sound pressure and speech interference levels for crew accommodation and work spaces

No.	Spaces / Working place on deck	Limit values in [dB] (4)								
		At anchor with own energy supply			Combat cruising speed/ Special operation cond. (1)			Maximum continuous speed v_0		
		dB(A)	NRC	SIL	dB(A)	NRC	SIL	dB(A)	NRC	SIL
1.	Working spaces									
1.1	Unmanned main & auxiliary engine rooms, control stations therein	110 (2, 5)	105 (2, 5)	—	110 (2, 5)	105 (2, 5)	—	110 (2, 5)	105 (2, 5)	—
1.2	Engine control rooms	—	—	—	80	75	73	80	75	73
1.3	Mechanical workshops	85	80	78	85	80	78	95 (2)	90	—
1.4	Electronical workshops	65	60	58	70	65	63	—	—	—
1.5	Equipment spaces/unmanned	—	—	—	85	80	—	85	80	—
2.	Service Spaces									
2.1	Galleys and pantries	70	65	—	70	65	—	—	—	—
3.	Control stations									
3.1	Bridge and chart room	—	—	—	65	60	58	65	60	58
3.2	Manned combat information center (CIC)	—	—	—	60	55	53	65	55	53
3.3	Operation control auxiliary rooms/unmanned	—	—	—	70	65	—	70	65	—
3.4	Rooms for navigation, telecommunication and sensor equipment/unmanned	—	—	—	75	70	—	75	70	—
3.5	Computer spaces/manned	—	—	—	65	60	58	65	60	58
4.	Accommodation									
4.1	Officer cabins	50	45	—	60	55	—	—	—	—
4.2	Living quarters for petty officers and crew	60	55	—	60	55	—	—	—	—
4.3	Mess rooms	55	50	48	65	60	58	—	—	—
4.4	Offices	60	55	—	65	60	—	—	—	—
4.5	Hospital	50	45	43	60	55	53	—	—	—
5.	Outdoor Spaces									
5.1	Working places on deck	—	80 (3)	78(3)	—	80(3)	78(3)	—	—	—
5.2	Open bridge/bridge wings	—	65 (6)	—	—	70(3)	68(3)	—	75(3)	73(3)
(1) Special operating conditions are e.g. mine hunting, mine sweeping, etc. (2) Not to be exceeded at any place where operational actions are executed. (3) Noise created by wind and waves is not considered. (4) Environmental conditions: wind < 4 Beaufort, continuous wind/sea state. (5) If very low values for radiated-noise are requested, these values have to be reduced. (6) The NR-Curve has to be maintained for 1/1 octave band levels mainly between 250 Hz to 8 000 Hz										

4.1.3.2.2 Airborne and structure-borne noise measurements are to be conducted at relevant noise sources aboard the ship e.g. during SAT and HAT.

4.1.3.2.3 Radiated-noise measurements are to be conducted according to the building specification.

4.1.3.2.4 Noise measurements are to be conducted to evaluate the sonar's self noise level, if applicable.

4.1.3.3 Detailed information

The Noise Survey Program shall contain all relevant data, drawings, noise limit curves, measurement protocol sheets, etc. necessary to conduct the measurements in a straight forward manner. It has to be ensured that all relevant structure-borne and airborne noise sources are indicated in the drawings (including air intake and outlet openings of mechanical ventilation and HVAC-systems). The final edition of thermal, fire and noise protection insulation drawings, data about the materials etc. are to be submitted.

A switch list, which contains exactly the operation condition of all relevant noise sources (on/off, rpm and/or performance, relevant excitation frequencies, etc.), has to be established for each measurement set.

4.1.3.4 The Noise Survey Program shall contain drawings showing all measuring positions with corresponding reference numbers as planned by the ship- yard. Noise measurement protocol sheets are to be prepared for each measurement set.

4.1.3.5 The Noise Survey Program has to be based on the final design stage of the ship and shall be presented in form of a document to **BCS** . The complete Program has to be submitted at least three months prior to each acoustic acceptance test.

4.2 Measurement conditions

4.2.1 Environmental conditions for SAT

Following environmental conditions have to be considered if no other definitions are agreed on in the building specification:

- Wind speed less than 4 Bft
- Sea state less than 3 (significant wave height approx. 1,25 m)
- Constant wind/wave conditions
- The minimum water depth depends mainly on the ship's speed and the test program.

4.2.2 Operational test conditions

If no requirements are agreed on in the building specification, the following recommendations should be observed:

4.2.2.1 Measurements on board the ship (SAT, HAT)

- Ship in the status of the displacement ready for combat (SAT, HAT)
- The course of the ship shall be as straight as possible. Minimum rudder movement is imperative. Rudder angle shall not exceed ± 5 degrees (SAT).
- In general, doors and windows are to be closed (SAT, HAT).
- Operating condition of all relevant noise sources according to the switch list for each measurement set, defined in 4.1.3.3 (SAT, HAT)
- Unnecessary human activities have to be avoided (SAT, HAT).

4.2.2.2 Radiated-noise measurements

The noise measurement range, measurement conditions as well as the test condition for each test run of the ship have to be agreed upon between Naval Authority, shipyard and **BCS**.

4.2.2.3 Sonar tests

These aspects are to be treated as confidential and should be discussed between shipyard, Naval Authority and **BCS** case by case.

4.2.3 Reproduction of results

The operational and environmental conditions shall be chosen according to the measurement program in such a way, that they can be reproduced for measurements to be repeated with sufficient accuracy.

4.3 Measurement instrumentation

4.3.1 Airborne noise

The instrumentation for measurement is to be chosen depending on the scope and accuracy defined in the Noise Survey Program according to 4.1.3.3. The following aspects on instrumentation have to be considered.

4.3.1.1 Integrating-averaging sound level meters are to be applied and should be able to store the measured data in the memory of the instrument.

4.3.1.2 The instrumentation including microphone, cables and recording devices, etc. shall meet the requirements for type 1 instrument specified in DIN EN 60804.

4.3.1.3 Each microphone shall be calibrated to have an essentially flat frequency response in a diffuse sound field.

4.3.1.4 A wind screen shall be used for indoor and outdoor measurements.

4.3.1.5 The wind screen shall not effect the measured A-weighted sound pressure level by more than 0,5 dB when there is no wind or in case the wind screen shall be used for indoor measurements.

4.3.1.6 1/1 octave and third-octave filters shall comply with the requirements of DIN EN 61260.

4.3.1.7 Class 1 sound calibrators shall be used and

comply with the requirements of DIN EN 60942 (IEC 60942: 2003).

4.3.1.8 Compliance verification of measuring instrumentation has to be done as follows:

- The compliance of the integrating-averaging sound level meter with the requirements of DIN EN 60 804 has to be verified by the manufacturer or other authorised organisation at least every two years.
- The compliance of the sound calibrator with the requirements of DIN EN 60942 (IEC 60942: 2003) has to be verified by the manufacturer or other authorised organisation at least every two years.
- The date of the last verification and confirmation of the compliance with the relevant standard is to be recorded to **BCS**.

4.3.1.9 An instrument suitable to store the time signal shall be available, in case that subjectively annoying low frequency noise (booming) or obvious tonal components (time records to be stored) occur.

4.3.2 Underwater noise

The instrumentation for underwater noise measurements has to be specially agreed.

4.3.3 Structure-borne noise

The instrumentation for underwater noise measurements has to be specially agreed.

4.4 Measurement procedure

4.4.1 Airborne noise measurements

4.4.1.1 Measurements in the accommodation and work spaces of the crew

If no particulars are agreed on in the building specification, the following procedures shall be applied:

4.4.1.1.1 Condition of spaces

- Measurements shall be conducted with closed doors, windows and hatches, etc.
- All spaces and rooms shall be fully equipped. The furniture shall be completely installed.
- Mechanical ventilation and air conditioning equipment shall be in normal operation (capacity to be in accordance with the design condition). All air conditioning systems shall be adjusted prior to measurements.
- For each measurement set all devices are in operation according to the switch list as defined in 4.1.3.3.

4.4.1.1.2 Measurement locations

- Height above floor of approx. 1,2 m
- At least 0,5 m away from reflecting surfaces (bulkheads, walls, ceilings, etc.)
- Distance to next position of microphone approx. 2,0 m, if possible
- Distance to measuring expert at least 0,5 m
- At the bridge wing lee side preferable
- In engine rooms with a height of several decks: at every deck approx. 1,2 m above floor
- At any work space measurements shall be carried out at the operator's ear position.
- In crew and officer cabins one measurement shall be taken in the centre of the room and one additional measurement shall be carried out at the head of the berth with the highest noise level.

4.4.1.1.3 Measuring conditions

- The equivalent continuous A-weighted sound pressure level in dB(A) shall be measured.

The sound level instrumentation shall be set to "fast" response. The measuring time shall be at least 15 seconds.

- During each measurement, the microphone shall be slowly moved horizontally and/or vertically over a distance of approx. $\pm 0,5$ m, if possible.

4.4.1.1.4 Evaluation of results

The measured values are to be rounded. For example:

- 56,2 dB(A) rounded to 56,0 dB(A)
- 56,3 dB(A) rounded to 56,5 dB(A)
- 56,7 dB(A) rounded to 56,5 dB(A)
- 56,8 dB(A) rounded to 57,0 dB(A)

4.4.1.2 FAT-Airborne noise measurements**4.4.1.2.1 Acoustic environment**

The test field shall meet the following conditions:

- The influence of sound reflection and absorbing on walls and the ceiling of the test room has to be corrected e.g. acc. to DIN45635.
- Any influence of air flows on the measurements has to be avoided (a wind screen or wind ball to be used).
- The influence of disturbing sound which may be created in environs of the test field shall be investigated. Such noise shall be at least 8 dB lower than the expected sound of equipment investigated. If this is not possible, relevant corrections are to be introduced. Such background noise measurements are to be conducted before and after each measurement set.

4.4.1.2.2 Measurement area

Depending on the location and type of machinery the measurement method and standard to be applied have to be agreed with **BCS**.

4.4.1.2.3 Measuring conditions

- For main noise sources, like propulsion machinery, gears, generator sets, every unit of a series has to be tested.
- Other series of equipment may be tested with the first unit only.
- The equivalent continuous A-weighted sound pressure level in dB(A) shall be measured. The sound level instrumentation shall be set to "fast" response. The measuring time shall be at least 15 seconds.
- The microphone shall not be situated close to input and output openings of mechanical ventilation and exhaust gas openings.
- For better judgment of noise behaviour third-octave band spectra (16 Hz- 10 kHz) and a narrow band analysis shall be conducted.
- If the overall sound pressure level is fluctuating by more than ± 5 dB(A), the minimum and maximum overall sound pressure levels are to be measured and reported additionally.

4.4.1.2.4 Evaluation of results

- The measured values are to be rounded as de-scribed in 4.4.1.1.4.
- The power averaged sound pressure level is to be calculated based on all measurement positions taken at the enveloping surface of each unit.

4.4.2 Structure-borne noise measurements**4.4.2.1 General requirements**

4.4.2.1.1 For evaluation of the influence of the radiated-noise, structure-borne noise measurements shall be conducted at relevant noise sources (e.g. foundations, shell plating etc.). For such measurements requirements shall be observed for establishing comparable results as follows:

4.4.2.1.2 It is recommended to use measuring equipment which is suitable to evaluate the results immediately after the measurements. Thus it will be possible to decide quickly if repeated or additional measurements become necessary.

4.4.2.1.3 The measurement equipment has to be calibrated before and after each measurement set.

4.4.2.2 FAT-Structure-borne noise measurements**4.4.2.2.1 Test bed foundation**

Machinery and equipment shall be mounted on their original vibration isolators which will be used on board. The foundation of the test field should be provided as follows (starting with the best solution):

- same foundation as on board
- A resiliently mounted concrete foundation (vertical tuning frequency < 5 Hz) may be used as test bed floor.
- standard test field foundation consisting of a double T-girder (e.g. IPB1 of DIN 1025) with stiffening brackets below the fixing points of the vibration isolator of unit

However, the driving-point admittance shall be measured for each test bed foundation at least in the frequency range of approx. 50 to 2000 Hz. Single measurement points are to be chosen below each vibration isolator of the unit. The power average driving-point admittance shall be calculated. All results shall be reported.

4.4.2.2.2 Measuring positions

See 4.4.2.3.2.

4.4.2.2.3 Measuring conditions

See 4.4.2.3.3

4.4.2.2.4 Evaluation of results

- Comparison of the results with the predefined, frequency depending limit curves for the test bed

- Remarks on special influences and boundary conditions, etc.
- The result of the FAT shall be presented in a measurement report.

4.4.2.3 SAT-Structure-borne noise measurements

4.4.2.3.1 Situation on board

- For each measurement the influence of disturbing noise which may be created in the environs of the machinery to be investigated shall be considered. Such noise should be at least 8 dB lower than the expected structure-borne noise limit of the unit to be investigated.
- Background noise measurements are to be conducted before and after each measurement set. If necessary, the structure-borne noise levels measured are to be corrected.
- For measurements to be taken at the shell plating, the wind speed shall be less than or equal 4 Bft and sea state less than or equal 3.
- Rudder movements are to be limited to maximum rudder angles of $\pm 5^\circ$.
- Water depth is to be correlated with the ship's speed.

4.4.2.3.2 Measuring positions

- Structure-borne noise measurements shall be conducted at each relevant noise source. The list of noise sources is to be prepared by the shipyard and shall be submitted and discussed with **BCS**.
- Based on the list of noise sources the number and location of measurement points shall be agreed on with **BCS** in detail for relevant unit. The agreement should be during an early state of the design.

4.4.2.3.3 Measurement conditions

- To be agreed in detail with the shipyard

4.4.2.3.4 Evaluation of results

- The power averaged structure-borne noise level shall be calculated based on all measurement positions taken below the vibration isolators at the ship foundation of each relevant unit. Minimum and maximum levels shall be plotted too.
- The power averaged structure-borne noise levels are to be compared with the noise limit curves and/or for further evaluations.
- All results shall be presented in a measurement report.

4.4.3 Radiated-noise measurements

4.4.3.1 General requirements

4.4.3.1.1 The frequency depending limit curves for the permissible radiated-noise of the ship may be defined normally by the Naval Authority. The limit curves are to be defined as third-octave band level, re 1 μ Pa. These levels are related to a certain depth of the water and to a certain distance from the ship.

4.4.3.1.2 Radiated-noise measurements are to be conducted as follows:

- The ship is to be kept stationary over the noise measurement range for shallow and/or deep water condition. Each relevant noise source shall be operated according the switch list, defined for each measurement task. The radiated-noise shall be measured as third-octave band levels, re 1 μ Pa.
- The ship is moving over the measurement noise range. The procedure shall be repeated for different ship speeds as agreed on in the building specification. The machinery are to be operating according the switch list, defined for each measurement task. The radiated-noise shall be measured as third-octave band levels, re 1 μ Pa.

4.4.3.1.3 For operating conditions of the ship which are to be expected as critical or when the Naval Authority

adhere strictly to keep defined radiated-noise limits the measurements shall be repeated at least three times.

4.4.3.1.4 Narrow band analysis

Measurements and evaluation of results have to be agreed on case by case. The scope of work shall be executed by institutions specialized in this field.

4.4.3.1.5 Evaluation of the results

The work shall be executed by institutions specialized in this field. The measurement results shall be compared with specified acoustic signatures. All results shall be presented in measurement reports.

4.4.3.2 Measurement noise range

The Naval Authority has to decide which measurement noise range shall be chosen for the vessel e.g. shallow and/or deep water condition. All radiated-noise measurements shall be conducted by institutions specialized in this field.

4.5 Noise Survey Report

4.5.1 All Noise Survey Reports are based on the Noise Survey Program prior approved by **BCS**.

4.5.2 The Noise Survey Report contains all final results of each noise measurement and discussion of the results. In case acoustic signatures are not fulfilled causes therefore and proposals for improvement have to be given.

4.5.3 The Noise Survey Report shall be presented in form of a document and shall contain the following sections for each operation mode investigated:

- Designation of tests
- Environmental conditions
- Operational conditions
- Measurement instrumentation
- Summary of the main measurement results

- Discussion of results
- Proposals for improvement, if necessary
- Conclusion of the acceptance tests if all tests are finished
- Attachments e.g. all measured data in detail, reading sheets, drawings, etc.

C. Vibration

1. General

In the following the influence of vibration on the habitability of the crew as well as the effect of vibration on hull structures, electronic devices, main/ auxiliary machinery and equipment is given.

2. Applicable standards

2.1 For the definition of basic principles of vibration calculation, assessment and measurement procedures it is referred to well proven standards. Unless a particular edition of a standard is defined, the latest edition of the respective standard shall be applied.

If these Rules contain procedures deviating from the relevant standards, these Rules have priority.

2.2 International standards

- ISO 6954: 2000 (E), "Mechanical vibration - Guidelines for the measurement, reporting and evaluation of vibration with regard to habitability on passenger and merchant ships"
- ISO 2631-1: 1997 (E), "Mechanical vibration and shock - Evaluation of human exposure to whole-body vibration - Part 1: General requirements"
- ISO 2631-2: 1989 (E), "Mechanical vibration and shock - Evaluation of human exposure to whole-body vibration - Part 2: Continuous and shock induced vibration in buildings (1-80 Hz)"

- ISO 20283-2, 2008, "Measurement of vibration on ships-Part 2: Structural Vibration"
- ISO 8041: 1990 (E), "Human response to vibration - Measuring instrumentation"

3. Habitability

3.1 If the Naval Authority does not request specific maximum vibration levels, the levels of Table 16.3 are recommended.

The limit values in Table 16.3 refer to ISO 6954, edition 2000. Consequently the limit values are defined as overall frequency weighted root mean square (rms) values in the frequency range 1 to 80 Hz.

3.2 Requirements are to be defined mainly for the following operating conditions:

- Maximum continuous ahead speed v_0 , see Section 1, B.7.1
- Economic, continuous ahead cruising speed v_M , see Section 1, B.7.3

3.3. Vibration verification by measurements

3.3.1 General

The measurements and the evaluation of their results shall be carried out only by experienced personnel **(1)**.

3.3.2 Conditions for measurements

The operating conditions of the naval ship, like operating time, revolutions per minute and rated driving power P of the propulsion machinery, ship's speed, etc. shall be verified during the measurement procedure. During the measurements the following conditions have to be observed:

- The loading case shall be typical for normal operation

(1) *BCS may be entrusted with carrying out measurements and evaluations within the marine advisory services.*

- Shallow water effects have to be excluded by calculating the Depth Froude Number for each individual ship and by choosing the test area accordingly
- A sea state 3 and significant wave height of approx. 1,25 m shall not be exceeded
- 4 Bft wind speed shall not be exceeded
- The course of the ship shall be as straight as possible, minimum rudder movement is imperative and the rudder angles shall not exceed ± 2 degrees

3.3.3 Measurement instrumentation

The instrumentation has to be specially agreed by and shall fulfil the following conditions:

- The instrumentation shall comply with the requirements of ISO 8041
- A calculation of the weighted rms value in terms of vibration velocity according to ISO 6954 must be possible
- Provision shall be made for the storage of all spectra and a limited number of time records
- For non-magnetic floors three-legged plates with a minimum weight of 1 500 g shall be available for carrying the measuring sensors
- The equipment shall be calibrated at periodic intervals of not more than two years, calibration sheets shall be presented before the measurements

3.3.4 Measurement procedure

3.3.4.1 If no other agreements are made, the following principles shall be applied:

- The standards ISO 4867 and 4868 have to be observed

- Measurement positions for assessing longitudinal and transverse vibration shall be chosen in a way that the measurement results reflect the global level
- Measurement positions for assessing vertical vibration shall include at least all accommodation, recreation and working areas
- The velocity spectrum achieved by a Fast Fourier Transformation (FFT) of the measured time series shall generally be made available i.e. during sea trials; the spectrum shall be stored

3.3.4.2 To ensure comparability of the spectra, the following parameters shall be applied for data acquisition and signal processing:

- Measuring time per point: ≥ 1 min
- Sampling rate: ≥ 300 l/s
- Spectral frequency range: 1-80 Hz
- Minimum spectral resolution: 0,2 Hz
- FFT window function: flat top
(if not available: Hanning window)
- FFT averaging mode: linear averaging
(stable mean)

3.3.4.3 The results shall be presented as weighted rms values in terms of vibration velocity.

4. Vibration induced fatigue of hull structures

4.1 Design principles

4.1.1 Hull structures are normally subjected to vibration stresses. Design, construction and installation shall in every case take account of these stresses. Fatigue considerations are to be included.

4.1.2 Particular attention is to be given to the ship's lines including the stern post, shaft brackets as well as to the minimisation of possible cavitation. With regard to bow shape consideration is to be given to limiting excitation from the seaway.

4.2 Excessive vibration

4.2.1 Excessive vibration may damage the ship's structure. Therefore, it has to be ensured that local structures are not vibrating in resonance with a main excitation frequency created by the propeller or other machinery. This can be realised by designing structures with sufficiently high natural frequencies.

4.2.2 The calculated natural frequencies of the structures under investigation have to be put into relation to the excitation frequencies in a resonance diagram.

Note

The frequencies of the excitation sources shall be beyond a range of +/- 15 % from the critical natural frequencies, if detailed analysis models are used a safety margin of +/- 10 % may be used. Figure 16.1 shows an example. If the excitation forces are created by the propulsion devices/propellers, resonance must be avoided especially for the rpm corresponding to:

- standard cruising speed v_M
- maximum speed v_0

4.3 Severity of effects of strong vibration

Severity of the effects of strong vibration depends on multiple influence factors: material, detail design, welding process, environmental conditions, etc. As a rough guideline for assessment of vibration severity with regard to structural damage the diagram Fig. 16.1 can be used. The diagram is valid for steel structures and refers to peak values of maximum single frequency components of the measured response spectrum. For aluminium structures the values shall be multiplied by a factor of 0,4.




Figure 16.1 Resonance diagram

5. Vibration of mast mounted electronic equipment

5.1 Vibration may affect the operation of electronic instruments installed on masts. Vibration is mainly excited by the seaway and the propulsion system. In any case the electronic equipment shall withstand vibration loads without limitation of its intended purpose.

5.2 For any electronic equipment which is relevant for safety, functionality or fulfilment of the ship's tactical purpose safety towards vibration must be demonstrated by suitable procedures. That may be:

- Type tests using shaking devices simulating vibration loads on navy ships
- Proof of successful applications in comparable conditions
- Theoretical investigations

Requirements regarding proof of safety towards vibration by type testing are defined in Chapter 105 - Electrical Installations, Section 1, Table 1.3.

5.3 Masts and mast modules shall be constructed in such a way that no resonance of basic vibration modes with relevant excitation frequencies is

present. This should be verified during design stage by theoretical investigations (2).

5.4 The mast itself as well as its support should be designed as stiff as possible. Support on longitudinal and transverse walls is advantageous. Sufficient shear stiffness shall be provided for the mast construction.

5.5 The overall rms vibration-level in the frequency range 1 to 80 Hz should not exceed 15 mm/s at mast locations intended for installation of electronic equipment in any direction.

6. Vibration of main/auxiliary machinery and equipment

6.1 Where a part of machinery or equipment generates vibrations when in operation, the intensity of the vibration shall not exceed defined limits. The purpose is to protect the vibration generators, the connected assemblies, peripheral equipment and hull components from additional, excessive vibration stresses liable to cause premature failures or malfunctions.

Special attention has to be paid to the design of the foundation. If a resilient support is provided, it has to be ensured that the foundation is of sufficient stiffness in order to achieve the desired isolation effects.

6.2 Vibration may damage machinery or equipment. Vibration can be self-excited, as in the case of propulsion machinery, or is caused by excitation originating from the foundation. In any case machinery and equipment shall withstand vibration loads without loss of intended function.

6.3 Vibration limit values regarding reciprocating main engines and auxiliary machinery are defined in Chapter 104 - Propulsion Plants, Section 1, D.2.

(2) BCS may be entrusted with carrying out investigations within the marine advisory services.

Table 16.3 Proposal for maximum vibration levels
(overall frequency weighted rms value in frequency range 1-80 Hz)

Space category / Space	Limits of vibration level [mm/s]	
	At cruising speed v_M	At maximum continuous speed v_0
Working spaces		
Unmanned main and auxiliary machinery spaces	5,0	6,0
Mechanical workshops	4,0	5,0
Electronic workshops	3,0	4,5
Galley range	3,5	4,5
Control stations		
Navigation bridge and chartroom	3,0	3,5
Manned combat information centre (CIC) Manned flight control centre (FCC)	2,5	3,5
Manned machinery control centre (MCC) Manned damage control centre (DCC)	3,0	3,5
Accommodation		
Officer cabins	2,5	4,0
Petty officer and crew cabins	3,0	4,5
Messes	3,0	4,5
Offices	3,0	4,5
Hospitals	2,5	3,5
Outdoor spaces		
Working areas	4,0	5,0
Recreation areas	3,5	4,5




Figure 16.2 Guideline for vibration severity with regard to structural damage

6.4 For any machinery/equipment which is relevant for safety, functionality or fulfilment of the ship's tactical purpose, safety towards vibration shall be demonstrated by suitable procedures, that may be

- Type tests using shaking devices simulating vibration loads on navy ships
- Proof of successful applications in comparable conditions
- Theoretical investigations

6.5 Type tests as well as theoretical calculations must provide the natural frequencies of the main basic vibration modes of the respective machinery/equipment. Elements connecting the device and its foundation must be considered during tests as well as calculations. The lowest natural frequency obtained is defined as the critical machinery/equipment natural frequency: f_{Device} .

6.6 In order to reduce vibration transferred from ship structure into machinery/equipment or vice versa resilient mounting should be provided.

6.7 If any machinery/equipment is mounted resiliently sufficient space for motions caused by seaway, heeling or shock loads must be provided. If two machinery/equipment items are placed next to each other opposite-phase motion must be considered too.

6.8 The design frequency of resilient supports must be compared to the main excitation frequencies which occur on the individual ship. The properties of the mounting elements must be chosen in such a way that the safety margin between those frequencies is sufficient, i.e.

$$f_{\text{Design}} < 0,80 \cdot f_{\text{Blade Propeller}} \quad [\text{Hz}]$$

f_{Design} = natural frequency of resilient mounting which is determined from element type, number of elements and shore hardness [Hz]

$f_{\text{Blade Propeller}}$ = propeller blade passage frequency at rpm corresponding cruising speed v_M [Hz]

6.9 In order to avoid vibration excitation from propeller shafting and hull girder vibration caused by seaway excitation the following criteria should be observed:

$$f_{\text{Design}} > 1,20 \cdot f_{\text{Propeller Shaft}} \quad [\text{Hz}]$$

$$f_{\text{Design}} > 1,20 \cdot f_{\text{Natural Hull Vibration}} \quad [\text{Hz}]$$

$f_{\text{Propeller Shaft}}$ = propeller shaft rotation speed at rpm corresponding maximum speed v_0 [Hz]

$f_{\text{Natural Hull Vibration}}$ = natural frequency of basic hull girder vibration mode [Hz]

6.10 To avoid coupling of elastic vibration of the machinery/equipment or parts of it with rigid body vibration on its resilient support the following criteria should be observed:

$$f_{\text{Device}} > 3,0 \cdot f_{\text{Design}} \quad [\text{Hz}]$$

6.11 For any resiliently mounted machinery/equipment which is relevant for safety, functionality or fulfilment of the ship's tactical purpose it must be demonstrated by suitable procedures that the desired design frequency f_{Design} is obtained. The natural frequency can be determined alternatively by:

- Type tests using shaking devices
- Measurements at comparable installations
- Theoretical investigations (2)

6.12 Mounting elements shall be standardised and of inflammable type. It must be ensured that the elastic properties are maintained during their whole life time. Wire-rope elements are preferred if no structure borne noise isolation is required.

D. Shock Strength

1. Shock loads from underwater explosion

1.1 General

For the calculation of the resulting shock load for a given system the knowledge of the shock response spectrum (SRS) is necessary. The SRS of a shock load represents the maximum response of a linear single degree of freedom (SDOF) vibration system (or a combination of multiple SDOFs) with defined damping characteristics as a function of frequency.

A data base of SRS has been gathered from experience with naval ships. Further SRS can be deduced from direct simulations.

For an actual project the SRS represent normally classified data.

1.2 Shock loads on the hull

If the pressure waves of an underwater explosion in some distance of the naval ship reach the ship, mechanical vibration will be induced. The character of this oscillation primarily depends on the size of the explosion as well as on the stiffness and the mass distribution of the ship.

The oscillation of the directly excited shell of the ship is characterised by high frequency vibration with extremely large acceleration amplitudes in combination with a rigid body motion of the ship. The vibration is non-linear because of:

- Appearance of cavitation, which depends on the relative velocity between water and shell which may increase the original load
- Large deformations, which may be beyond the elastic limit

The vibration expand to the adjacent parts of the hull structure. The frequency decreases with increasing distance from the shell. Often the structural elements are oscillating with their basic natural frequencies in combination with high acceleration amplitudes. This is

especially the case if structural elements, like decks and bulkheads are connected to the shell with a low bending rigidity. If the construction of the bulkheads, decks and walls is very stiff the high frequency vibration of the shell reaches also the inner structure of the ship, like superstructures, deckhouses and masts.

From a characteristic "shock response spectrum" (SRS) it can be concluded that, in the lower frequency range the maximum relative deflection, in the medium range the maximum vibration velocity and in the high frequency range the maximum absolute acceleration is decisive for the effect of a shock load.

1.3 Shock loads on resiliently mounted equipment

1.3.1 Character of the shock load

If no other characteristic is defined by the Naval Authority the analysis of shock behaviour of the equipment and its resilient mounting can be based on the following two forms of acceleration distribution at the initial stage of a shock. If possible the use of the sinusoidal distribution should be preferred against the triangular form.

1.3.2 Triangular distribution

This distribution is shown in Figure 16.3 and defined by:




Figure 16.3 Triangular distribution

- The size of the acceleration peak of the first (positive) triangle shall be 0,6 times of the maximum acceleration a_{SRS} gained from the shock response spectrum (SRS)

- The integration of the area of the first triangle shall create a velocity v_2 which amounts to 75 % of the maximum velocity v_{SRS} according to the SRS
- The area of the second triangle shall be equal to the area of the first triangle to achieve a final velocity of the foundation equal to zero
- The double integration of the acceleration distribution shall give a displacement of the foundation which is slightly bigger (abt. 5 %) than the maximum relative displacement gained from SRS
- It is recommendable to choose $t_2 = 0,4 \cdot t_3$ and $t_4 - t_3 = 0,6 (t_5 - t_3)$

$$t_3 = 2 \cdot \frac{v_2}{a_2}$$

$$t_5 - t_3 = \frac{6 \cdot d_{SRS} \cdot 1,05 - 1,6 \cdot a_2 \cdot t_3^2}{1,6 \cdot a_2 \cdot t_3}$$

$$a_4 = -a_2 \cdot \frac{t_3}{t_5 - t_3}$$

$$t_4 = t_3 + 0,6 \cdot (t_5 - t_3)$$

d_{SRS} = relative displacement of foundation according to SRS [m]

1.3.2.1 Double sinusoidal distribution

This distribution is shown in Figure 16.4 and defined by:

- The amplitude of the positive half wave shall reach approximately half the value of the maximum acceleration a_{SRS} according to SRS
- The area under each half wave shall be about two thirds of the maximum "pseudo-velocity" v_{SRS} according to SRS
- The double integration of this acceleration distribution shall give a relative displacement of the foundation which is equivalent to the maximum relative displacement d_{SRS} gained from SRS




Fig. 16.4 Double sinusoidal distribution of acceleration on equipment foundations caused by shock loads

These relations can be defined by the following formula:

$$a_2 = 0,5 \cdot a_{SRS}$$

$$a_4 = -\pi \cdot \frac{v_1}{2 \cdot t_2}$$

$$t_1 = \pi \cdot \frac{v_1}{2 \cdot a_2}$$

$$t_2 = 2 \cdot \frac{d_{SRS}}{v_1 - t_1}$$

$$v_1 = v_2 = 2 \cdot \frac{v_{SRS}}{3}$$

1.3.3 Shock loads on equipment in direct contact with water

Components of the equipment located in an area of the ship, which is flooded or which are in direct contact with water have to withstand two types of shock loads:

- Structural shock
- So called water shock, created by the direct contact with the shock wave

Shock resistance can be confirmed by calculation or blasting tests. Tests are preferable compared to calculations.

Equipment exposed to water shock are the rudders (including the shaft), stabilizing fin units, various retractable units, sensors and valves at the ship's shell, etc.

As a basis for the calculation of the shock influence the following pressure distribution of the shock wave can be assumed, see Fig. 16.4:

$$p = \frac{p_{\max}}{100} e^{-\frac{t}{\Theta}}$$

$p_{\max}$ = Maximum pressure [kN/m²]

Θ = Time constant

$p_{\max, \Theta}$ = Depending on mass of explosive and distance R from explosion location to the relevant element of the ship

For elements of the ship immediately below the water surface a reduction of the pressure load ("Surface Cut-Off") can be assumed, see Figure 16.5.




Figure 16.5 Pressure distribution of an underwater explosion

The absolute amount of the pressure depends on the mass of the explosive and the distance to the relevant component of the ship. Because of the reflection on the component the pressure will be doubled. The effect of the different shock wave parameters for the explosive TNT is demonstrated in the diagram Figure 16.6. These relations are determined by the following formulae:

$$p_{\max} = 524 \left(\frac{W^{0,33}}{R} \right)^{1,13} \quad [\text{bar}]$$

$$\Theta = 0,084 \cdot W^{0,33} \left(\frac{W^{0,33}}{R} \right)^{-0,23} \quad [\text{milliseconds}]$$

$$I = 0,057 \cdot W^{0,33} \left(\frac{W^{0,33}}{R} \right)^{0,89} \quad [\text{bar} \cdot \text{s}]$$

$$E = 0,844 \cdot W^{0,33} \left(\frac{W^{0,33}}{R} \right)^{2,04} \quad [\text{m} \cdot \text{bar}]$$

R = Distance between explosive and relevant element of the ship [m]

W = Mass of TNT explosive [kg]

$p_{\max}$ = Maximum pressure [bar]

Θ = Time constant [milliseconds]

I = Impulse per area [bar · s]

E = Energy flow density [m · bar]

On the back side of the component the shock wave passing by builds up a counter pressure area, which supports the component (e.g. the rudder). As the shock wave travels with sonic velocity (1450 -1510 m/s) this supporting effect happens with time retardation and depends on the diffraction of the wave at the component.

Note:

Fig. 16.6 shows an example for a mass of TNT of 1 000 kg and a distance to the ship of 10 m. The results are:

$$\Theta = 0,84 \text{ milliseconds}$$

$$p_{\max} = 524 \text{ bar}$$

$$I = 0,57 \text{ bar} \cdot \text{s}$$

$$E = 8,44 \text{ m} \cdot \text{bar}$$

1.3.4 Installation areas

The effect of a shock load to the equipment of the naval

ship depends also on the installation area within the ship's steel structure. Three installation areas can be characterised:

- Installation area I:

Installation basis is formed by the shell and its supporting structure, tank deck of double bottom, bulkheads up to strength deck, see Figure 16.7
- Installation area II:

Installation basis is formed by decks (tween decks and strength deck), walls below strength deck, bulkheads above strength deck, see Figure 16.8
- Installation area III:

Installation basis is formed by decks above strength deck, side and intermediate walls above strength deck, see Figure 16.9

2. Proof of shock safety

2.1 The methods to proof the permissible shock safety of different equipment components have to be agreed with the Naval Authority. Shock tests already executed on order of the Naval Authority may be incorporated in the shock proof procedure.

Only in exceptional, justified cases proof of shock safety will not be needed.

2.2 The following methods for confirming shock safety may be applied:

- Blasting test for the equipment to be checked installed on a shock barge or a blast platform
- Full scale tests at a vibration test stand or a shock test stand
- Partial or model tests, if full scale test facilities of required size are not available

- Calculations, if test facilities of required size are not available

The proof of shock safety is mandatory for the permission to install equipment aboard. If also other tests have to be provided, e.g. tests for electromagnetic compatibility, these tests have to be executed successfully before shock behaviour is investigated as the final test.

2.3 Definition of shock safety classes

In accordance to the importance and type of the combat mission of the naval ship the equipment has to be tested under different conditions. Depending on the relevant test results the equipment will be classed in three "shock safety classes". It is recommended to list all equipment for these classes and to integrate this list to the building specification:

- Shock safety class A:

For all parts of the equipment which are necessary for the ship's safety and fulfilment of its combat task. Full function during and after shock load without reduction of performance. No loosening of parts which could endanger crew or other equipment of class A.
- Shock safety class B:

All other parts of the equipment which are not essential for safety and fulfilment of combat task. No loosening of parts which could endanger crew or equipment of class A under full shock load. Nevertheless, they have to withstand reduced shock loads during and after shock.
- Shock class C:

Equipment with no shock resistance requirements, the mounting of the complete devices has to be done in a way that they do not endanger ship and crew under full shock load.




Figure 16.6 Shock wave parameters of an underwater explosion of TNT




Figure 16.7 Installation area I




Figure 16.8 Installation area II




Figure 16.9 Installation area III

3. Shock strength of the hull

To improve shock strength of the hull structures of a naval ship already at the beginning of the design process the following recommendations should be observed:

- As far as possible higher strength hull structural steel and tough steel materials should be used
- Hard materials, like cast iron should not be used
- Longitudinal stiffening system should be preferred
- Reinforcing of longitudinal girders
- Symmetrical sections of profiles and girders should be preferred
- Arrange for continuous hull girder scantlings along the ship's length as far as possible
- Avoiding of stress concentrations in the shell like usual at scallops, penetration of seawater pipes, etc. by careful detail design
- Mountings should not be fixed directly to the shell
- Dimensioning of tanks in double bottom in a way that they can be safely used with partial fillings

The basic rule to improve the shock strength is to avoid structural discontinuities, stress concentrations or even stress peaks.

4. Protection of the equipment

4.1 General requirements

The design principle is to protect the equipment from high shock loads, but to reduce structure-borne sound and avoid vibration at the same time.

Shock isolation of equipment can be achieved by storing temporarily the incoming, high frequent energy and to transfer this energy afterwards with low frequency and small amplitudes to the equipment/device. This requires sufficient margin for spring movement in direction of all three main axes. This requirement has to be observed in parallel with other considerations:

- Vibration, especially these excited by the propellers (the main excitation frequency is equal to the number of shaft revolutions per second x number of propeller blades).

Such vibration characterised by frequencies below 50 Hz may be in a state of resonance with the resilient mountings, which requires high damping characteristics for them or if possible avoidance of resonance.
- Structure-borne noise, produced by various devices aboard and transmitted into the water thus increasing the ship's signature. To reduce these effects low natural frequencies and restricted damping of the mounting elements are necessary.
- Non-mechanical influences, like the ambient conditions temperature, humidity, oil mist, etc. Temperature may influence the spring characteristics, the other influences mentioned may reduce the life time of the mounting elements.

4.2 Solutions for navy type equipment

The contradictory requirements, summarized in 4.1, demand for a compromise in the design/choice of the elastic elements for the equipment to be protected. Often an acceptable solution can be achieved by using mountings with progressive spring characteristic or by using a combination of shock reducing elements with stoppers to achieve a practical compromise between the requirements regarding shock safety and noise insulation.

The natural frequencies of lowly tuned shock mountings often coincide with the range of the strongest ship vibration. The increase of the amplitude in case of resonance can be limited by using elements with high damping. Unfortunately, high damping is disadvantageous with regard to the insulation of structure borne noise. Therefore, a compromise has to be found in each individual case and to be verified by measurements.

As a first guideline a correlation between the type of equipment/machinery to be protected and the type of the mounting element is defined in Table 16.4.

Table 16.4 Suitability of shock isolating mountings for different types of machinery and equipment

Equipment type → Type of mounting ↓	Electronic devices, control elements	Electrical aggregates	Control consoles, pointer instruments	Electrical switch boards	Hydraulic units	Diesel generator sets	Gas turbines	Internal combustion engines
Rubber strips	- (1)	0 (1)	-	0	+ (1)	+	+	+
Elastomer/rubber spring elements	-	0	-	0	+	0	0	0
Compound shock absorber	+	+	+	0	+	+	0	0
Elastic metal/spring elements	+	+	+	0	+	-	+	-
Damping optimized isolators	+	+	+	+	+	0	0	0
(1) suitability classification: +: very suitable 0: suitable -: less suitable								

SECTION 17**FATIGUE STRENGTH**

	Page
A. General	17-2
1. Definitions	
2. Scope	
3. Quality requirements (fabrication tolerances)	
B. Fatigue Strength Analysis for Free Plate Edges and for Welded Joints Using Detail Classification	17-5
1. Definition of nominal stress and detail classification for welded joints	
2. Permissible stress range for standard stress range spectra or calculation of the cumulative damage ratio	
3. Design S-N curves	
C. Fatigue Strength Analysis for Welded Joints Based on Local Stresses	17-11

Preamble

The proof of sufficient fatigue strength, i.e. the strength against crack initiation under dynamic loads during operation, is useful for judging and reducing the probability of crack initiation of structural members during the design stage.

Due to the randomness of the load process, the spreading of material properties and fabrication factors and to effects of ageing, crack initiation cannot be completely excluded during later operation. Therefore among other things periodical surveys are necessary.


A. General**1. Definitions**

Figure 17.1 Definition of time-dependent stresses

$\Delta\sigma$ = Applied stress range ($\sigma_{\max} - \sigma_{\min}$) [N/mm²], see also Figure 17.1

$\sigma_{\max}$ = Maximum upper stress of a stress cycle [N/mm²]

$\sigma_{\min}$ = Maximum lower stress of a stress cycle [N/mm²]

$\Delta\sigma_{\max}$ = Applied peak stress range within a stress range spectrum [N/mm²]

σ_m = Mean stress ($\sigma_{\max}/2 + \sigma_{\min}/2$) [N/mm²]

$\Delta\sigma_p$ = Permissible stress range [N/mm²]

$\Delta\tau$ = Corresponding range for shear stress [N/mm²]

n = Number of applied stress cycles

N = Number of endured stress cycles according to S-N curve (= endured stress cycles under constant amplitude loading)

$\Delta\sigma_R$ = Fatigue strength reference value of S-N curve at $2 \cdot 10^6$ cycles of stress range [N/mm²] (= FAT class number according to Table 17.3)

f_m = Correction factor for material effect

f_R = Correction factor for mean stress effect

f_w = Correction factor for weld shape effect

f_i = Correction factor for importance of structural element

f_s = Additional correction factor for structural stress analysis

f_t = Correction factor for plate thickness effect

f_n = Factor considering stress spectrum and number of cycles for calculation of permissible stress range

$\Delta\sigma_{RC}$ = Corrected fatigue strength reference value of S-N curve at $2 \cdot 10^6$ stress cycles [N/mm²]

D = Cumulative damage ratio

2. Scope

2.1 A fatigue strength analysis is to be performed for structures which are predominantly subjected to cyclic loads. Due consideration shall thereby be given to auxiliary structures such as e.g. fasteners. The notched details i.e. the welded joints as well as notches at free plate edges are to be considered individually.

The fatigue strength assessment is to be carried out either on the basis of a permissible peak stress range for standard stress spectra, see B.2.1 or on the basis of a cumulative damage ratio, see B.2.2.

2.2 No fatigue strength analysis is required if the peak stress range due to dynamic loads in the seaway (stress spectrum A according to 2.4) and/or due to changing draught or loading conditions, respectively, fulfils the following conditions:

- Peak stress range only due to seaway-induced dynamic loads:

$$\Delta\sigma_{\max} \leq 2,5 \Delta\sigma_R$$

- Sum of the peak stress ranges due to seaway-induced dynamic loads and due to changes of draught or loading condition, respectively:

$$\Delta\sigma_{\max} \leq 4,0 \Delta\sigma_R$$

Note:

For welded steel structures of FAT class 80 or higher a fatigue strength analysis is required only in case of extraordinary high dynamic stresses.

2.3 The rules are applicable to constructions made of normal and higher strength hull structural steels according to Section 3, B. as well as of aluminium alloys according to Section 3, D. Other materials such as cast steel can be treated in an analogous manner by using appropriate design S-N curves.


Low cycle fatigue problems in connection with extensive cyclic yielding have to be specially considered. When applying the following rules, the calculated nominal stress range should not exceed 1,5 times the minimum yield stress. In special cases the fatigue strength analysis may be performed by considering the local elasto-plastic stresses.

2.4 The stress ranges $\Delta\sigma$ which are to be expected during the service life of the ship or structural component, respectively, may be described by a stress range spectrum (long-term distribution of stress range). Figure 17.2 shows three standard stress range spectra A, B and C, which differ from each other in regard to the distribution of stress range $\Delta\sigma$ as a function of the number of load cycles.

In general the fatigue analysis has to be performed for a number of cycles $n_{\max} = 5 \cdot 10^7$ for seaway induced stresses with the stress range spectrum A. This considers a lifetime of 25 years with 230 days per year at sea in the North Atlantic.

Under extreme seaway conditions stress ranges exceeding $\Delta\sigma_{\max}$ occur. These stress ranges, which load cycles are to be generally assumed with $n < 10^4$, can be neglected regarding the fatigue life, when the stress ranges $\Delta\sigma_{\max}$ derived from loads according to Table 17.1 are assigned to the spectrum A.

Modified numbers of cyclic loads, load profiles and life time have to be agreed with the Naval Authority. For direct calculated stress range spectra (long term distributions of stress range), based on the requirements of Section 6, C.2.1.6, the factor f_0 in Table 17.1 has to be agreed with **BCS**.



- A : straight-line spectrum (typical stress range spectrum of seaway-induced stress ranges),
- B : parabolic spectrum (approximated normal distribution of stress range $\Delta\sigma$ acc. to DIN 15018),
- C : rectangular spectrum (constant stress range within the whole spectrum; typical spectrum of engine-or propeller-excited stress ranges).

Fig. 17.2 Standard stress range spectra A, B and C

The maximum and minimum stresses result from the maximum and minimum relevant seaway-induced load effects. The different load-effects for the calculation of $\Delta\sigma_{\max}$ are, in general, to be superimposed conservatively.

Table 17.1 shows examples for the individual loads which have to be considered in normal cases.

Other significant fluctuating stresses, e.g. in longitudinal due to deflections of supporting transverses as well as additional stresses due to the application of nonsymmetrical sections, have to be considered, see Section 4, D.5

For ships of unconventional hull shape and for ships for which a special mission profile applies, a stress range spectrum deviating from spectrum A may be applied which may be evaluated by the spectral method.

2.5 Additional stress cycles resulting from changing mean stresses, e.g. due to changing loading conditions or draught, need generally not be considered as long as the seaway-induced stress ranges are determined for the loading condition being most critical with respect to fatigue strength and the maximum change in mean stress is less than the maximum seaway-induced stress range.

Larger changes in mean stress are to be included in the stress range spectrum by conservative super positioning of the largest stress ranges, e.g. in accordance with the "rain flow counting method".

2.6 The fatigue strength analysis is, depending on the detail considered, based on one of the following types of stress:

- For notches of free plate edges the notch stress σ_k , determined for linear-elastic material behaviour, is relevant, which can normally be calculated from a nominal stress σ_n and a theoretical stress concentration factor K_t . Values for K_t are given in Section 4, Figure 4.12 and Figure 4.13 for different types of cut-outs. The fatigue strength is determined by the FAT class (or $\Delta\sigma_R$) according to Table 17.3, type E2 and E3.
- For welded joints the fatigue strength analysis is normally based on the nominal stress σ_n at the structural detail considered and on an appropriate detail classification as given in Table 17.3, which defines the FAT class (or $\Delta\sigma_R$).

- For those welded joints, for which the detail classification is not possible or additional stresses occur, which are not or not adequately considered by the detail classification, the fatigue strength analysis may be performed on the basis of the structural stress σ_s in accordance with C.

3. Quality requirements (fabrication tolerances)

3.1 The detail classification of the different welded joints as given in Table 17.3 is based on the assumption that the fabrication of the structural detail or welded joint, respectively, corresponds in regard to external defects at least to quality group B according to DIN EN ISO 5817 and in regard to internal defects at least to quality group C. Further information about the tolerances can also be found in **BCS** Rules, Part Chapter 3, Welding, Sections 7,8,9,10,11..

A production standard which considers the special manufacturing requirements of naval ships has to be agreed case by case with **BCS**, see Section 1, E.

3.2 Relevant information has to be included in the manufacturing document for fabrication. If it is not possible to comply with the tolerances given in the standards, this has to be accounted for, when designing the structural details or welded joints, respectively. In special cases an improved manufacture as stated in 3.1 may be required, e.g. stricter tolerances or improved weld shapes, see also B.3.2.4.

3.3 The following stress increase factors k_m for considering significant influence of axial and angular misalignment are already included in the fatigue strength reference values $\Delta\sigma_R$ (Table 17.3):

- $k_m = 1,15$ butt welds (corresponding type A1, A2, A11)
- $= 1,30$ butt welds (corresponding type A3–A10)
- $= 1,45$ cruciform joints (corresponding type D1– D5)
- $= 1,25$ fillet welds on one plate surface (corresponding type C7, C8)

Other additional stresses need to be considered separately

B. Fatigue Strength Analysis for Free Plate Edges and for Welded Joints Using Detail Classification

1. Definition of nominal stress and detail classification for welded joints

1.1 Corresponding to their notch effect, welded joints are normally classified into detail categories considering particulars in geometry and fabrication, including subsequent quality control, and definition of nominal stress. Table 17.3 shows the detail classification based on recommendations of the International Institute of Welding (IIW) giving the FAT class number (or $\Delta\sigma_R$) for structures made of steel or aluminium alloys (Al).

In Table 17.4 $\Delta\sigma_R$ -values for steel are given for some intersections of longitudinal frames of different shape and webs, which can be used for the assessment of the longitudinal stresses.

It has to be noted that some influence parameters cannot be considered by the detail classification and that a large scatter of fatigue strength has therefore to be reckoned with.

1.2 Details which are not contained in Table 17.3 may be classified either on the basis of local stresses in accordance with C. or, else, by reference to published experimental work or by carrying out special fatigue tests, assuming a sufficiently high confidence level, see 3.1 and taking into account the correction factors as given in C.4.

1.3 Regarding the definition of nominal stress, the arrows in Table 17.3 indicate the location and direction of the stress for which the stress range is to be calculated. The potential crack location is also shown in Table 17.3. Depending on this crack location, the nominal stress range has to be determined by using either the cross sectional area of the parent metal or the weld throat thickness, respectively. Bending stresses in plate and shell structures have to be incorporated into the nominal stress, taking the nominal bending stress acting at the location of crack initiation.

Note:

The factor K_s for the stress increase at transverse butt welds between plates of different thickness, see type 5 in Table 17.3 can be estimated in a first approximation as follows:

$$K_s = \frac{t_2}{t_1}$$

t_1 = smaller plate thickness,

t_2 = larger plate thickness,

Additional stress concentrations which are not characteristic of the FAT class itself, e.g. due to cut-outs in the neighbourhood of the detail, have also to be incorporated into the nominal stress.

1.4 In the case of combined normal and shear stress the relevant stress range is to be taken as the range of the principal stress at the potential crack location which acts approximately perpendicular (within $\pm 45^\circ$) to the crack front as shown in Table 17.3, as long as it is larger than the individual stress components.

1.5 Where pure shear stresses are acting, the largest principal stress $\sigma_1 = \tau$ may be used in combination with the relevant FAT class.

2. Permissible stress range for standard stress range spectra or calculation of the cumulative damage ratio

2.1 For standard stress range spectra according to Figure 17.2, the permissible peak stress range can be calculated as follows:

$$\Delta\sigma_P = f_n \cdot \Delta\sigma_{Rc}$$

$\Delta\sigma_{Rc}$ = FAT class or fatigue strength reference value, respectively, corrected according to 3.2

f_n = factor as given in Table 17.2

The peak stress range of the spectrum must not exceed the permissible value, i.e.

$$\Delta\sigma_{\max} \leq \Delta\sigma_P$$

Table 17.1 Maximum and minimum value for variable cyclic loads

Load		Maximum load (1)		Minimum load (1)
Vertical and horizontal hull girder bending (2) (Section 6, C.2.)		$M_{SW} + f_Q \cdot \sqrt{M_{WV}^2 + M_{WH}^2}$		$M_{SW} - f_Q \cdot \sqrt{M_{WV}^2 + M_{WH}^2}$
Loads on weather decks, weather exposed walls and at ship's shell (Section 5, B.) (5)		$p_s = p_{Sstat} + p_{Sdyn}$		$p_s = p_{Sstat} - p_{Sdyn} \geq 0$
Liquid pressure in completely filled tanks (Section 5, F.)	Upright (5)	$p_{T1} = p_{T1stat} + p_{T1dyn}$		$p_{T1} = p_{T1stat} - p_{T1dyn}$
	Heeled	$p_{T1} = \gamma_{fstat} \cdot p_{T1stat} + \gamma_{fdyn} \cdot \rho \cdot g (0,3b+7) \sin\phi$		$p_{T1} = \gamma_{fstat} \cdot p_{T1stat} + \gamma_{fdyn} \cdot \rho \cdot g (0,3b-7) \sin\phi$ but $\geq 100 \Delta p$
Loads due to general stowage (Section 5, E.) (3)		$p_L = p_{Lstat} (1+ a_z)$ $= p_{Lstat} \cdot a_x$ $= p_{Lstat} \cdot a_y$	vertical longitudinal transverse	$p_L = p_{Lstat} (1- a_z)$ $= - p_{Lstat} \cdot a_x$ $= - p_{Lstat} \cdot a_y$
Loads due to rudder forces (4) (Section 12, B.)		rudder force C_R rudder torque Q_R		- C_R - Q_R
(1) Maximum and minimum loads are to be determined that the largest applied stress range $\Delta\sigma$ as per Figure 17.1 is obtained. The loads are to be superposed with the load combination factor ψ according to Section 4, A.2. if applicable. For minor loads of the combination ψ may be reduced to 0,75. (2) For probability factor f_Q see Section 6, D.4.1.2, for load collectives determined by direct calculation (see Section 6, C.2.1.6) the probability factor f_Q has to be agreed with BCS . (3) Probability factor $f_Q = 1,0$ is to be taken for determination of a_0 and further calculation of a_x and a_y . (4) In general the largest load is to be taken in connection with the load spectrum B according to Figure 17.2 without considering further cyclic loads. (5) Assumption of conservative superpositioning of sea and tank pressures within $0,2 < x/L \leq 0,7$: Where appropriate, prof is to be furnished for T_{min} .				

Table 17.2 Factor f_n for the determination of the permissible stress range for standard stress range spectra

Stress range spectrum	Welded joints					Plates edges														
	(m ₀ = 3)					Type E1 (m ₀ = 5)					Type E2,E2a (m ₀ = 4)					Type E3 (m ₀ = 3,5)				
	n _{max} =					n _{max} =					n _{max} =					n _{max} =				
	10 ³	10 ⁵	5 · 10 ⁷	10 ⁸	3.10 ⁸	10 ³	10 ⁵	5 · 10 ⁷	10 ⁸	3.10 ⁸	10 ³	10 ⁵	5 · 10 ⁷	10 ⁸	3.10 ⁸	10 ³	10 ⁵	5 · 10 ⁷	10 ⁸	3.10 ⁸
A		(17,2)	3,53	3,02	2,39		(8,1)	3,63	3,32	2,89		(8,63) (9,2) (3)	3,66	3,28	2,76		(10,3) (12,2) (2)	3,65	3,19	2,62
B		(9,2)	1,67	1,43	1,15	(9,5)	5,0	1,95	1,78	1,55	(10,3) (11,2) (3)	5,50 5,90 (3)	1,86	1,65	1,40		6,6 7,5 (2)	1,78	1,55	1,28
C	(12,6)	2,71	0,424 0,543 (1)	0,369 0,526 (1)	0,296 0,501 (1)	(4,57)	1,82	0,606 0,673 (1)	0,561 0,653 (1)	0,500 0,621 (1)	(4,57)	1,82	0,532 0,621 (1)	0,482 0,602 (1)	0,411 0,573 (1)	(4,57)	1,82	0,483 0,587 (1)	0,430 0,569 (1)	0,358 0,541 (1)
For definition of type E1 to type E3 see Table 17.3. For definition of m₀ see 3.1.2. The values given in parentheses may be applied for interpolation. For interpolation between any pair of values (n_{max1} ; f_{n1}) and (n_{max2} ; f_{n2}), the following formula may be applied in the case of stress spectrum A or B: $\log f_n = \log f_{n1} + \log \left(\frac{n_{max}}{n_{max1}} \right) \frac{\log(f_{n2} / f_{n1})}{\log(n_{max2} / n_{max1})}$ For the stress spectrum C intermediate values may be calculated according to 3.1.2 by taking N = n_{max} and f_n = Δσ /Δσ_R.																				
(1) f_n for non-corrosive environment, see also 3.1.4. (2) Δσ_R= 100 [N/mm²] (3) Δσ_R= 140 [N/mm²]																				

2.2 If the fatigue strength analysis is based on the calculation of the cumulative damage ratio, the stress range spectrum expected during the envisaged service life is to be established, see A.2.4 and the cumulative damage ratio D is to be calculated as follows:

$$D = \sum_{i=1}^I (n_i / N_i)$$

I = Total number of blocks of the stress range spectrum for summation (normally $I \geq 20$)

n_i = Number of stress cycles in block i

N_i = Number of endured stress cycles determined from the corrected design S-N curve (see 3.) taking $\Delta\sigma = \Delta\sigma_i$

$\Delta\sigma_i$ = Stress range of block i

To achieve an acceptable high fatigue life, the cumulative damage ratio should not exceed $D = 1$.

If the expected stress range spectrum can be superimposed by two or more standard stress spectra according to A.2.4, the partial damage ratios D_i due to the individual stress range spectra can be derived from Table 17.2. In this case a linear relationship between number of load cycles and cumulative damage ratio may be assumed. The numbers of load cycles given in Table 17.2 apply for a cumulative damage ratio of $D = 1$.

3. Design S-N curves

3.1 Description of the design S-N curves

3.1.1 The design S-N curves for the calculation of the cumulative damage ratio according to 2.2 are shown in Figure 17.3 for welded joints at steel and in Figure 17.4 for notches at plate edges of steel plates. For aluminium alloys (Al) corresponding S-N curves apply with reduced reference values of S-N curve (FAT class) acc. to Table 17.3. The S-N curves represent the lower limit of the scatter band of 95 % of all test results available (corresponding to 97,5 % survival probability) considering further detrimental effects in large structures.

To account for different influence factors, the design S-N curves have to be corrected according to 3.2.

3.1.2 The S-N curves represent section-wise linear relationships between $\log(\Delta\sigma)$ and $\log(N)$:

$$\log(N) = 7,0 + m \cdot Q$$

$$Q = \log(\Delta\sigma_R / \Delta\sigma) - 0,69897/m_0$$

m = slope exponent of S-N curve, see 3.1.3 and 3.1.4

m_0 = slope exponent in the range $N \leq 1 \cdot 10^7$

= 3 for welded joints

= 3,5 ÷ 5 for free plate edges, see Figure 17.4

The S-N curve for FAT class 160 forms the upper limit also for the S-N curves of free edges of steel plates with detail categories 100 - 150 in the range of low stress cycles, see Figure 17.4.

The same applies accordingly to FAT class 32 to 40 of aluminium alloys with an upper limit of FAT 71, see type E1 in Table 17.3.

3.1.3 For structures subjected to variable stress ranges, the S-N curves shown by the solid lines in Figure 17.3 and Figure 17.4 have to be applied (S-N curves of type "M"), i.e.

$$m = m_0 \quad \text{for } N \leq 10^7 \quad (Q \leq 0)$$

$$m = 2 \cdot m_0 - 1 \quad \text{for } N > 10^7 \quad (Q > 0)$$

3.1.4 For stress ranges of constant magnitude (stress range spectrum C) in non-corrosive environment from $N = 1 \cdot 10^7$ the S-N curves of type "O" in Figure 17.3 and Figure 17.4 can be used, thus:

$$m = m_0 \quad \text{for } N \leq 10^7 \quad (Q \leq 0)$$

$$m = 22 \quad \text{for } N > 10^7 \quad (Q > 0)$$

$$f_m = 1,0$$

For free edges at steel plates the effect of the material's yield point is accounted for as follows:

$$f_m = 1 + \frac{R_{eH} - 235}{1200}$$

For aluminium alloys, $f_m = 1$ generally applies.

3.2.3 Effect of mean stress (f_R)

The correction factor is calculated as follows:

- in the range of tensile pulsating stresses, i.e.

$$\sigma_m \geq \frac{\Delta\sigma_{max}}{2}$$

$$f_R = 1,0$$

- in the range of alternating stresses, i.e.

$$-\frac{\Delta\sigma_{max}}{2} \leq \sigma_m \leq \frac{\Delta\sigma_{max}}{2}$$

$$f_R = 1 + c \left(1 - \frac{2 \cdot \sigma_m}{\Delta\sigma_{max}} \right)$$

- in the range of compressive pulsating stresses, i.e.

$$\sigma_m \leq -\frac{\Delta\sigma_{max}}{2}$$

$$f_R = 1 + 2 \cdot c$$

- $c = 0$ for welded joints subjected to constant stress cycles (stress range spectrum C)
- $= 0,15$ for welded joints subjected to variable stress cycles (corresponding to stress range spectrum A or B)
- $= 0,3$ for unwelded base material

3.2.4 Effect of weld shape (f_w)

In normal cases:

$$f_w = 1,0$$

A factor $f_w > 1,0$ applies for welds treated e.g. by grinding. By this surface defects such as slag inclusions, porosity and crack-like undercuts shall be removed and a smooth transition from the weld to the base material shall be achieved. Final grinding shall be performed transversely to the weld direction. The depth should be approx. 0,5 mm larger than that of visible undercuts.

For ground weld toes of fillet and K-butt welds machined by:

Disc grinder: $f_w = 1,15$

Burr grinder: $f_w = 1,30$

Premise for this is that root and internal failures can be excluded. Application of toe grinding to improve fatigue strength is limited to following details of Table 17.3:

- Butt welds of type A2, A3 and A5 if they are ground from both sides
- Non-load-carrying attachments of type C1, C2, C5 and C6 if they are completed with a full penetration weld
- Transverse stiffeners of type C7
- Doubling plates of type C9 if the weld throat thickness acc. to Section 19 was increased by 30 %
- Cruciform and T-joints of type D1 with full penetration welds

The corrected FAT class that can be reached by toe grinding is limited for all types of welded connections of steel to $f_w \cdot \Delta\sigma_R = 100 \text{ N/mm}^2$ and of aluminium to $f_w \cdot \Delta\sigma_R = 40 \text{ N/mm}^2$.

For butt welds ground flush the corresponding FAT class has to be chosen, e.g. type A1, A10 or A12 in Table 17.3.

For endings of stiffeners or brackets, e.g. type in Table 17.3, which have a full penetration weld and are completely ground flush to achieve a notch-free transition, the following factor applies:

$$f_w = 1,4$$

The assessment of a local post-weld treatment of the weld surface and the weld toe by other methods has to be agreed on in each case.

3.2.5 Influence of importance of structural element (f_i)

In general the following applies:

$$f_i = 1,0$$

For secondary structural elements failure of which may cause failure of larger structural areas, the correction factor f_i is to be taken as:

$$f_i = 0,9$$

For notches at plate edges in general the following correction factor is to be taken which takes into account the radius of rounding:

$$f_i = 0,9 + 5/r \leq 1,0$$

r = Notch radius [mm]; for elliptical roundings the mean value of the two main half axes may be taken

3.2.6 Plate thickness effect

In order to account for the plate thickness effect, application of the reduction factor f_t is required by **BCS** butt welds oriented transversely to the direction applied stress for plate thicknesses $t > 25$ mm.

$$f_t = (25/t)^n$$

n = 0,17 as welded

= 0,10 toe-ground

For all other weld connections consideration of the thickness effect may be required subject to agreement with **BCS**.

C. Fatigue Strength Analysis for Welded Joints Based on Local Stresses

1. Alternatively to the procedure described in the preceding, the fatigue strength analysis for welded joints may be performed on the basis of local stresses. For common plate and shell structures in ships the assessment based on the so-called structural (or hot-spot) stress σ_s is normally sufficient.

The structural stress is defined as the stress being extrapolated to the weld toe excluding the local stress concentration in the local vicinity of the weld, see Figure 17.5.




Figure 17.5 Structural stress

2. The structural stress can be determined by measurements or numerically, e.g. by the finite element method using shell or volumetric models, under the assumption of linear stress distribution over the plate thickness. Normally the stress is extrapolated linearly to the weld toe over two reference points which are located 0,5 and 1,5 x plate thickness away from the weld toe. In some cases the structural stress can be calculated from the nominal stress σ_n and a structural stress concentration factor K_s , which has been derived from parametric investigations using the methods mentioned. Parametric equations should be used with due consideration of their inherent limitations and accuracy.

3. For the fatigue strength analysis based on structural stress, the S-N curves shown in Figure 17.3

apply with the following reference values:

$$\Delta\sigma_R = 100 \quad (\text{resp. } 40 \text{ for Al})$$

for the butt welds types A1 –A 6 and for K-butt welds with fillet welded ends, e.g. type D1 in Table 17.3, and for fillet welds which carry no load or only part of the load of the attached plate, type C1- C9 in Table 17.3

$$\Delta\sigma_R = 90 \quad (\text{resp. } 36 \text{ for Al})$$

for fillet welds, which carry the total load of the attached plate, e.g. Type D2 in Table 17.3.

In special cases, where e.g. the structural stresses are obtained by non-linear extrapolation to the weld toe and where they contain a high bending portion, increased reference values of up to 15 % can be allowed.

4. The reference value $\Delta\sigma_{RC}$ of the corrected S-N curve is to be determined according to B.3.2, taking into account the following additional correction factor which describes influencing parameters not included in the calculation model such as e.g. mis-alignment:

$$f_s = \frac{1}{k_m' - \frac{\Delta\sigma_{s,b}}{\Delta\sigma_{s,max}}(k_m' - 1)}$$

$\Delta\sigma_{s,max}$ = Applied peak stress range within a stress range spectrum

$\Delta\sigma_{s,b}$ = Bending portion of $\Delta\sigma_{s,max}$

$$k_m' = k_m - 0,05$$

k_m = Stress increase factor due to mis-alignment under axial loading, at least k_m according to A.3.3.

The permissible stress range or cumulative damage ratio, respectively, has to be determined according to B.2.

5. In addition to the assessment of the structural stress at the weld toe, the fatigue strength with regard to root failure has to be considered by analogous application of the respective FAT class, e.g. Type D3 of Table 17.3.

In this case the relevant stress is the stress in the weld throat caused by the axial stress in the plate perpendicular to the weld. It is to be converted at a ratio of $t/2a$.

Table 17.3 Catalogue of details



A. Butt welds, transverse loaded				
Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	FAT class $\Delta\sigma_R$	
			Steel	Al
A1		Transverse butt weld ground flush to plate, 100% NDT (Non-Destructive Testing)	112	45
A2		Transverse butt weld made in the shop in flat position, max. weld reinforcement 1 mm + 0,1 x weld width, smooth transitions, NDT	90	36
A3		Transverse butt weld not satisfying conditions for joint type No.2, NDT	80	32
A4		Transverse butt weld on backing strip or three-plate connection with unloaded branch	71	25
		Butt weld, welded on ceramic backing, root crack	80	28
A5		Transverse butt welds between plates of different widths or thickness, NDT		
		as for joint type No.A2, slope 1: 5	90	32
		as for joint type No.A2, slope 1: 3	80	28
		as for joint type No.A2, slope 1: 2	71	25
		as for joint type No.A3, slope 1: 5	80	25
		as for joint type No.A3, slope 1: 3	71	22
		as for joint type No.A3, slope 1: 2	63	20
		For the third sketched case the slope results from the ratio of the difference in plate thicknesses to the breadth of the welded seam. Additional bending stress due to thickness change to be considered, see also B.1.3.		
A6		Transverse butt welds welded from one side without backing bar, full penetration	71	28
		root controlled by NDT not NDT For tubular profiles $\Delta\sigma_R$ may be lifted to the next higher FAT class.	36	12
A7		Partial penetration butt weld; the stress is to be related to the weld throat sectional area, weld overfill not to be taken into account	36	12

Table 17.3 Catalogue of details (continued)






Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	FAT class $\Delta\sigma_R$	
			Steel	Al
A8		Full penetration butt weld at crossing flanges Welded from both sides.	50	18
A9		Full penetration butt weld at crossing flanges Welded from both sides Cutting edges in the quality according to type E2 or E3 Connection length $w \geq 2b$ $\sigma_{\text{nominal}} = \frac{F}{b \cdot t}$	63	22
A10		Full penetration butt weld at crossing flanges Welded from both sides, NDT, weld ends ground, butt weld ground flush to surface Cutting edges in the quality according to type E2 or E3 with $\Delta\sigma_R = 125$ Connection length $w \geq 2b$ $\sigma_{\text{nominal}} = \frac{F}{b \cdot t}$	80	32
A11		Full penetration butt weld at crossing flanges welded from both sides made in shop at flat position, radius transition with $R \geq b$ Weld reinforcement $\leq 1 \text{ mm} + 0,1 \times \text{weld width}$, smooth transitions, NDT, weld ends ground Cutting edges in the quality according to type E2 or E3 with $\Delta\sigma_R = 125$	90	36
A12		Full penetration butt weld at crossing flanges, radius transition with $R \geq b$ Welded from both sides, no misalignment, 100 % NDT, weld ends ground, butt weld ground flush to surface Cutting edges broken or rounded according to type E2	100	40

Table 17.3 Catalogue of details (continued)







B. Longitudinal load-carrying weld				
Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	FAT class $\Delta\sigma_R$	
			Steel	Al
B1		Longitudinal butt welds		
		both sides ground flush parallel to load direction	125	50
		without start/stop positions, NDT	125	50
		with start/stop positions	90	36
B2		Continuous automatic longitudinal fully penetrated K-butt without stop/start positions (based on stress range in flange adjacent to weld)	125	50
B3		Continuous automatic longitudinal fillet weld penetrated K-butt weld without stop/start positions (based on stress range in flange adjacent to weld)	100	40
B4		Continuous manual longitudinal fillet or butt weld (based on stress range in flange adjacent to weld)	90	36
B5		Intermittent longitudinal fillet weld (based on stress range in flange at weld ends) In presence of shear τ in the web, the FAT class has to be reduced by the factor $(1 - \Delta\tau / \Delta\sigma)$, but not below 36 (steel) or 14 (Al).	80	32
B6		Longitudinal butt weld, fillet weld or intermittent fillet weld with cut outs (based on stress range in flange at weld ends)	71	28
		If cut out is higher than 40 % of web height In presence of shear τ in the web, the FAT class has to be reduced by the factor $(1 - \Delta\tau / \Delta\sigma)$, but not below 36 (steel) or 14 (Al). Note: For Ω -shaped scallops, an assessment based on local stresses is recommended.	63	25

Table 17.3 Catalogue of details (continued)





C. Non-load-carrying attachments				
Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	FAT class $\Delta\sigma_R$	
			Steel	Al
C1		Longitudinal gusset welded on beam flange, bulb or plate: $l \leq 50 \text{ mm}$ $50 \text{ mm} < l \leq 150 \text{ mm}$ $150 \text{ mm} < l \leq 300 \text{ mm}$ $l > 300 \text{ mm}$ For $t_2 \leq 0,5 t_1$, $\Delta\sigma_R$ may be increased by one class, but not over 80 (steel) or 28 (Al); not valid for bulb profiles. When welding close to edges of plates or profiles (distance less than 10 mm) and/or the structural element is subjected to bending, $\Delta\sigma_R$ is to be decreased by one class.	80 71 63 56	28 25 20 18
		Gusset with smooth transition (sniped end or radius) welded on beam flange, bulb or plate; $c \leq 2 t_2$, max. 25 mm $r \geq 0,5 h$ $r < 0,5 h$ or $\phi \leq 20^\circ$ $\phi > 20^\circ$ see joint type C1 For $t_2 \leq 0,5 t_1$, $\Delta\sigma_R$ may be increased by one class; not valid for bulb profiles. When welding close to the edges of plates or profiles (distance less than 10 mm), $\Delta\sigma_R$ is to be decreased by one class.	71 63	25 20+
C3		Fillet welded non-load-carrying lap joint welded to longitudinally stressed component. – flat bar – to bulb section – to angle section For $l > 150 \text{ mm}$, $\Delta\sigma_R$ has to be decreased by one class, while for $l \leq 50 \text{ mm}$, $\Delta\sigma_R$ may be increased by one class. If the component is subjected to bending, $\Delta\sigma_R$ has to be reduced by one class.	56 56 50	20 20 18
C4		Fillet welded lap joint with smooth transition (sniped end with $\phi \leq 20^\circ$ or radius) welded to longitudinally stressed component. – flat bar – to bulb section – to angle section $c \leq 2 t$, max. 25 mm	56 56 50	20 20 18
C5		Longitudinal flat side gusset welded on plate or beam flange edge $l \leq 50 \text{ mm}$ $50 \text{ mm} < l \leq 150 \text{ mm}$ $150 \text{ mm} < l \leq 300 \text{ mm}$ $l > 300 \text{ mm}$ For $t_2 \leq 0,7 t_1$, $\Delta\sigma_R$ may be increased by one class, but not over 56 (steel) or 20 (Al). If the plate or beam flange is subjected to in-plane bending, $\Delta\sigma_R$ has to be decreased by one class.	56 50 45 40	20 18 16 14

Table 17.3 Catalogue of details (continued)

C. Non-load-carrying attachments				
Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	FAT class $\Delta\sigma_R$	
			Steel	Al
C6		Longitudinal flat side gusset welded on plate edge or beam flange edge, with smooth transition (sniped end or radius); $c \leq 2 t_2$, max. 25 mm $r \geq 0,5 h$ $r < 0,5 h$ or $\phi \leq 20^\circ$ $\phi > 20^\circ$ see joint type C5 For $t_2 \leq 0,7 t_1$, $\Delta\sigma_R$ may be increased by one class.	50 45	18 16
C6a		Longitudinal flat side gusset welded on plate edge or beam flange edge, with smooth transition radius $r/h > 1/3$ or $r \geq 150$ mm $1/6 < r/h < 1/3$ $r/h < 1/6$ Smooth transition radius formed by grinding the full penetration weld area in order to achieve a notchfree transition area. Final grinding shall be performed parallel to stress direction.	90 71 50	36 28 22
C7		Transverse stiffener with fillet welds (applicable for short and long stiffeners)	80	28
C8		Non-load-carrying shear connector	80	28
C9		End of long doubling plate on beam, welded ends (based on stress range in flange at weld toe) $t_D \leq 0,8 t$ $0,8 t < t_D \leq 1,5 t$ $t_D > 1,5 t$ The following features increase $\Delta\sigma_R$ by one class accordingly: – reinforced ends according to Section 15, Fig. 15.4 – weld toe angle $\leq 30^\circ$ – length of doubling ≤ 300 mm For length of doubling ≤ 150 mm, $\Delta\sigma_R$ may be increased by two classes.	56 50 45	20 18 16

Table 17.3 Catalogue of details (continued)














D. Cruciform joints and T-joints				
Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	FAT class $\Delta\sigma_R$	
			Steel	Al
D1		Cruciform or tee-joint K-butt welds with full penetration or with defined incomplete root penetration according to Section 15, Fig. 15.9. cruciform joint tee-joint	71 80	25 28
D2		Cruciform or tee-joint with transverse fillet welds, toe failure (root failure particularly for throat thickness $a < 0,7 \cdot t$, see joint type D3) cruciform joint tee-joint	63 71	22 25
D3		Welded metal in transverse load-carrying fillet welds at cruciform or tee-joint, root failure (based on stress range in weld throat), see also joint type No. D2 $a \geq t/3$ $a < t/3$ <i>Note: Crack initiation at weld root</i>	36 40	12 14
D4		Full penetration weld at the connection between a hollow section (e.g. pillar) and a plate, for tubular section for rectangular hollow section For $t \leq 8$ mm, $\Delta\sigma_R$ has to be decreased by one class.	56 50	20 18
D5		Fillet weld at the connection between a hollow section (e.g. pillar) and a plate, for tubular section for rectangular hollow section The stress is to be related to the weld sectional area. For $t \leq 8$ mm, $\Delta\sigma_R$ has to be decreased by one class.	45 40	16 14
D6		Continuous butt or fillet weld connecting a pipe penetrating through a plate $d \leq 50$ mm $d > 50$ mm <i>Note</i> <i>For large diameters an assessment based on local stress is recommended.</i>	71 63	25 22









Table 17.3 Catalogue of details (continued)

E. Unwelded base material				
Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	FAT class $\Delta\sigma_R$	
			Steel	Al
E1		Rolled or extruded plates and sections as well as seamless pipes, no surface or rolling defects	160 ($m_0=5$)	71 ($m_0=5$)
E2a		Plate edge sheared or machine-cut by any thermal process with surface free of cracks and notches, cutting edges chamfered or rounded by means of smooth grinding, groove direction parallel to the loading direction. Stress increase due to geometry of cut-outs to be considered by means of direct numerical calculation of the appertaining maximum notch stress range.	150 ($m_0=4$)	-
E2		Plate edge sheared or machine-cut by any thermal process with surface free of cracks and notches, cutting edges broken or rounded. Stress increase due to geometry of cut-outs to be considered. (1)	140 ($m_0=4$)	40 ($m_0=4$)
E3		Plate edge not meeting the requirements of type E2, but free from cracks and severe notches. Machine cut or sheared edge: Manually thermally cut: Stress increase due to geometry of cut-outs to be considered (1) .	125 ($m_0=3,5$) 100 ($m_0=3,5$)	36 ($m_0=3,5$) 32 ($m_0=3,5$)
(1) Stress concentrations caused by an opening to be considered as follows: $\Delta\sigma_{max} = K_t \cdot \Delta\sigma_N$ K_t : Notch factor according to Section 3, J. $\Delta\sigma_N$: Nominal stress range related to net section Alternatively direct determination of $\Delta\sigma_{max}$ from FE-calculation, especially in case of hatch openings or multiple arrangement of openings.				
Note: Partly based on Recommendations on Fatigue of Welded Components, reproduced from IIW document XIII-2151-07 / XV-1254-07, by kind permission of the International Institute of Welding.				

Table 17.4 Various intersections

Joint configuration Loads Locations being at risk for cracks	Description of joint	FAT class $\Delta\sigma_R$ steel			
	None watertight intersection without heel stiffener For predominant longitudinal load only.	80	80	80	80
	Watertight intersection without heel stiffener (without cyclic load on the transverse member) see Section 9, B.4.1) For predominant longitudinal load only.	71	71	71	71
(2)	With heel stiffener direct connection $l \leq 150$	45	56	56	63
	connection $l > 150$	40	50	50	56
	overlapping connection $l \leq 150$	50	50	45	
	connection $l > 150$	45	45	40	
(2)	With heel stiffener and integrated bracket	45	56	56	63
	With heel stiffener and integrated bracket and with backing bracket direct connection	50	63	63	71
	overlapping connection	56	56	50	
	With heel stiffener but considering the load transferred to the stiffener (see Section 9, B.4.9) crack initiation at weld toe crack initiation at weld root Stress increase due to eccentricity and shape of cut out has to be observed.	80	71 40	71 40	71 40
(1) Additional stresses due to asymmetric sections have to be observed, see Section 3, L. (2) To be increased by one category, when longitudinal loads only					

Structure or equipment detail	Description of structure or equipment detail	Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	Detail category $\Delta\sigma_R$ Steel
	Unstiffened flange to web joint, to be assessed according to type D1, D2 or D3, depending on the type of joint. The stress in the web is calculated using the force F_g in the flange as follows : $\sigma = \frac{F_g}{r \cdot t}$ Furthermore, the stress in longitudinal weld direction has to be assessed according to type B2 ÷ B4. In case of additional shear or bending, also the highest principle stress may become relevant in the web, see B.1.4.	D1		Cruciform or tee-joint K-butt welds with full penetration or with defined incomplete root penetration according to Section 19, Fig.19.9. Cruciform joint Tee-joint	71 80
	Joint at stiffened knuckle of a flange, to be assessed according to type D1, D2 or D3, depending on the type of joint. The stress in the stiffener at the knuckle can normally be calculated as follows: $\sigma = \sigma_a \frac{t_f}{t_b} 2 \sin \alpha$	D2		Cruciform or tee-joint with transverse fillet welds, toe failure (root failure particularly for throat thickness $a < 0,7 \cdot t$, see joint type D3) Cruciform joint Tee-joint.	63 71
		D3		Welded metal in transverse load-carrying fillet welds at cruciform or tee-joint, root failure (based on stress range in weld throat), see also joint type No.D2	36
	Holder welded in way of an opening and arranged parallel to the edge of the opening. Not valid for hatch corner	C1		$l \leq 150 \text{ mm}$ In way of the rounded corner of an opening with the radius r a minimum distance x from the edge to be kept (hatched area): $x [\text{mm}] = 15 + 0,175 \cdot r [\text{mm}]$ $100 \text{ mm} \leq r \leq 400 \text{ mm}$ In case of an elliptical rounding the mean value to both semiaxes to be applied.	71

Structure or equipment detail	Description of structure or equipment detail	Type No.	Joint configuration showing mode of fatigue cracking and stress σ considered	Description of joint	FAT class $\Delta\sigma_R$ Steel
	Circular doubler plate with max. 150 mm. diameter.	C9		$t_D \leq 0,8 t$ $0,8 t < t_D \leq 1,5 t$ $t_D > 1,5 t$	71 63 56
	Drain plugs with full penetration butt weld $d \leq 150$ mm. Assessment corresponding to doubling plate.	C9		$t_D \leq 0,8 t$ $0,8 t < t_D \leq 1,5 t$ $t_D > 1,5 t$ For 150 mm $\Delta\sigma_R$ has to be decreased by one class	71 63 56
	Drain plugs with partial penetration butt weld and a defined root gap $d \leq 150$ mm For $v < 0,4.t$ or $v < 0,4.t_D$	C9		$0,2t < t_D \leq 0,8t$ $0,8t < t_D \leq 1,5t$ $1,5t < t_D \leq 2,0t$ For $d > 150$ mm $\Delta\sigma_R$ has to be decreased by one class	50 45 40
	For $v \geq 0,4.t$ and $v \geq 0,4.t_D$	A7		Partial penetration butt weld; the stress is to be related to the weld throat sectional area, weld overfill not to be taken into account	36
	The detail category is also valid for not fully circumferential welded holders For stiffeners loaded in bending $\Delta\sigma_R$ to be downgraded by one class.	C7		Transverse stiffener with fillet welds (applicable for short and long stiffeners)	80

SECTION 18

EQUIPMENT

	Page
A. General	18-2
B. Equipment Numeral.....	18-2
1. Monohull ships	
2. Multihull ships	
C. Anchors	18-3
1. Arrangement	
2. Anchor design	
3. High holding power anchors	
4. Very high holding power anchors	
5. Stern anchors	
6. Special stern anchors	
D. Chain Cables.....	18-4
E. Chain Locker.....	18-5
F. Mooring and Towing Equipment	18-6
1. Mooring Lines and Towing Lines	
2. Specifications of Mooring and Towing Ropes	
G. Shipboard Fittings and Supporting Hull Structures Associated With Mooring and Towing	18-6
1. Mooring	
2. Towing	
3. Towing and Mooring Arrangements Plan	
4. Corrosion Addition	
5. Surveys After Construction	

A. General

1. The equipment of anchors, chain cables, wires and ropes is to be determined from Table 18.1 in accordance with the equipment numeral EN.

Note:

Anchoring equipment required by this Section is intended of temporary mooring of a naval ship within a harbour or sheltered area when the ship is awaiting berth, tide, etc.

The equipment is, therefore, not designed to hold a naval ship off fully exposed coasts in rough weather or to stop a ship which is moving or drifting. In this condition the loads on the anchoring equipment increase to such a degree that its components may be damaged or lost owing to the high energy forces generated, particularly in very large naval ships.

Anchoring equipment required by this Section is designed to hold a naval ship in good holding ground in conditions such as to avoid dragging of the anchor. In poor holding ground the holding power of the anchors will be significantly reduced.

The equipment numeral formula for anchoring equipment required under this Section is based on an assumed current speed of 2,5 m/s, wind speed of 25 m/s and a scope of chain cable between 6 and 10, the scope being the ratio between length of chain paid out and water depth.

It is assumed that under normal circumstances a naval ship will use only one bow anchor and chain cable at a time.

2. Every naval ship is to be equipped with at least one anchor windlass. For bigger naval ships two anchor windlasses are recommended and shall be agreed with the naval authority.

For small craft with a length $L \leq 24$ m, some partial exemption from the Rules may be accepted especially if it concerns anchor operation; in particular, where proper and safe anchor operation is assured, hand operated machinery and/or absence of a hawse pipe may be accepted.

Windlasses and chain stoppers, if fitted, are to comply with Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 5.

For the substructures of windlasses and chain stoppers, see Section 14, B.4.

3. For naval ships operating not more than 50 nautical miles from a port of refuge and Class Notation **K50/20** assigned equipment may be determined as for one numeral range lower than required in accordance with equipment numeral EN.

4. Naval ships built under survey of **BCS** and which are to have the mark * stated in their Certificate and in the Register Book, must be equipped with anchors and chain cables complying with the **BCS** Rules, Part A, Chapter 2 – Materials, Section 10 – Equipment. For non-magnetizable materials the **BCS** Rules, Chapter 103 Materials for Naval Ships, Section 8 apply. Anchors and chain cables have to be tested on approved machines in the presence of a **BCS** Surveyor.

5. For naval ships having three or more propellers, a reduction of the weight of the bower anchors and the chain cables may be considered.

B. Equipment Numeral**1. Monohull ships**

For monohull naval ships the equipment numeral is to be calculated as follows:

$$EN = \Delta^{2/3} + 2(a \cdot B + \sum b_i \cdot h_i \cdot \sin \Theta_i) + 0,1 \cdot A$$

Δ = The moulded displacement [t] at the design waterline in sea water having a density of 1,025 t/m³

a = Vertical distance [m], from design waterline, amidships, to the upper deck at side

b_i = Actual breadth of deckhouses with a breadth greater $B/4$

h_i = Height [m] on the centreline of each tier of superstructures and deckhouses corresponding to b_i (deck sheer, if any, is to be ignored)
For the lowest tier "h" is to be measured at centreline from the upper deck or from a notional deck where there is local discontinuity in the upper deck.

Θ_i = Angle of inclination of each front bulkhead, as shown in Figure 18.1

A = Area [m^2], in profile view of the hull, super-structures and deck houses, having a breadth greater than $B/4$, above the design waterline within the length L and up to the height $a + \sum h_i$

Screens of bulwarks 1,5 m or more in height above the deck at side are to be regarded as parts of houses when determining h and A , e.g. the areas specially marked in Figure 18.1 are to be included in A .

2. Multihull ships

For multihull naval ships the equipment numeral has to be defined in analogous way, details are given in the **BCS Rules – Part C, Chapter 7, High Speed Craft**.

C. Anchors

1. Arrangement

The two bow anchors are to be connected to their chain cables and positioned on board ready for use. It is to be ensured that each anchor can be stowed in the hawse and hawse pipe in such a way that it remains firmly secured in seagoing conditions. Details have to be coordinated with the naval authority.

2. Anchor design

2.1 Anchors must be of approved design. The mass of the heads of patent (ordinary stockless) anchors, including pins and fittings, is not to be less than 60 per cent of the total mass of the anchor.

2.2 For stock anchors, the total mass of the anchor, including stock, shall comply with the values in Table 18.1. The mass of the stock shall be 20 per cent of this total mass.

2.3 The mass of each individual bow anchor may vary by up to 7 per cent above or below the required individual mass provided that the total mass of all the bow anchors is not less than the sum of the required individual masses.

3. High holding power anchors

3.1 Where special anchors are approved by **BCS** as "High Holding Power Anchors" (HHP), the anchor mass may be 75 per cent of the anchor mass as per Table 18.1

"High Holding Power Anchors" are anchors which are suitable for the naval ship's use at any time and which do not require prior adjustment or special placement on sea bed.

3.2 For approval as a "High Holding Power Anchor", satisfactory tests are to be made on various types of bottom and the anchor is to have a holding power at least twice that of a patent anchor ("Admiralty Standard Stockless") of the same mass. The tests have to be approved by **BCS**.

3.3 Dimensioning of the chain cable and of the windlass is to be based on the undiminished anchor mass according to Table 18.1.

4. Very high holding power anchors

Where special anchors are approved by **BCS** as "Very High Holding Power Anchors" (VHHP), the anchor mass may be not less than 2/3 of the mass required for the HHP anchor it replaces.

5. Stern anchors

5.1 Where stern anchors are fitted as stream anchors, such equipment is to comply in all respects with the rules for anchor equipment. The mass of each stern anchor shall be at least 35 per cent of that of the bow anchors. The diameter of chain cables and the chain length is to be determined from Table 18.1 in accordance with anchor mass. Where a stern anchor windlass is fitted, the requirements of Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 5 are to be observed.

5.2 Where a steel wire rope is to be used for the stern anchor instead of a chain cable the following has to be observed:




Figure 18.1 Profile view of hull, superstructure and deckhouses relevant for the equipment numeral

5.2.1 The steel wire rope must at least be as long as the required chain cable. The strength of the steel wire rope must at least be of the value for the required chain of grade K 1.

5.2.2 Between anchor and steel wire rope a shot of 12,5 m in length or of the distance between stowed anchor and windlass must be provided. The smaller length has to be taken.

5.2.3 A cable winch must be provided according to the requirements for windlasses in Chapter 107 – Ship Operation Installations and Auxiliary Systems, Section 5

6. Special stern anchors

Special stern anchors of considerable size may be used to tow back a landing ship, which is touching the beach with its forward bottom, to deeper water after the troops are embarked or landed.

At least for medium sized and large landing ships it is recommended to provide two anchors in a symmetric arrangement, to be able to tow the ship back more or less along its longitudinal axis.

The size of anchors and the arrangement of towing winches in relation to ship displacement, draught/ water depth assumed, landing procedure, etc., has to be defined according to the specification of the Naval Authority.

D. Chain Cables

1. Chain cable diameters given in Table 18.1 apply to chain cables made of chain cable materials specified in the requirements of the **BCS** Rules, Part A Chapter 2 Materials, Section 11 – Equipment for following grades:

- Grade K 1 (ordinary quality)
- Grade K 2 (special quality)
- Grade K 3 (extra special quality)

For HHP anchors at least chain cables of grade K 2, for VHHP anchors chain cables of grade K 3 shall be provided.

Grade K 2 and K 3 chain cables must be purchased from and post production quenched and tempered by recognized manufacturers only.

2. Non-magnetizable austenitic steel as defined in Section 3 may be used for anchors and chain cables, see also the **BCS** Rules Chapter 103 -Special Materials for Naval Ships, Sections 8 and 9.

3. For ships with $EN \leq 150$ chain cables without stud links may be used as special equipment. The correlation to the values of Table 18.1 has to be approved by **BCS**. The equivalence in strength is to be based on proof load (not on breaking load).

4. The total length of chain given in Table 18.1 is to be divided in approximately equal parts between the two bower anchors.

5. For connection of the anchor with the chain-cable approved Kenter-type anchor shackles may be chosen in lieu of the common Dee-shackles. A forerunner with swivel is to be fitted between anchor and chain cable. In lieu of a forerunner with swivel an approved swivel shackle may be used. However, swivel shackles are not to be connected to anchor shank unless specially approved.

6. Upon request and agreement with **BCS** steel wire and synthetic wire ropes may be used as an alternative to the chain cables defined in Table 18.1 for naval ships of limited size.

7. The attachment of the inboard ends of chain cables to the ship's structure is to be provided with means suitable to permit, in case of emergency, an easy slipping of chain cables to sea operable from an accessible position outside the chain locker.

The inboard ends of the chain cables are to be secured to the structures by a fastening device able to withstand a force not less than 15 % but not more than 30 % of the rated breaking load of the chain cable

E. Chain Locker

1. The chain locker is to be of capacity and depth adequate to provide an easy direct lead of the cables through the chain pipes and self-stowing of the cables.

The minimum required stowage capacity without mud box for the two bow anchor chains is as follows:

$$S = 1,1 \cdot d^2 \cdot \frac{\ell}{100000} \quad [\text{m}^3]$$

d = Chain diameter [mm] according to Table 18.1

ℓ = Total length of stud link chain cable according to Table 18.1

The total stowage capacity is to be distributed on two chain lockers of equal size for the port and starboard chain cables. The shape of the base areas shall as far as possible be quadratic with a maximum edge length of 33 d. As an alternative, circular base areas may be selected, the diameter of which shall not exceed 30 -35 d.

Above the stowage of each chain locker in addition a free depth of

$$h = 1500 \quad [\text{mm}]$$

is to be provided, where practicable.

2. The chain locker boundaries and their access openings are to be watertight to prevent flooding of adjacent spaces, where essential installations or equipment are arranged, in order to not affect the proper operation of the ship after accidental flooding of the chain locker.

Spurling pipes and cable lockers are to be watertight up to the weather deck.

Spurling pipes through which anchor cables are led are to be provided with permanently attached closing appliances to minimize water ingress. Where means of access is provided, it is to be closed by a substantial cover and secured by closely spaced bolts.

3. Adequate drainage facilities of the chain locker are to be provided.

4. The scantlings of the structural elements of chain locker are determined with a design pressure according to p_{T3} of Section 5, F.3. and the distance h_3 of load centre from the top of chain locker pipe.

Where the chain locker boundaries are also tank boundaries their scantlings of stiffeners and plating are to be determined as for tanks in accordance with Section 10, B.

A corrosion addition of 2,0 mm has to be applied. The minimum thickness of plating is 5,0 mm.

F. Mooring and Towing Equipment1570 - 1770 N/mm²1770 - 1960 N/mm²**1. Mooring Lines and Towing Lines**

1.1 The mooring lines and towing line are given in Table 18.1 and are based in an equipment number EN calculated in compliance with B.1.

1.2 The towing lines given in col. 8 of Table 18.1 are intended as own towline of a ship to be towed by a tug or other ship.

1.3 Mooring lines and towing lines are given as guidance only.

2. Specifications of Mooring and Towing Ropes

2.1 Mooring lines and towlines may be of steel wire, natural fibre or synthetic fibre construction or of a mixture of steel wire and fibre. The lengths of individual mooring ropes may be reduced by up to 7% of the table length, provided that the total length of mooring ropes is not less than would have resulted had all ropes been of equal length.

2.2 Notwithstanding the strength requirements given in Table 18.1, no fibre rope is to be less than 20 mm diameter.

2.3 Wire ropes

2.3.1 Where wire ropes are used, they are to be of a flexible construction with not less than:

- 72 wires in 6 strands with 7 fibre cores for the loads up to 216 kN
- 144 wires in 6 strands with 7 fibre cores for the loads of 216 kN to 490 kN
- 216 wires in 6 strands with 1 fibre cores for loads exceeding 490 kN.

2.3.2 Tensile strength of wires for wire rope mooring lines is to be within the following ranges:

1420 - 1570 N/mm²

2.3.3 Wire ropes for use in association with mooring winches where the rope is to be stored on the drum may be constructed with an independent wire rope core instead of fibre core.

2.4 The required diameters of synthetic fibre ropes used in lieu of steel wire ropes may be taken from Table 18.2.

G. Shipboard Fittings and Supporting Hull Structures Associated With Mooring and Towing**1. Mooring****1.1 Strength**

The strength of shipboard fittings used for mooring operations and their supporting hull structures are to comply with the requirements of this subsection.

For fittings intended to be used for, both, mooring and towing, G.2 applies to towing.

1.2 Arrangement

Shipboard fittings for mooring are to be located on longitudinal, beams and/or girders, which are part of the deck construction so as to facilitate efficient distribution of the mooring load. Other arrangements may be accepted (for Panama chocks, etc.) provided the strength is confirmed adequate for the service.

1.3 Load considerations

1.3.1 Unless greater safe working load (SWL) of shipboard fittings is specified by the applicant, the design load applied to shipboard fittings and supporting hull structures is to be 1.25 times the breaking strength of the mooring line according to Table 18.1.

Note :

Side projected area including maximum stacks of deck cargoes is to be taken into account for assessment of lateral wind forces, arrangements of tug boats and selection of mooring lines.

1.3.2 The design load applied to supporting hull structures for winches, etc. is to be 1.25 times the

intended maximum brake holding load and, for capstans, 1.25 times the maximum hauling-in force.

1.3.3 The design load is to be applied through the mooring line according to the arrangement shown on the towing and mooring arrangement plans.

1.3.4 The method of application of the design load to the fittings and supporting hull structures is to be taken into account such that the total load need not be more than twice the design load specified in 1.3.1 above, i.e. no more than one turn of one line (see figure 18.2).




Figure 18.2 Application of design loads

1.3.5 When a specific SWL is applied for a shipboard fitting at the request of the applicant, by which the design load will be greater than the above minimum values, the strength of the fitting is to be designed using this specific design load.

1.4 Shipboard fittings

The selection of shipboard fittings is to be made by the shipyard in accordance with an industry standard (e.g. ISO 13795 Ships and marine technology – Ship's mooring and towing fittings – Welded steel bollards for sea-going vessels) accepted by BCS. When the shipboard fitting is not selected from an accepted industry standard, the design load used to assess its strength and its attachment to the ship is to be in accordance with 1.3.

1.5 Supporting hull structure

1.5.1 Arrangement

Arrangement of the reinforced members beneath shipboard fittings is to consider any variation of direction (horizontally and vertically) of the mooring forces (which is to be not less than the design load as per 1.3) acting through the arrangement of connection to the shipboard fittings.

1.5.2 Acting point of mooring force

The acting point of the mooring force on shipboard fittings is to be taken at the attachment point of a mooring line or at a change in its direction.

1.5.3 Allowable stresses

Allowable stresses under the design load conditions as specified in 1.3 are as follows:

1.5.3.1 For strength assessment by means of beam theory or grillage analysis:

- Normal stress : $1,0 R_{eH}$
- Shear stress : $0,6 R_{eH}$

No stress concentration factors being taken into account. Normal stress is the sum of bending stress and axial stress.

1.5.3.2 For strength assessment by means of finite element analysis:

For strength assessment by means of finite element analysis the mesh is to be fine enough to represent the geometry as realistically as possible. The aspect ratios of elements are not to exceed 3. Girders are to be modelled using shell or plane stress elements. Symmetric girder flanges may be modelled by beam or truss elements. The element height of girder webs must not exceed one-third of the web height. In way of small openings in girder webs the web thickness is to be reduced to a mean thickness over the web height as per BCS rules. Large openings are to be modelled. Stiffeners may be modelled by using shell, plane stress, or beam

elements. The mesh size of stiffeners is to be fine enough to obtain proper bending stress. If flat bars are modeled using shell or plane stress elements, dummy rod elements are to be modelled at the free edge of the flat bars and the stresses of the dummy elements are to be evaluated. Stresses are to be read from the centre of the individual element. For shell elements the stresses are to be evaluated at the mid plane of the element.

R_{eH} is the specified minimum yield stress of the material.

1.6 Safe working load (SWL)

1.6.1 The SWL is not to exceed 80% of the design load per 1.3.

1.6.2 The SWL of each shipboard fitting is to be marked (by weld bead or equivalent) on the deck fittings used for mooring.

1.6.3 The above requirements on SWL apply for a single post basis (no more than one turn of one cable).

1.6.4 The towing and mooring arrangements plan mentioned in 3. is to define the method of use of mooring lines.

1.7 Net thickness (t_{net})

Strength calculations for supporting hull structures of mooring equipment are to be based on net thicknesses.

$$t_{net} = t - t_k$$

t_k = Corrosion addition according to G.4.

2. Towing

2.1 Strength

The strength of shipboard fittings used for normal towing operations at bow, sides and stern and their supporting hull structures are to comply with the requirements of this subsection.

For fittings intended to be used for, both, mooring and towing, G.1 applies to mooring.

2.2 Shipboard fittings for towing are to be located on longitudinals, beams and/or girders, which are part of the deck construction so as to facilitate efficient distribution of the towing load. Other arrangements may be accepted (for Panama chocks, etc.) provided the strength is confirmed adequate for the intended service.

2.3 Load considerations

Unless greater safe working load (SWL) of shipboard fittings is specified by the applicant, the minimum design load to be used is the following value of 2.3.1 or 2.3.2, whichever is applicable:

2.3.1 For normal towing operations (e.g. harbour) 1.25 times the intended maximum towing load (e.g. static bollard pull) as indicated on the towing and mooring arrangements plan.

2.3.2 For other towing service (e.g. escort), the nominal breaking strength of the tow line according to Table 18.1 for the equipment numeral EN.

Note:

Side projected area including maximum stacks of deck cargoes is to be taken into account for assessment of lateral wind forces, arrangements of tug boats and selection of towing lines.

2.3.3 The design load is to be applied through the tow line according to the arrangement shown on the towing and mooring arrangements plan.

2.3.4 The method of application of the design load to the fittings and supporting hull structures is to be taken into account such that the total load need not be more than twice the design load (see figure 18.2).

2.3.5 When a specific SWL, is applied for a shipboard fitting at the request of the applicant, by which the design load will be greater than the above minimum values, the strength of the fitting is to be designed using this specific design load.

Table 18.1 Anchors, chain cables and ropes

Equipment numeral EN	2 stock-less bower anchors	Stud link chain cables					Chain cables	Recommended ropes			
	Mass per anchor	Bower anchors					Towline		Mooring ropes		
		Total length	Diameter (1)				Length	Breaking load	Number	Length	Breaking load
			d ₁	d ₂	d ₃	d ₄					
	[kg]	[m]	[mm]	[mm]	[mm]	[mm]	[m]	[kN]	-	[m]	[kN]
1	2	3	4	5	6	7	8	9	10	11	12
-50	120	165	12,5	12,5	12,5	12,5	180	100	3	80	35
50-70	180	220	14	12,5	12,5	14	180	100	3	80	35
70-90	240	220	16	14	14	16	180	100	3	100	40
90-110	300	247,5	17,5	16	16	18	180	100	3	110	40
110-130	360	247,5	19	17,5	17,5	18	180	100	3	110	45
130-150	420	275	20,5	17,5	17,5	20	180	100	3	120	50
150-175	480	275	22	19	19	22	180	100	3	120	55
175-205	570	302,5	24	20,5	20,5	24	180	110	3	120	60
205-240	660	302,5	26	22	20,5	26	180	130	4	120	65
240-280	780	330	28	24	22	28	180	150	4	120	70
280-320	900	357,5	30	26	24	30	180	175	4	140	80
320-360	1020	357,5	32	28	24	30	180	200	4	140	85
360-400	1140	385	34	30	26	32	180	225	4	140	95
400-450	1290	385	36	32	28	34	180	250	4	140	100
450-500	1440	412,5	38	34	30	36	190	275	4	140	110
500-550	1590	412,5	40	34	30	38	190	305	4	160	120
550-600	1740	440	42	36	32	40	190	340	4	160	130
600-660	1920	440	44	38	34	42	190	370	4	160	145
660-720	2100	440	46	40	36	44	190	405	4	160	160
720-780	2280	467,5	48	42	36	46	190	440	4	170	170
780-840	2460	467,5	50	44	38	48	190	480	4	170	185
840-910	2640	467,5	52	46	40	48	190	520	4	170	200
910-980	2850	495	54	48	42	50	200	560	4	170	215
980-1060	3060	495	56	50	44	-	200	600	4	180	230
1060-1140	3300	495	58	50	46	-	200	645	4	180	250
1140-1220	3540	522,5	60	52	46	-	200	690	4	180	270
1220-1300	3780	522,5	62	54	48	-	200	740	4	180	285
1300-1390	4050	522,5	64	56	50	-	200	785	4	180	305
1390-1480	4320	550	66	58	50	-	220	835	4	180	325
1480-1570	4590	550	68	60	52	-	220	890	5	190	325
1570-1670	4890	550	70	62	54	-	220	940	5	190	335
1670-1790	5250	577,5	73	64	56	-	220	1025	5	190	350
1790-1930	5610	577,5	76	66	58	-	220	1110	5	190	375
1930-2080	6000	577,5	78	68	60	-	240	1170	5	190	400
2080-2230	6450	605	81	70	62	-	240	1260	5	200	425
2230-2380	6900	605	84	73	64	-	240	1355	5	200	450
2380-2530	7350	605	87	76	66	-	260	1455	5	200	480
2530-2700	7800	632,5	90	78	68	-	260	1470	6	200	480
2700-2870	8300	632,5	92	81	70	-	260	1470	6	200	490
2870-3040	2870-30	632,5	95	84	73	-	280	1470	6	200	500
3040-3210	9300	660	97	84	76	-	280	1470	6	200	520
3210-3400	9900	660	100	87	78	-	280	1470	6	200	555
3400-3600	10500	660	102	90	78	-	300	1470	6	200	590
3600-3800	11100	687,5	105	92	81	-	300	1470	6	200	620
3800-4000	11700	687,5	107	95	84	-	300	1470	6	200	650
(1) d ₁ = Chain diameter Grade K 1 (Ordinary quality) d ₂ = Chain diameter Grade K 2 (Special quality) d ₃ = Chain diameter Grade K 3 (Extra special quality) d ₄ = Chain diameter for non-magnetizable austenitic steel (WN 1.3964)											

2.3.6 Ships complying with the requirements of this section will be eligible to be classed with the notation TA1, TA2 or TA3.

2.3.7 TA1, TA2 and TA3 notations will be assigned when an appraisal has been made of the towing arrangements and strength performance of the supporting structures in accordance with the Rules for considering the severe weather conditions, see Beaufort scale given in Table 18.3.

2.3.8 These three levels of towing arrangements in 2.3.7 recognise towing a ship of similar displacement at 6 knots in defined environmental conditions.

2.3.9 In case of alternative requirements to the breaking load of the towing hawser required by 2.3.14.1 are specified, and have been complied with, the ship will be entitled to the notation TA(NS). These alternative requirements are to be clearly defined and referenced in the Certificate of Class. The load specified in the alternative is to replace the BL value given by the expression in 2.3.14.1.

2.3.10 Where the towline complies with the strength requirements of Table 18.1 as applicable to merchant ships for the related equipment number, the ship will be entitled to the assignment of the TA(S) notation. The breaking load specified in Table 18.1 is to replace the BL value given by the expression in 2.3.14.1.

2.3.11 Towing operations are to be in accordance with the towing, mooring and arrangements plan or equivalent information which is required to be placed on board. See 2.3.12.

2.3.12 Information Required

2.3.12.1 Plans are to be of sufficient detail for plan approval purposes. Plans covering the following items are to be submitted for approval:

- Strong points, bollards and fairleads, see 2.3.13.7.
- Support structure and foundations of towing equipment.

2.3.12.2 The towing arrangement plan is to be submitted for information. It is to include the following in respect of each shipboard fitting:

- Location on the ship.
- Fitting type.
- Safe working load (SWL).
- Manner of applying towing line load, including limiting fleet angles.

The towing arrangement plan is to be provided on board the ship for the guidance of the Master.

2.3.13 Towing Arrangements

2.3.13.1 A towing arrangement is to be provided at both the fore and aft end of the ship.

2.3.13.2 The fixed towing equipment is to comprise a securing arrangement which is a strong point and may be in the form of a stopper bollard, bracket, deck clench or towing slip. A fairlead, rollers or other appropriate towline guides as necessary are to be included in the arrangement.

2.3.13.3 Loose towing equipment is to comprise a towing hawser and a towing pennant. The towing pennant may comprise a length of chafing chain. In the absence of a length of chafing chain suitable arrangements (e.g. a low friction sheath) are to be provided.

2.3.13.4 Fairleads and guides are to be designed so as to prevent excessive bending stress in the towing hawser, towing pennant or chafing chain, whichever is applicable. The bending ratio of the guides bearing surface to the diameter of the applicable towline element is not to be less than 7 to 1. For fibre rope towing hawsers and towing pennants the bending ratio is to comply with the rope manufacturer's specification.

2.3.13.5 The fairlead or guide is to have an opening large enough to allow the passage of the largest element of the loose towing equipment.

Table 18.2 Equivalent diameters of synthetic wire and fibre ropes

Steel wire ropes (1)	Steel wire ropes	Synthetic fibre ropes		
	Polyamide (2)	Polyamide	Polyester	Polypropylene
Diameter [mm]	Diameter [mm]	Diameter [mm]	Diameter [mm]	Diameter [mm]
12	30	30	30	30
13	30	32	32	32
14	32	36	36	36
16	32	40	40	40
18	36	44	44	44
20	40	48	48	48
22	44	48	48	52
24	48	52	52	56
26	56	60	60	64
28	60	64	64	72
32	68	72	72	80
36	72	80	80	88
40	72	88	88	96
(1) According to DIN 3068 or similar				
(2) Regular laid ropes of refined polyamide monofilaments and filament fibres				

Table 18.3 Design weather factors / Environmental conditions

Applicable notation	Wind speed coefficient, C_{mW}	Weather factor, K	Beaufort scale	Equivalent mean wind speed (knots)
TA1	0,0150	8	10+	48+
TA2	0,0129	7,2	9	41-47
TA3	0,0108	6,3	8	34-40

2.3.13.6 The fairlead or guide is to be fitted as close to the deck as practicable and in a position so that the tow will be approximately parallel to the deck when under tension between the strong point and the guide.

2.3.13.7 The selection of shipboard fittings is to be made by the shipyard in accordance with an acceptable National or International standard. If the shipboard fitting is not selected from an acceptable National or International standard then the design load used to assess its strength and its attachment to the ship is to be in accordance with the design load given in 2.3.14.3. The design is to be submitted for approval.

2.3.13.8 Deck fittings and strong points are to be located on longitudinals, beams and/or girders, which are part of the deck construction so as to facilitate efficient distribution of the towing load. Other equivalent arrangements will be considered, providing the strength is confirmed as adequate for the intended use.

2.3.13.9 To avoid chafing, the arrangement is to be designed so that no element of the loose towing equipment, when under tension, is to contact with the ship's hull at any point other than those specified as a securing arrangement, fairlead or guide. The final point of contact of the towline with the ship is to be positioned as close as practicable to the centre line so as to reduce the adverse effect on manoeuvrability.

2.3.13.10 The chafing arrangement is to extend a minimum of 3 m outboard of the fairlead or guide when in the deployed position and 2 m inboard.

2.3.13.11 The loose towing equipment is to be located as near as practicable to the strong point and is to be designed to be capable of being rigged and deployed in the absence of power. It is recommended that extra loose gear meeting the requirements of this Section be carried on board to provide for redundancy.

2.3.13.12 The minimum length of the towing hawser is to be as given in Table 18.1.

2.3.13.13 The SWL of each shipboard fitting is to be clearly marked, by weld bead or equivalent, on each of the fittings used for towing, see 2.3.14.10.

2.3.14 Strength Requirements for Towing Arrangements

2.3.14.1 The minimum Breaking Load (hereinafter referred to as BL), of the towing hawser carried on board the ship is assessed, in tonnes, is not to be less than that calculated below:

$$BL = (0,03\Delta^{2/3} + (C_{mw}A_t)) K$$

where

Δ = Displacement, in tonnes, to the deep draught waterline

C_{mw} = Wind speed coefficient, which is to be taken from Table 18.3 for the relevant notation

K = Weather factor, which is to be taken from Table 18.3 for the relevant notation

A_t = Transverse projected area, in m^2 , of the hull and of all superstructures, houses, masts, etc. above the design draught

2.3.14.2 The strength of other loose towing equipment e.g., links, shackles rings and chafing chain is to be determined on the basis of a design load equal to 1,25 times the BL of the towing hawser.

2.3.14.3 The strength of shipboard fittings and their supporting structure is to be determined on the basis of a design load equal to 1,25 times the BL of the towing hawser. The design load is to be applied through the towline according to the arrangement shown on the towing arrangement plan. The point of action of the force on the fitting is to be taken as the point of attachment of the mooring line or towline or at a change in its direction. The total design load applied to a fitting need not be more than twice the design load, see Figure 18.2.

2.3.14.4 The stress in all loose and fixed towing equipment constructed of steel, and its supporting structure, is not to exceed the specified minimum yield stress of the material in bending and 60 per cent of the specified minimum yield stress of the material in shear.

Special consideration will be given if the vessel and/or towing equipment is not constructed of steel.

2.3.14.5 The reinforced members (carling) beneath shipboard fittings are to be effectively arranged for any variation of direction (horizontally and vertically) of the towing forces (which is to be not less than the design load) acting through the arrangement of connection to the shipboard fittings. Other arrangements will be specially considered provided that the strength is confirmed as adequate for the service.

2.3.14.6 For the assessment of fairleads and their supporting structure, due consideration is to be given to lateral loads. The strength of the fairlead is to be sufficient for all angles of towing load up to 90° horizontally from the ship's centreline and 30° vertically from the horizontal plane.

2.3.14.7 For the assessment of a strong point and its supporting structure, the applied load is to be in the direction that the towing pennant or towing hawser will take up during normal deployment. It is also to be applied at the maximum height possible above the deck for that specific type of strong point.

2.3.14.8 The structural arrangements of strong points, bollards and fairleads are to be such that continuity will be ensured. Abrupt changes in section; sharp corners and other points of stress concentration are to be avoided.

2.3.14.9 Strong points are to be fitted in way of a transverse or longitudinal deck girder or beam to facilitate efficient distribution of the towing load.

2.3.14.10 The SWL of each towing arrangement component is to be no greater than 80 per cent of the design load applied.

2.4 Shipboard fittings

The selection of shipboard fittings is to be made by the shipyard in accordance with an industry standard (e.g. ISO 13795 Ships and marine technology – Ship's mooring and towing fittings – Welded steel bollards for sea-going vessels) accepted by **BCS** . When the

shipboard fitting is not selected from an accepted industry standard, the design load used to assess its strength and its attachment to the ship is to be in accordance with 2.3.

2.5 Supporting hull structure

2.5.1 Arrangement

The reinforced members beneath shipboard fittings are to be effectively arranged for any variation of direction (horizontally and vertically) of the towing forces (which is to be not less than the design load as per 2.3) acting through the arrangement of connection to the shipboard fittings.

2.5.2 Acting point of towing force

The acting point of the towing force on shipboard fittings is to be taken at the attachment point of a towing line or at a change in its direction.

2.5.3 Allowable stresses

Allowable stresses under the design load conditions as specified in 2.3 are as follows:

2.5.3.1 For strength assessment by means of beam theory or grillage analysis:

- Normal stress : $1,0 R_{eH}$
- Shear stress : $0,6 R_{eH}$

No stress concentration factors being taken into account. Normal stress is the sum of bending stress and axial stress.

2.5.3.2 For strength assessment by means of finite element analysis:

For strength assessment by means of finite element analysis the mesh is to be fine enough to represent the geometry as realistically as possible. The aspect ratios of elements are not to exceed 3. Girders are to be modelled using shell or plane stress elements. Symmetric girder flanges may be modelled by beam or truss elements. The element height of girder webs must

not exceed one-third of the web height. In way of small openings in girder webs the web thickness is to be reduced to a mean thickness over the web height as per **BCS** rules. Large openings are to be modelled. Stiffeners may be modelled by using shell, plane stress, or beam

elements. The mesh size of stiffeners is to be fine enough to obtain proper bending stress. If flat bars are modeled using shell or plane stress elements, dummy rod elements are to be modelled at the free edge of the flat bars and the stresses of the dummy elements are to be evaluated. Stresses are to be read from the centre of the individual element. For shell elements the stresses are to be evaluated at the mid plane of the element.

R_{eH} is the specified minimum yield stress of the material.

2.6 Safe working load (SWL)

2.6.1 The SWL used for normal towing operations is not to exceed 80% of the design load per 2.3.1 and SWL used for other towing operations is not to exceed the design load per 2.3.2. For fittings used both normal and other towing operations, the greater of the design loads of 2.3.1 and 2.3.2 is to be used.

2.6.2 The SWL of each shipboard fitting is to be marked (by weld bead or equivalent) on the deck fittings used for towing.

2.6.3 The above requirements on SWL apply for a single post basis (no more than one turn of one cable).

2.6.4 The towing and mooring arrangements plan mentioned in 3. is to define the method of use of towing lines.

3. Towing and Mooring Arrangements Plan

3.1 The SWL for the intended use for each shipboard fitting is to be noted in the towing and mooring arrangements plan available on board for the guidance of the Master.

3.2 Information provided on the plan is to include in respect of each shipboard fitting:

- Location on the ship,
- Fitting type,
- SWL,
- Purpose (mooring/harbour towing/escort towing); and,
- Manner of applying towing or mooring line load including limiting fleet angles.

This information is to be incorporated into the pilot card in order to provide the pilot proper information on harbour/escorting operations.

4. Corrosion Addition

The total corrosion addition, t_k , in mm. for both sides of the hull supporting structure is not to be less than 2,0 mm.

5. Surveys After Construction

The condition of deck fitting, their pedestals, if any, and the hull structures in the vicinity of the fittings are to be examined in accordance with **BCS** Rules. The wastage allowances as specified by **BCS** Rules are not to exceed the corrosion addition as specified in 4.

SECTION 19

HULL OUTFIT

		Page
A.	Partition Bulkheads.....	19-2
	1. Gastight partitions	
	2. Partition bulkheads between engine and boiler rooms	
B.	Breakwater	19-2
	1. Design references	
C.	Sheathings and Ceilings	19-2
	1. Deck sheathings	
	2. Bottom ceiling	
	3. Ceilings at tank bulkheads	
D.	Openings in Hull and Superstructures	19-3
	1. Openings in the shell plating	
	2. Pipe connections at the shell plating	
	3. Openings in closed superstructures	
	4. Side scuttles and windows	
E.	Scuppers, Sanitary Discharges and Freeing Ports.....	19-6
	1. Scuppers and sanitary discharges	
	2. Freeing ports	
F.	Air Pipes, Overflow Pipes, Sounding Pipes	19-8
	5. Special strength requirements for fore deck fittings	
G.	Ventilators	19-9
	1. General	
	2. Closing appliances	
H.	Stowage of Containers	19-11
	1. General	
	2. Load assumptions	
	3. Permissible stresses	
I.	Lashing Arrangements.....	19-12
J.	Life Saving Appliances	19-12
K.	Signal, Radar and Sensor Masts	19-12
	1. General	
	2. Signal masts	
	3. Radar and sensor masts	
	4. Structural details	
L.	Loading and Lifting Gear	19-14
M.	Guard Rails	19-15
N.	Ammunition Rooms	19-15
O.	Accesses to Ships	19-15
P.	Bottom Plugs	19-16

A. Partition Bulkheads**1. Gastight partitions**

Notwithstanding the ability of the ship to meet the requirements for NBC-protection, spaces, which are to be accessible for the service of the naval ship, such as spaces for storage, hangars, docks, etc. as well as accommodation spaces are to be gastight against each other.

2. Partition bulkheads between engine and boiler rooms

2.1 Rooms for auxiliary boilers are to be separated generally from adjacent engine rooms by bulkheads. Where these bulkheads are watertight or tank bulkheads, their scantlings must comply with Section 9 or 10 respectively.

2.2 The bilges are to be separated from each other in such a way that no oil can pass from the boiler room bilge to the engine room bilge. Bulkhead openings are to have hinged doors.

2.3 Where a close connection between engine and boiler room is advantageous in respect of supervision and safety, complete bulkheads may be dispensed with, provided the conditions given in Chapter 104 - Propulsion Plants and Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 15 are complied with.

B. Breakwater**1. Design references**

The scantlings of the breakwater are to be designed like unprotected front walls according to Section 8 with loads according to Section 5, C.1.

C. Sheathings and Ceilings**1. Deck sheathings****1.1 General requirements**

1.1.1 Generally the different deck sheathings of a naval ship on the weather deck, on superstructures and deckhouses have to meet the following requirements:

- Protection of the hull structure against corrosion in a standard climate defined by the Naval Authority e.g. in Europe for temperatures from -20 °C to +80 °C
- Good connection to the deck area
- Fire-resistant or at least not easily flammable
- Special requirements of the Naval Authority, like colour, etc.

1.1.2 Before establishing the deck sheathing, the structural material, on which the sheathing will be brought up, has to be prepared according to the specification of the supplier. Normally this will include cleaning, grinding, degreasing, etc.

1.1.3 The compliance with the requirements defined in 1.1.1 has to be shown by the supplier by tests with a reasonable number of specimens according to recognized standards and approved by **BCS**.

1.2 Decks for aircraft operation and helicopter landing

The special, additional requirements for flight decks are specified in Section 23, B.5.1.

1.3 Missile starting positions

The blast of rockets and missiles may influence the deck sheathing during the launch in the following way:

- High temperature of blast cone
- Efflux blast loading and blast speed
- Chemical composition of efflux and particles contained

The sheathing has to comply with the general requirements defined in 1.1.1. In addition, the thickness of the sheathing/cover has to be evaluated for the so called "hang fire" condition, when the motor of a missile ignites and burns out, but - by defect - does not leave the starting ramp.

2. Bottom ceiling

2.1 If a naval ship contains holds for the transport of materials or special equipment a tight bottom ceiling is to be fitted on the bottom of such a hold. It is recommended, that the thickness of a wooden ceiling is not less than 60 mm. If no ceiling is foreseen, **BCS** decide whether the thickness of the load bearing areas has to be increased case by case.

2.2 On single bottoms, ceilings are to be removable for inspection of bottom plating at any time.

2.3 Ceilings on double bottoms are to be laid on battens not less than 12,5 mm thick, providing a clear space for drainage of water or leakage oil. The ceiling may be laid directly on the inner bottom plating, if embedded in preservation and sealing compound.

2.4 It is recommended to fit double ceilings under deck openings used for loading/unloading.

2.5 The manholes are to be protected by a steel coaming welded around each manhole and shall be fitted with a cover of wood or steel, or by other suitable means.

3. Ceilings at tank bulkheads

Where tanks are intended to carry liquids at temperatures exceeding 40 °C, their boundaries facing holds for transport or storage shall be fitted with a ceiling. At vertical walls, sparred ceilings may be sufficient. The ceiling may be dispensed only with consent of the Naval Authority.

D. Openings in Hull and Superstructures

1. Openings in the shell plating

1.1 For bow doors and inner doors see Section 22, B.

1.2 For side shell doors and stern doors see Section 22, C.

1.3 Where openings are cut in the shell plating for windows or side scuttles, hawses, scuppers, sea valves etc., they are to have well rounded corners. If they exceed 500 mm in width in ships up to L = 70 metres, and 700 mm in ships having a length L of more than 70 metres, the openings are to be surrounded by framing or a thicker insert plate.

1.4 Above openings in the sheer strake within 0,4 L amidships, generally a strengthened plate or a continuous doubling is to be provided compensating the omitted plate sectional area. For shell doors and similar large openings see Section 22, C. Special strengthening is required in the range of openings at ends of superstructures.

1.5 The shell plating in way of the hawse pipes is to be reinforced.

2. Pipe connections at the shell plating

Scupper pipes and valves are to be connected to the shell by weld flanges. Instead of weld flanges short flanged sockets of adequate thickness may be used if they are welded to the shell in an appropriate manner. Reference is made to E. and **BCS** Rules, Chapter 107 Ship Operation Installations and Auxiliary Section 8, J.

Construction drawings are to be submitted for approval

3. Openings in closed superstructures

3.1 All access openings in end bulkheads and walls of closed superstructures shall be fitted with weathertight doors permanently attached to the bulkhead, having the same strength as the bulkhead.

The doors shall be so arranged that they can be operated from both sides of the bulkhead. Doors should generally open outwards to provide additional safety against the impact of the sea with hinges arranged in forward direction. Doors which open inwards are to be especially approved by **BCS**.

The coaming heights of the access openings above the deck are to be at least 600 mm in Pos. 1 **(1)**, see Section 14, A.2 and 380 mm in Pos. 2. Openings to deckhouses without access to spaces below the freeboard/bulkhead deck may have lower coamings if an equivalent level of safety can be achieved.

3.2 Portable sills should be avoided. However in order to facilitate loading/unloading of heavy equipment, spare parts, etc., portable sills may be fitted under following conditions:

- They must be installed before the naval ship leaves the basis or any port
- Sills are to be gasketed and fastened by closely spaced bolts
- The date of replacing shall be recorded in the ship's log book.

3.3 Any opening in a superstructure deck or in a deck directly above the freeboard deck like deckhouse surrounding companionways, is to be protected by efficient weathertight closures.

4. Side scuttles and windows

4.1 General

4.1.1 Side scuttles and windows, together with their glasses, deadlights and storm covers **(2)**, if fitted,

shall be of an approved design and substantial construction. Non-metallic frames are not acceptable.

4.1.2 Side scuttles are defined as being round or oval openings with an area not exceeding 0,16 m². Round or oval openings having areas exceeding 0,16 m² shall be treated as windows.

4.1.3 Windows are defined as being rectangular openings generally, having a radius at each corner relative to the window size and round or oval openings with an area exceeding 0,16 m².

4.1.4 Side scuttles to the following spaces shall be fitted with hinged inside deadlights:

- Spaces below freeboard deck
- Spaces within the first tier of enclosed superstructures
- First tier deckhouses on the freeboard deck protecting openings leading below or considered buoyant in stability calculations

Deadlights shall be capable of being closed and secured watertight if fitted below the freeboard deck and weathertight if fitted above.

4.1.5 Side scuttles shall not be fitted in such a position that their sills are below a line drawn parallel to the freeboard deck at side and having its lowest point 2,5 % of the breadth **B**, or 500 mm, whichever is the greatest distance, above the Summer Load Line, see Figure 19.1.

4.1.6 If the required damage stability calculations indicate that the side scuttles would become immersed at any intermediate stage of flooding or the final equilibrium waterline, they shall be of the non-opening type.

(1) *The definition of these positions is given in Section 1, B.*

(2) *Deadlights are fitted to the inside of windows and side scuttles, while storm covers are fitted to the outside of windows, where accessible, and may be hinged or portable.*




Figure 19.1 Arrangement of side scuttles

4.1.7 Windows shall not be fitted in the following locations:

- Below the freeboard deck
- In the first tier end bulkheads or sides of enclosed superstructures
- In first tier deckhouses that are considered buoyant in the stability calculations

4.1.8 Side scuttles and windows at the side shell in the second tier shall be provided with hinged inside deadlights capable of being closed and secured weathertight if the superstructure protects direct access to an opening leading below or is considered buoyant in the stability calculations.

4.1.9 Side scuttles and windows in side bulkheads set inboard from the side shell in the second tier which protect direct access below to spaces listed in 2.1.4 shall be provided with either hinged inside deadlights or, where they are accessible, permanently attached external storm covers which are capable of being closed and secured weathertight.

4.1.10 Cabin bulkheads and doors in the second tier and above separating side scuttles and windows from a direct access leading below or the second tier considered buoyant in the stability calculations may be

accepted in place of deadlights or storm covers fitted to the side scuttles and windows.

4.1.11 Deckhouses situated on a raised quarter deck or on the deck of a superstructure of less than standard height may be regarded as being in the second tier as far as the requirements for deadlights are concerned, provided that the height of the raised quarter deck or superstructure is equal to or greater than the standard quarter deck height.

4.1.12 Fixed or opening skylights shall have a glass thickness appropriate to their size and position as required for side scuttles and windows. Skylight glasses in any position shall be protected from mechanical damage and, where fitted in position 1 or 2, shall be provided with permanently attached deadlights or storm covers.

4.2 Design Load

4.2.1 The design load shall be in accordance with Section 5.

4.2.2 For ships with a length **L_c** equal to or greater than 100 m, loads in accordance with ISO 5779 and 5780 standard have to be calculated additionally. The greater value has to be considered up to the third tier.

4.2.3 Deviations and special cases are subject to separate approval.

4.3 Frames

4.3.1 The design has to be in accordance with ISO standard 1751, 3903 and 21005 or any other recognised, equivalent national or international standard.

4.3.2 Variations from respective standards may require additional proof of sufficient strength by direct calculation or tests. This is to be observed for bridge windows in exposed areas (e.g. within forward quarter of ships length) in each case.

4.4 Glass panes

4.4.1 Glass panes have to be made of thermally toughened safety glass (TSG), or laminated safety glass made of TSG. The ISO standards 614 and 21005 are to be observed.

4.4.2 The glass thickness for windows and side scuttles has to be determined in accordance with the respective ISO standard 21005 or any other equivalent national or international standard, considering the design loads given in 4.2.2. For sizes deviating from the standards, the formulas given in ISO 3903 may be used.

4.4.3 Heated glass panes have to be in accordance with ISO 3434.

4.4.4 An equivalent thickness (t_s) of laminated toughened safety glass is to be determined from the following formula:

$$t_s = \sqrt{t_1^2 + t_2^2 + \dots + t_n^2}$$

t_1 = glass pane 1, t_2 = glass pane 2, ... t_n = glass pane n

4.5 Tests

Windows and side scuttles have to be tested in accordance with the respective ISO standards 1751 and

3903. Where the size of the glass panes exceeds the ISO limit, i.e. 1100 × 800, the window is to be subjected to hydrostatic testing at 4 times the design pressure for the respective area.

E. Scuppers, Sanitary Discharges and Freeing Ports

1. Scuppers and sanitary discharges

1.1 Scuppers sufficient in number and size to provide effective drainage of water are to be fitted in the weather deck and in the freeboard deck within weathertight closed superstructures and deckhouses. Lower decks and decks within closed superstructures are to be drained to the bilge or special tanks. Scuppers from superstructures and deckhouses which are not closed weathertight are also to be led outside.

1.2 Scuppers draining spaces below the design waterline, are to be connected to pipes, which are led to the bilges or special tanks and are to be well protected.

1.3 Where scupper pipes are led outside from spaces below the freeboard deck and from weather tight closed superstructures and deckhouses, they are to be fitted with non-return valves of automatic type, which can be operated from a position always accessible and above the freeboard deck. Means showing whether the valves are open or closed (positive means of closing) are to be provided at the control position.

1.4 Where the vertical distance from the design waterline to the inboard end of the discharge pipe exceeds 0,01 L, the discharge may have two automatic non-return valves without positive means of closing provided that the inboard valve is always accessible for examination.

1.5 Where the vertical distance mentioned under 1.4 exceeds 0,02 L, a single automatic non-return valve without positive means of closing may be accepted. This relaxation is not valid for compartments below the freeboard deck of naval ships, for which a flooding calculation in the damaged condition is required.

1.6 Scuppers and discharge pipes originating at any level and penetrating the shell either more than 450 mm below the freeboard deck or less than 600 mm above the design waterline are to be provided with a non-return valve at the shell. This valve, unless required by 1.3, may be omitted if a heavy gauge discharge pipe is fitted.

1.7 Except in unmanned machinery and auxiliary machinery spaces, sea inlets and discharges in connection with the operation of the machinery may be controlled locally. The controls shall be readily accessible and shall be provided with indicators showing whether the valves are open or closed.

1.8 All valves including the ship side valves required under 1.2 to 1.7 are to be of steel, bronze or other approved ductile material. Ordinary cast iron is not acceptable. Pipe lines are to be of steel or similar material, see also Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8.

It is recommended to use scuppers according to DIN 87223 (non turning-off type) and DIN 87223 (turning-off type).

1.9 Scuppers and sanitary discharges should not be fitted above the design waterline in way of life raft launching positions or means for preventing any discharge of water into picket boats are to be provided for. The location of scuppers and sanitary discharges is also to be taken into account when arranging gangways, pilot access, troop embarkation recesses, etc.

1.10 No scuppers shall lead to aircraft operating decks. The special requirements for the drainage of flight decks are defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9,M.3.

1.11 If scuppers are arranged within the ship's NBC citadel, special measures have to be taken (e.g. water traps), which guarantee that the slight overpressure in the citadel will be kept at all operating conditions.

1.12 For special measures for the discharge of seawater used for fire fighting and spraying of the ship's

surface see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, R.

2. Freeing ports

2.1 Where bulwarks on exposed portions of freeboard and/or superstructure decks form wells, ample provision is to be made for rapidly freeing the decks of water.

2.2 Except as provided in 2.3 to 2.5 the minimum freeing port area on each side of the ship for each well on the freeboard deck is to be determined by the following formulae in cases where the sheer in way of the well is standard or greater than standard:

$$A = 0,7 + 0,035\ell \quad [\text{m}^2] \text{ for } \ell \leq 20 \text{ m}$$

$$A = 0,07\ell \quad [\text{m}^2] \text{ for } \ell > 20 \text{ m}$$

ℓ = length of bulwark [m]

$$\ell_{\max} = 0,7 L$$

The minimum area for each well on superstructure decks shall be one half of the area obtained by the formulae.

If the bulwark is more than 1,2 m in average height the required area is to be increased by 0,004 m² per metre of length of well and for each 0,1 m difference in height. If the bulwark is less than 0,9 m in average height, the required area may be decreased accordingly.

Freeing port areas which includes alternative solutions as direct seakeeping calculations (possibility of wet deck calculations etc.) should be accepted in accordance with Naval Authority and **BCS**.

2.3 In ships with no sheer the area calculated according to 2.2 is to be increased by 50 %. Where the sheer is less than the standard the percentage shall be obtained by linear interpolation.

2.4 In ships having open superstructures, adequate freeing ports are to be provided which guarantee proper drainage.

2.5 The lower edges of the freeing ports shall be as near to the deck as practicable. Two thirds of the freeing port area required shall be provided in the half of the well nearest to the lowest point of the sheer curve.

2.6 All such openings in the bulwarks shall be protected by rails or bars spaced approximately 230 millimetres apart. If shutters are fitted to freeing ports, ample clearance shall be provided to prevent jamming. Hinges shall have pins or bearings of non-corrodible material.

F. Air Pipes, Overflow Pipes, Sounding Pipes

1. Each tank is to be fitted with air pipes, overflow pipes and sounding pipes. The air pipes are in general to be led to above the exposed deck. The arrangement is to be such as to allow complete filling of the tank. For the arrangement and scantlings of pipes see Chapter 107 -Ship Operation Installations and Auxiliary Systems, Section 8, R. The height from the deck of the point where the water may have access is to be at least 760 mm on the freeboard deck and 450 mm on a superstructure deck.

2. Suitable closing appliances are to be provided for air pipes, overflow pipes and sounding pipes, see also Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8, R.

Where materials, containers, vehicles, etc. are carried on deck, the closing appliances are to be readily accessible at all times. In naval ships for which flooding calculations are to be made, the ends of the air pipes are to be above the damage waterline in the flooded condition. Where they immerge at intermediate stages of flooding, these conditions are to be examined separately.

3. Closely under the inner bottom or the tank top, holes are to be cut into floor plates and side girders as well as into beams, girders, etc., to give the air free access to the air pipes.

Besides, all floor plates and side girders are to be provided with limbers to permit the water or oil to reach the pump suction.

4. Sounding pipes are to be extended to directly above the tank bottom. The shell plating is to be strengthened by thicker plates or doubling plates under the sounding pipes.

5. Special strength requirements for fore deck fittings

5.1 General

The following strength requirements are to be observed to resist green sea forces for the items given below, located within the forward quarter length:

- Air pipes, ventilator pipes and their closing devices

5.2 Application

For ships that are contracted for construction on or after 1st July 2004 on the exposed deck over the forward 0,25 L, applicable to:

- All seagoing naval ships with a length L of 80 m or more, where the height of the exposed deck in way of the item is less than 0,1 L or 22 m above the summer load waterline, whichever is the lesser

5.3 Applied loading for air pipes, ventilator pipes and their closing devices

5.3.1 The pressures p [kN/m²] acting on air pipes, ventilator pipes and their closing devices may be calculated from:

$$p = 0,5 \cdot \rho \cdot V^2 \cdot C_d \cdot C_s \cdot C_p$$

ρ = Density of sea water (1,025 t/m³)

V = Velocity of water over the fore deck
= 13,5 m/sec for $d \leq 0,5 d_1$

$$= 13,5 \sqrt{2 \cdot \left(1 - \frac{d}{d_1}\right)} \text{ m/sec for } 0,5 d_1 < d < d_1$$

d = distance from summer load waterline to exposed deck

d_1 = 0,1 L or 22 m whichever is the lesser

C_d = Shape coefficient
 = 0,5 for pipes
 = 0,8 for an air pipe or ventilator head of cylindrical form with its axis in the vertical direction
 = 1,3 for air pipes or ventilator heads

C_s = Slamming coefficient
 = 3,2

C_p = Protection coefficient
 = 0,7 for pipes and ventilator heads located immediately behind a breakwater or forecastle
 = 1,0 elsewhere and immediately behind a bulwark

5.3.2 Forces acting in the horizontal direction on the pipe and its closing device may be calculated from 5.3.1 using the largest projected area of each component.

5.4 Strength requirements for air pipes, ventilator pipes and their closing devices

5.4.1 Bending moments and stresses in air and ventilator pipes are to be calculated at critical positions:

- at penetration pieces
- at weld or flange connections
- at toes of supporting brackets

Bending stresses in the net section are not to exceed $0,8 \cdot \sigma_y$, where σ_y is the specified minimum yield stress or 0,2 % proof stress of the steel at room temperature. Irrespective of corrosion protection, a corrosion Addition to the net section of 2,0 mm is then to be applied.

5.4.2 For standard air pipes of 760 mm height closed by heads of not more than the tabulated projected area, pipe thicknesses and bracket heights are specified in Table 19.1. Where brackets are required, three or more radial brackets are to be fitted.

Brackets are to be of gross thickness 8 mm or more, of minimum length 100 mm, and height according to Table 19.1 but need not extend over the joint flange for the

head. Bracket toes at the deck are to be suitably supported.

5.4.3 For other configurations, loads, according to 5.3 are to be applied, and means of support determined in order to comply with the requirements of 5.4.1. Brackets, where fitted, are to be of suitable thickness and length according to their height. Pipe thickness is not to be taken less than as indicated in the **BCS** Chapter 107 for Ship Operation Auxiliary Systems, Section 8, 8.20.

5.4.4 For standard ventilators of 900 mm height closed by heads of not more than the tabulated projected area, pipe thicknesses and bracket heights are specified in Table 19.2. Brackets, where required are to be as specified in 5.4.2.

5.4.5 For ventilators of height greater than 900 mm, brackets or alternative means of support are to be specially considered. Pipe thickness is not to be taken less than as indicated in the **BCS** Rules, Chapter 107 Ship Operation Installations and Auxiliary Section 8, Table 8.19 and Table 8.20.

5.4.6 All component part and connections of the air pipe or ventilator are to be capable of withstanding the loads defined in 5.3.

5.4.7 Rotating type mushroom ventilator heads are unsuitable for application in the areas defined in 5.2.

G. Ventilators

1. General

1.1 Ventilators need not be fitted with closing arrangements unless specifically required by the Naval Authority, if :

- in position 1 the coamings extend to more than 4,5 m above the deck
- in position 2 the coamings extend to more than 2,3 m above the deck

1.2 On exposed superstructure decks abaft 0,25 L from FP the coaming height is not to be less than 760 mm.

Table 19.1 760 mm air pipe thickness and bracket standards

Nominal pipe diameter [mm]	Minimum fitted (1) gross thickness [mm]	Maximum projected area of head [cm ²]	Height (2) of brackets [mm]
65A	6,0	-	480
80A	6,3	-	460
100A	7,0	-	380
125A	7,8	-	300
150A	8,5	-	300
175A	8,5	-	300
200A	8,5 (3)	1900	300 (3)
250A	8,5 (3)	2500	300 (3)
300A	8,5 (3)	3200	300 (3)
350A	8,5 (3)	3800	300 (3)
400A	8,5 (3)	4500	300 (3)
(1) See BCS- I LL 36 c. (2) Brackets see 5.4.1.3 need not extend over the joint flange for the head. (3) Brackets are required where the as fitted (gross) thickness is less than 10,5 mm, or where the tabulated projected head area is exceeded.			
Note: For other air pipe heights, the relevant requirements of 5.4 are to be applied.			

Table 19.2 900 mm ventilator pipe thickness and bracket standards

Nominal pipe diameter [mm]	Minimum fitted gross thickness [mm]	Maximum projected area of head [cm ²]	Height of brackets [mm]
80A	6,3	-	460
100A	7,0	-	380
150A	8,5	-	300
200A	8,5	550	-
250A	8,5	880	-
300A	8,5	1200	-
350A	8,5	2000	-
400A	8,5	2700	-
450A	8,5	3300	-
500A	8,5	4000	-
Note: For other ventilator heights, the relevant requirements of 5.4 are to be applied.			

1.3 Ventilators of holds are not to have any connection with other spaces.

1.4 The thickness of the coaming plates is to be 7,5 mm where the clear opening sectional area of the ventilator coaming is 300 cm² or less, and 10 mm where the clear opening sectional area exceeds 1600 mm². Intermediate values are to be determined by direct interpolation. A thickness of 6 mm will generally be sufficient within not permanently closed superstructures

1.5 The thickness of ventilator posts should be at least equal to the thickness of coaming as per 1.4.

1.6 The wall thickness of ventilator posts of a clear sectional area exceeding 1600 cm² is to be increased according to the expected loads.

1.7 Generally, the coamings and posts shall pass through the deck and shall be welded to the deck plating from above and below.

Where coamings or posts are welded onto the deck plating, fillet welds of $a = 0,5 \cdot t_0$, subject to Section 15, B.3.3 should be adopted for welding inside and outside.

1.8 Coamings and posts particularly exposed to wash of sea are to be efficiently connected with the ship's structure.

1.9 Coamings of a height exceeding 900 mm are to be specially strengthened.

1.10 Where the thickness of the deck plating is less than 10 mm, a doubling plate or insert plate of 10 mm is to be fitted. Their side lengths are to be equal to twice the length or breadth of the coaming.

1.11 Where beams are pierced by ventilator coamings, carlings of adequate scantlings are to be fitted between the beams in order to maintain the strength of the deck.

2. Closing appliances

2.1 Inlet and exhaust openings of ventilation systems are to be provided with easily accessible

closing appliances, which can be closed weathertight against wash of the sea. In ships of not more than 100 m in length, the closing appliances are to be permanently attached. Hinged covers are recommended for attachment, at least chains or wire ropes are to be used. In ships exceeding 100 m in length, they may be conveniently stowed near the openings to which they belong.

For larger covers it is recommended to install a remote control for the closing appliances with activation and indication of open and closed condition at the bridge.

2.2 If the height of the ventilator coaming exceeds 4,5 m above the freeboard deck resp. bulkhead deck or above exposed superstructure decks forward of 0,25 L from **FP** and exceeds 2,3 m above exposed superstructure decks abaft 0,25 L from **FP** closing appliances are required in special cases only.

2.3 For the case of fire draught-tight fire dampers are to be fitted.

3. For special strength requirements for fore deck fittings, see F.5.

H. Stowage of Containers

1. General

1.1 All parts for container stowing and lashing equipment are to comply with the **BCS Rules**, Part Chapter 51 - Stowage and Lashing of Containers. parts which are intended to be welded to the ship's including hatch covers, are to be made of complying with and tested in accordance **BCS Rules**, Part A, Chapter 2 Materials and Welding.

1.2 All equipment on deck and in holds essential for maintaining the safety of the ship and which are to be accessible at sea, e.g. firefighting equipment, sounding pipes etc., should not be made inaccessible by containers or their stowing and lashing equipment.

1.3 For transmitting the forces from the container stowing and lashing equipment into the ship's hull

adequate welding connections and local reinforcements of structural members are to be provided, see also 2. and 3.

1.4 Where inner bottom, decks, etc. are loaded with containers, adequate substructures, e.g. carlings, half height girders etc., are to be provided and the plate thickness is to be increased where required. For welded-in parts, see Section 15, B.2.

2 Load assumptions

2.1 The scantlings of the local ship structures and container substructures are to be determined on the basis of the Container Stowage and Lashing Plan.

2.2 For determining scantlings the following design forces are to be used which are assumed to act simultaneously in the centre of gravity of a stack:

ship's transverse (y-)direction:

$$0,5 \cdot g \cdot G \quad [\text{kN}]$$

ship's vertical (z-)direction:

$$(1 + a_z) g \cdot G \quad [\text{kN}]$$

G = stack mass [t]

a_z = vertical acceleration component, see Section 5, B.

3. Permissible stresses

3.1 The stresses in local ship structures and in substructures for containers and lashing devices are not to exceed the following values:

$$\sigma_b = \frac{R_{eH}}{1,5}$$

$$\tau = \frac{R_{eH}}{2,3}$$

$$\sigma_v = \sqrt{\sigma_b^2 + 3\tau^2} = \frac{R_{eH}}{1,3}$$

3.2 Where other structural members of the hull, e.g. frames, deck beams, bulkheads, hatchway coamings, bulwark stays, etc. are subjected to loads from containers and container lashing devices, these members are to be strengthened wherever necessary so that the actual stresses will not exceed those upon which the formulae in the respective Sections are based.

I. Lashing Arrangements

Lashing eyes and holes are to be arranged in such a way as to not unduly weaken the structural members of the hull. In particular where lashings are attached to frames, they are to be so arranged that the bending moment in the frames is not unduly increased. Where necessary, the frame is to be strengthened.

J. Life Saving Appliances

1. It is assumed that for the arrangement and operation of lifeboats and other life-saving appliances the regulations defined by the Naval Authority are complied with. It is recommended to follow the guidelines defined in the "International Convention for Safety of Life at Sea (SOLAS) 1974".

2. The design and testing of life saving appliances are not part of Classification. However, approval of the hull structure in way of the launching appliances taking into account the forces from the above appliances is part of Classification.

Note:

In all cases where BCS has been requested to approve the launching appliances, the BCS Additional Rules, Unified Interpretations for Life Saving Appliances apply.

K. Signal, Radar and Sensor Masts

1. General

1.1 Drawings of masts, mast substructures and hull connections are to be submitted for approval.

1.2 Vibration and shock aspects are not part of the classification process.

1.3 Loose and accessory parts are to comply with the **BCS** Rules , Part D, Chapter 50 , Rules for Appliances . All parts are to be individually shall be supervised and certified by **BCS**.

1.4 Other masts than covered by 2. and 3. as well as special construction forms, must as regards dimensions and design in each case be individually agreed with **BCS**.

2. Signal masts

The following requirements apply to single tubular or equivalent rectangular sections made of steel with an ultimate tensile strength $R_m = 400 \text{ N/mm}^2$, which are typically designed to carry only signals (navigation lanterns, flag and day signals).

2.1 Stayed masts

2.1.1 Stayed masts may be constructed as simply supported masts (rocker masts) or may be supported by one or more decks (constrained masts).

2.1.2 The diameter of stayed steel masts at the uppermost support is to be at least 20 mm for each 1 m length of mast (ℓ_w) from the uppermost support to the fixing point of shrouds. The length of the mast top above the fixing point of shrouds is not to exceed $1/3 \ell_w$.

2.1.3 Masts according to 2.1.2 may be gradually tapered towards the fixing point of shrouds to 75 per cent of the diameter at the uppermost support. The plate thickness is not to be less than $1/70$ of the diameter or at least 4 mm.

2.1.4 Wire ropes for shrouds are to be thickly galvanized. It is recommended to use wire ropes composed of a minimum number of thick wires, as for instance a rope construction 6x7 with a tensile breaking strength of $1\,570 \text{ N/mm}^2$ on which Table 19.3 is based. Other rope constructions shall be of equivalent stiffness.

2.1.5 Where masts are stayed forward and backwards by two shrouds on each side of the ship, steel wire ropes are to be used according to Table 19.3.

2.1.6 Where steel wire ropes according to Table 19.3 are used, the following conditions apply:

$$b \geq 0,3 \cdot h$$

$$0,15 \cdot h \leq a \leq b$$

Table 19.3 Definition of ropes for stays

h[m]	6	8	10	12	14	16
Rope diameter [mm]	14	16	18	20	22	24
Nominal size of shackle, rigging screw, rope socket	2,5	3	4	5	6	8
<i>h = height of shroud fixing point above shroud foot point</i>						

a = the longitudinal distance from a shroud's foot point to its fixing point

b = the transverse distance from a shroud's foot point to its fixing point

Alternative arrangements of stayings are to be of equivalent stiffness.

2.2 Unstayed masts

2.2.1 Unstayed masts may be completely constrained in the uppermost deck or be supported by two or more decks. In general, the fastenings of masts to the hull of a ship should extend over at least one deck height.

2.2.2 The scantlings for unstayed steel masts are given in the Table 19.4.

2.2.3 The diameter of masts may be gradually tapered to $D/2$ at the height of $0,75 \ell_m$.

Table 19.4 Scantlings of unstayed steel masts

Length of mast ℓ_m [m]	6	8	10	12	14
D x t [mm]	160x4	220x4	290 x 4,5	360x5,5	430 x 6,5
ℓ_m = length of mast from uppermost support to the top D = diameter of mast at uppermost support t = plate thickness of mast					

3. Radar and sensor masts

These masts are typically of 3-leg, box girder or frame work design.

3.1 For dimensioning, the dead loads, acceleration forces, see Section 5, B., and wind loads, see Section 5, I. are to be considered.

3.2 Where necessary, additional loads e. g. loads caused by the sea, fastening of crane booms or tension wires are also to be considered.

3.3 The design loads for 3.1 and 3.2 as well as the allowable stresses can be taken from the **BCS** Part D, Chapter 50, Rules for Lifting Appliances.

3.4 In case of 3-leg masts the individual leg forces shall be calculated with the aforementioned forces acting in the direction of a considered leg and rectangular to one of the two other legs.

3.5 Single tubular or rectangular masts mounted on the top of box girder or frame work masts may be dimensioned according to 2.

3.6 In case of thin walled box girder masts stiffening and/or additional buckling stiffeners may be necessary.

4. Structural details

4.1 The substructures are to be dimensioned for the transmission of the acting forces.

4.2 Doubling plates at mast feet are permissible only for the transmission of compressive forces since they are generally not suitable for the transmission of tensile forces or bending moments.

4.3 In case of tubular constructions all welded fastenings and connections must be of full penetration weld type.

4.4 If necessary, slim tubular structures are to be additionally stayed or supported in order to avoid vibrations.

4.5 The dimensioning normally does not require a calculation of vibrations. However, in case of undue vibrations occurring during the ship's trials a respective calculation will be required.

4.6 For determining scantlings of masts made from aluminium or austenitic steel, the requirements given in Section 3, B.4., and D. apply.

4.7 At masts solid steel ladders have to be fixed at least up to 1,50 m below top, if they have to be climbed for operational or maintenance purposes. Above them, suitable handgrips are necessary.

4.8 If possible from the construction point of view, ladders should be at least 0,30 m wide. The distance between the rungs shall be 0,30 m. The horizontal distance of the rung centre from fixed parts shall not be less than 0,15 m. The rungs shall be aligned and be made of square steel bars 20/20 edge up.

4.9 Platforms on masts which have to be used for operational reasons, shall have a rail of at least 0,90 m in height with one intermediate bar. Safe access from the mast ladders to the platform is to be provided.

4.10 If necessary, on masts a safety installation consisting of foot, back, and hand rings enabling safe work in places of servicing and maintenance is to be provided.

L. Loading and Lifting Gear

1. The dimensioning and testing of lifting

appliances, including derrick masts, derrick posts and their standing rigging on board ships, does not constitute part of the Classification of the ship. The Classification does, however, include checking the structure of the ship's hull in way of lifting appliances and forces transmitted thereby.

2. The dimensioning and testing of lifting appliances shall be as stipulated by the requirements defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 3 and in more detail by the **BCS** Rules, Part D, Chapter 50, Rules for Lifting Appliances.

3. The requirements of the Naval Authority and other requirements may be additionally complied with if this is agreed. If several regulations are to be applied their order of precedence is to be agreed upon.

4. Pad eyes for the reception or transmission of forces may be tested and hard stamped like lifting accessories if this is agreed upon.

5. On naval ships **BCS** normally only supervises and certifies the initial function and load testing which are to be conducted before lifting appliances are taken into use. If this is agreed upon would also conduct and certify regular surveys and/or load tests.

6. The equipment for replenishment at sea is defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 4.

M. Guard Rails

1. Efficient guard rails or bulwarks are to be fitted on all exposed parts of the freeboard and superstructure decks. The height is to be at least 1,0 m from the deck.

2. The height below the lowest course of the guard rails is not to exceed 230 mm. The other courses are not to be spaced more than 380 mm apart.

3. In the case of ships with rounded gunwales the guard rail supports are to be placed on the flat part of the deck.

4. Guard rails are to be constructed in accordance with a recognized standard (e.g. ISO 5480). Equivalent constructions of sufficient strength can be accepted.

5. Guard rail stanchions are not to be welded to the shell plating.

6. In special cases alternative solutions, like life lines, etc. may be acceptable.

N. Ammunition Rooms

An additional load for the structures of ammunition depots is to be considered to account for the case of a defective overflow piping system. If ammunition rooms are flooded according to the Chapter 107, Rules for Ship Operation Installations and Auxiliary Systems, Section 9, O., the complete space may finally be filled with water.

The total design load for filled ammunition room may be defined according to Section 5, G.3.

Note:

If the Naval Authority designates these depots and the stowage equipment therein as important for survival, their structure shall withstand shock loads as defined by the Naval Authority; see also Section 6.

O. Accesses to Ships

The design appraisal and testing of accesses to ships (accommodation ladders, gangways) are not part of Classification.

However, approval of substructures in way of accommodation ladders and gangways is part of Classification.

P. Bottom Plugs

Bottom plugs are not part of Classification. Following items are to be considered for guidance.

1. Plugs are to be manufactured in accordance with a recognized standard (e.g. JIS). Pads, if required, are to be the same grade of the steel where fitted.
2. Welding of plugs are to be checked visually and with a suitable NDE method if deemed necessary by the Surveyor.

3. Plugs are not to be fitted to spaces other than tanks (e.g. bilges, wells).

4. Welding of plugs are to be checked visually and with a suitable NDE method if deemed necessary by the Surveyor.

5. Plug heads should be chosen different to distinguish tank content (e.g. square heads for oil tanks, hexagonal for water tanks).

SECTION 20

STRUCTURAL FIRE PROTECTION

		Page
A.	General	20-2
	1. Application	
	2. Definitions	
B.	Basic Requirements for all Ships.....	20-4
	1. Documents to be submitted	
	2. Main structure	
	3. Restricted use of combustible materials	
	4. Means of escape	
	5. Fire detection system	
C.	Additional Requirements for Ships with Class Notation SFP	20-7
	1. General	
	2. Application	
	3. Documents to be submitted	
	4. Fire-resisting divisions	
	5. Restricted use of combustible materials	
	6. Means of escape and arrangement	
	7. Openings in fire-resisting divisions	
	8. Ventilation	
	9. Fire detection system	
	10. Fixed sprinkler system	
	11. Protection of Special Category Spaces and Ro-Ro Spaces	
	12. Requirements for Flight Decks and Hangars	

A. General

1. Application

1.1 The requirements of this Section are divided into two parts. Basic requirements according to B. and some part of C. which are determined case by case between the Naval Authority and the shipyard and agreed by **BCS**, apply to all classified naval In case the class notation SFP is additional requirements according to complied with.

1.2 Where this Section requires that a particular fitting, material, appliance or apparatus, or type thereof, shall be fitted or carried in a ship, or that any particular provision shall be made, **BCS** may allow any other material, appliance or apparatus, or type thereof fitted or carried, or any other provision to be ship, if it is satisfied by trial thereof or such fitting, material, appliance or thereof, or provision, is at least required by this Section.

Where compliance with any of the requirements of this Section would be impracticable for the particular design of the ship, **BCS** may substitute those with

1.3 The fire fighting systems and equipment for fire fighting is defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8 and 9.

1.4 The electrical installations for fire detection are defined in Chapter 105 - Electrical Installations.

2. Definitions

2.1 General definitions

2.1.1 Fire-restricting materials

Fire-restricting materials are those materials which have

fire-retarding properties in accordance with a standard acceptable to **BCS**.

2.1.2 Non-combustible material

Non-combustible material is a material which neither burns nor gives off flammable vapours in sufficient quantity for self-ignition when heated to approximately 750 °C, this being determined by a standard acceptable to **BCS**. Any other material is a combustible material.

2.1.3 Low flame spread

Low flame spread means that the surface thus described will adequately restrict the spread of flame, this being determined in accordance with a standard acceptable to **BCS**.

2.1.4 Equivalent material

Where the term "steel or other equivalent material" occurs, equivalent material means any non-combustible material which, by itself or due to insulation provided, has structural and integrity properties equivalent to steel at the end of the applicable exposure to the standard fire test (e. g. aluminium alloy with appropriate insulation).

2.1.5 Smoke-tight

Smoke-tight means that a division made of non-combustible or fire-restricting materials is capable of preventing the passage of smoke.

2.1.6 Fire-resisting divisions

Fire-resisting divisions are those divisions formed by bulkheads and decks which comply with the following:

2.1.6.1 They shall be constructed of non-combustible or fire-restricting materials which by insulation or inherent fire-resisting properties satisfy the following requirements.

2.1.6.2 They shall be suitably stiffened.

2.1.6.3 They shall be so constructed as to be capable of preventing the passage of smoke and flame up to the end of the appropriate fire protection time.

2.1.6.4 Where required they shall maintain load-carrying capabilities up to the end of the appropriate fire protection time.

2.1.6.5 They shall have thermal properties such that the average temperature on the unexposed side will not rise more than 140 °C above the original temperature, nor will the temperature, at any one point, including any joint, rise more than 180 °C above the original temperature during the appropriate fire protection time.

2.1.6.6 A prototype bulkhead or deck shall be required to ensure that the above requirements are met in accordance with approval by **BCS**.

2.1.7 Main vertical zones

Main vertical zones are those sections into which the hull, superstructure and deckhouses are divided by fire-resisting divisions, the mean length and width of which on any deck does not in general exceed 40 m.

2.1.8 Place of refuge

"Place of refuge" is any naturally or artificially sheltered area which may be used as a shelter by a ship or the persons on board under conditions likely to endanger the ship's safety.

2.2 Spaces other than machinery spaces

2.2.1 Accommodation spaces

Accommodation spaces are those spaces used for mess rooms, recreation rooms, corridors, cabins, sickbays, offices, lavatories and similar spaces.

2.2.2 Service spaces

Service spaces are those spaces used for pantries containing food warming equipment but no cooking facilities with exposed heating surfaces, lockers, store

rooms, work shops other than those forming part of the machinery spaces, and similar spaces and trunks to such spaces.

2.2.3 Galleys

Galleys are those enclosed spaces containing cooking facilities with exposed heating surfaces, or which have any cooking or heating appliances each having a power of more than 5 kW.

2.2.4 Cargo spaces

Cargo spaces are all spaces other than special category spaces and ro-ro spaces used for cargo and trunks to such spaces.

2.2.5 Special category spaces

Special category spaces are those enclosed ro-ro spaces, enclosed helicopter and fixed wing aircraft hangars where also maintenance work is performed, enclosed bays for landing craft, midget-submarines, etc. to which embarked troops have access. Special category spaces may be accommodated on more than one deck provided that the total overall clear height for vehicles, aircraft, etc. does not exceed 10 m.

2.2.6 Ro-ro spaces

Ro-ro spaces are spaces not normally subdivided in any way and normally extending to either a substantial length or the entire length of the ship in which motor vehicles, tanks, assault craft and other military vehicles with fuel in their tanks for their own propulsion and/or military goods, trailers, containers, pallets, demountable tanks or in or on similar stowage units or other respectables can be loaded and unloaded, normally in horizontal direction.

2.2.7 Open ro-ro spaces

Open ro-ro spaces are those ro-ro spaces, which:

- Are open at both ends, or
- Are open at one end and are provided with

permanent openings distributed in the side plating or deck head or from above, having a total area of at least 10 % of the total area of the space sides.

2.2.8 Control stations

Control stations are bridge, radio room, combat information centre (CIC), machinery control centre (MCC), damage control centre (DCC) and flight control centre (FCC) as well as gyro compass and analogous spaces, spaces where the emergency source of power and emergency switchboard or comparable systems are located or where the fire recording or fire control equipment is centralized or where other functions essential to the safe operation of the ship such as propulsion control, public address, stabilisation systems, etc. are located.

2.2.9 Continuously manned control station

A continuously manned control station is a control station which is continuously manned by a responsible member of the crew while the ship is in normal service.

2.2.10 Assembly station

Assembly station is an area or space where crew and embarked troops can be gathered in the event of an emergency, given instructions and prepared to abandon the ship, if necessary.

2.3 Machinery spaces

2.3.1 Machinery spaces (main spaces)

Machinery spaces are spaces containing internal combustion engines with an aggregate total power output of more than 110 kW, generators, oil fuel units, propulsion machinery, major electrical machinery and similar spaces and trunks to such spaces.

2.3.2 Auxiliary machinery space

Auxiliary machinery spaces are spaces containing internal combustion engines of power output up to and including 110kW, driving generators, sprinkler, drencher or fire pumps, bilge pumps etc., oil filling stations,

switchboards of aggregate capacity exceeding 800 kW, similar spaces and trunks to such spaces.

2.3.3 Auxiliary machinery spaces having little or no fire risk

Auxiliary machinery spaces having little or no fire risk are spaces containing refrigerating, stabilizing, ventilation and air conditioning machinery, switch boards of aggregate capacity 800 kW or less, similar spaces and trunks to such spaces.

B. Basic Requirements for all Ships

The requirements of B. apply to all ships.

1. Documents to be submitted

In addition to the documentation defined in Section 1, Table 1.3 the following documentation is to be submitted:

- Escape way plan
- Fire control plan
- List of type-approved materials with respect to linings and ceilings, insulation, deck coverings, interior surfaces (type, maker, approval number)

The documentation is to be submitted in triplicate . reserve the right to ask for additional information supplementary copies , if deemed particular cases.

2. Main structure

The hull, superstructures, structural bulkheads, decks, deckhouses and pillars shall be constructed of approved non-combustible materials having adequate structural properties. The use of other fire-restricting materials may be permitted provided the requirements of this Section are complied with and the materials are approved by **BCS**.

3. Restricted use of combustible materials

3.1 Insulation, lining, ceiling, deck covering and draught stop materials

3.1.1. All separating divisions, ceilings or linings shall be of non-combustible or fire-restricting materials. Draught stops shall be of non-combustible or fire-resisting material.

3.1.2 Where insulation is installed in areas in which it could come into contact with any flammable liquids or vapours, its surface shall be impermeable to such flammable liquids or vapours.

3.1.3 Any thermal and acoustic insulation shall be of non-combustible or of fire-resisting material. Vapour barriers and adhesives used in conjunction with insulation, as well as insulation of pipes for cold service systems need not be non-combustible or fire-restricting, but they shall be kept to the minimum quantity practicable and their exposed surfaces shall have approved low flame spread characteristics.

3.1.4. All deck finishing materials shall be of an approved standard.

3.1.5 Void spaces, where low-density combustible materials are used to provide buoyancy, shall be protected from adjacent fire hazard areas by fire-resisting divisions, in accordance with Table 20.1. The space shall be gastight towards adjacent spaces and shall be ventilated to atmosphere.

3.2 Surface materials

3.2.1 The following surfaces shall, as a minimum standard, be constructed of materials having approved low flame-spread characteristics:

- Exposed surfaces in corridors and stairway enclosures, and of bulkheads (including windows), wall and ceiling linings in all accommodation and service spaces and control stations
- Surfaces in concealed or inaccessible spaces in corridors and stairway enclosures, accommodation and service spaces and control stations

3.2.2 Exposed surfaces in corridors and stairway enclosures, and of bulkheads (including windows), wall and ceiling linings, in accommodation, service spaces and control stations shall be constructed of materials which, when exposed to fire, are not capable of producing excessive quantities of smoke or toxic products, this being determined with an approved fire test procedure.

4. Means of escape

4.1 General requirements

4.1.1 Unless expressly provided otherwise, at least two widely separated and ready means of escape shall be provided from all spaces or group of spaces.

4.1.2 Lifts shall not be considered as forming one of the means of escape.

4.2 Means of escape from accommodation and service spaces and control stations

4.2.1 Stairways, ladders and corridors

Stairways and ladders shall be so arranged as to provide ready means of escape to the life-saving appliances embarkation decks from all spaces in which personnel is normally employed or accommodated, other than machinery spaces.

No dead-end corridors having a length of more than 7 m shall be accepted.

Stairways and corridors used as means of escape shall be not less than 700 mm in clear width and shall have at least a handrail on one side. Stairways and corridors with a clear width of 1 800 mm and over shall have handrails on both sides. "Clear width" is considered the distance between the handrail and the bulkhead on the other side or between the handrails. Doorways which give access to a stairway shall be of the same size as the stairway.

4.2.2 Doors in escape routes

Doors in escape routes shall, in general, open in way of the direction of escape, except that:

- Individual cabin doors may open into the cabins in order to avoid injury to persons in the corridors when the door is opened.
- Doors in vertical emergency escape trunks may open out of the trunk in order to permit the trunk to be used both, for escape and for access.

4.2.3 Escape from spaces below the bulkhead deck or the lowest open deck

Below the bulkhead deck or the lowest open deck the main means of escape shall be a stairway and the second escape may be a watertight door, a trunk or a stairway.

4.2.4 Escape from spaces above the bulkhead deck or the lowest open deck

Above the bulkhead deck or the lowest open deck the means of escape shall be stairways or doors to an open deck or a combination thereof.

4.2.5 Exceptionally, **BCS** may dispense with one of the means of escape for spaces that are entered only occasionally, if the required escape route is independent of watertight doors.

4.3 Means of escape from machinery spaces

Means of escape from each machinery space shall comply with the following provisions.

4.3.1 Except as provided in 4.3.2, two means of escape shall be provided from each main machinery space other than auxiliary machinery spaces. In particular, one of the following provisions shall be complied with:

4.3.1.1 Two sets of steel ladders, as widely separated as possible, leading to doors in the upper part of the space, similarly separated and from which access is provided to the open deck. One of these ladders shall provide continuous fire shelter from the

lower part of the space to a safe position outside the space. This fire shelter shall be of steel and shall be insulated to the satisfaction of **BCS** and provided self-closing doors if necessary; or

4.3.1.2 One steel ladder leading to a door in the upper part of the space from which access is provided to the open deck and, additionally, in the lower part of the space and in a position well separated from the ladder referred to, a steel door capable of being operated from each side and which provides access to a safe escape route from the lower part of the space to the open deck.

4.3.2 For smaller ships **BCS** may dispense with one of the means of escape required in 4.3.1, due regard being paid to the dimension and disposition of the upper part of the space. In addition, the means of escape from the machinery spaces need not comply with the requirement for a continuous fire shelter as per 4.3.1.1. In steering gear spaces, a second means of escape shall be provided when the emergency steering position is located in that space unless there is direct access to the open deck.

4.3.3 From all kinds of auxiliary machinery spaces, two escape routes shall be provided except that a single escape route may be accepted for spaces that are entered only occasionally, and for spaces where the maximum walking distance to the door is 5 m or less.

4.3.4 One of the escape routes from the machinery spaces where the crew is normally employed shall avoid direct access to any special category space.

4.4 Means of escape from special category and open ro-ro spaces to which embarked personnel can have access

In special category and open ro-ro spaces to which embarked personnel can have access, the number and locations of the means of escape both below and above the bulkhead deck shall be to the satisfaction **BCSBCS** in general, the safety of access to the open deck be at least equivalent to that provided for under and 4.2.5. Such spaces shall be designated walkways to the means of escape with a

width of at least 600 mm. The parking arrangements for the vehicles shall maintain the walkways at all times.

4.5 Means of escape from ro-ro spaces

At least two means of escape shall be provided in ro-ro spaces where the crew and/or embarked troops are normally employed. The escape routes shall provide a safe escape to the open deck and shall be located at the fore and aft end of the space.

5. Fire detection system

The spaces to be provided with a fixed fire detection and fire alarm system are defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, C.

C. Additional Requirements for Ships with Class Notation SFP

1. General

The requirements of C. are additional to those of B. They are based on relevant experience and international regulations, but their use is optional in accordance with the intentions of the Naval Authority and if fully met, the Class Notation **SFP** (structural fire protection) will be granted. The requirements of C. take precedence over B. For ships without SFP refer to A.1.1.

2. Application

The requirements of C. apply on the following conditions unless hull, superstructures, structural bulkheads, decks and deckhouses are constructed of steel or equivalent material and all divisions, ceilings, linings and insulations are made from approved non-combustible materials:

- Ships are capable of maintaining the main functions and safety systems of unaffected spaces after fire in any one compartment on board. Ships need not be able to return to a place of refuge under its own power.
- All personnel on board can abandon the ship within a period less than the structural fire

protection time for major hazard areas as per 4.2.2.

- Ships do not proceed during their mission more than 8 hours at operational speed from a base at land or sea or any other place of refuge.

3. Documents to be submitted

The documentation to be submitted for approval in addition to the documentation defined in B.1. is defined as follows:

- Fire division plan
- Insulation plan
- Arrangement of draught stops
- Fundamental design of constructing draught stops
- Deck covering plan
- Joiner plan
- Fire barrier penetrations of ducts, pipes and cables, including information on type, maker and approval number
- Fire door plan
- Ventilation and air condition functional scheme
- List of type-approved structural components and materials with respect to fire divisions, fire doors, fire dampers, combustible duct materials, furniture materials, suspended textile materials, bedding component materials (type, maker, approval numbers)
- Space allocation of fire detectors and sprinkler heads
- Fire protection scheme for flight decks

The documentation is to be submitted in triplicate . reserve the right to ask for additional information supplementary copies , if deemed particular cases.

4. Fire-resisting divisions

Ships of all types shall be subdivided into thermal and structural divisions having regard to the fire risk of the space.

4.1 Main vertical and horizontal zones

4.1.1 Vertical zones

4.1.1.1 The hull, superstructure and deckhouses shall be subdivided into main vertical zones by fire-resisting divisions of 60 minutes structural fire protection time on either side. Where a category C space defined in 4.2.2.3 or where fuel oil tanks are adjacent to the division no fire insulation need to be provided on that side.

4.1.1.2 As far as practicable, the bulkheads forming the boundaries of the main vertical zones above the bulkhead deck shall be in line with watertight subdivision bulkheads situated immediately below the bulkhead deck. The length and the width of main vertical zones may be extended to a maximum of 48 m in order to bring the ends of main vertical zones to coincide with watertight subdivision bulkheads or in order to arrange a large accommodation space extending for the whole length of the main vertical zone provided that the total area of the main vertical zone is not greater than 1600 m² on any deck. The length or width of a main vertical zone is the maximum distance between the furthestmost points of the bulkheads bounding it.

4.1.1.3 The bulkheads forming boundaries of main vertical zones shall extend from deck to deck and to the shell or other boundaries.

4.1.2 Horizontal zones

4.1.2.1 In ships designed for special purposes, such as amphibious warfare vessels or aircraft carriers, where the provision of main vertical zone bulkheads would defeat the purpose for which the ship is intended, equivalent means for controlling and limiting a fire shall be substituted and specially approved by **BCS**.

4.1.2.2 The basic principle is that the main vertical

zoning may not be practicable in vehicle spaces and, therefore, equivalent protection must be obtained in such spaces on the basis of a horizontal zone concept and by the provision of an efficient fixed fire-extinguishing system. Based on this concept, a horizontal zone for the purpose of this regulation may include special category spaces on more than one deck provided that the total overall clear height for vehicles does not exceed 10 m.

4.1.2.3 The basic principle underlying the provisions of 4.1.2.2 is also applicable to ro-ro spaces.

4.1.2.4 The requirements for ventilation systems, openings and penetrations in fire-resisting divisions for maintaining the integrity of vertical zones in this Section shall be applied equally to decks and bulkheads forming the boundaries separating horizontal zones from each other and the remainder of the ship.

4.1.2.5 Notwithstanding the provisions of 4.1.1, the boundary bulkheads and decks of special category spaces and ro-ro spaces shall have 60 min structural fire protection time on either side. However, where a category C space is adjacent to the division or where fuel oil tanks are below a special category space or a ro-ro space, no fire insulation need to be provided on that side.

4.2 Fire integrity of decks and bulkheads

4.2.1 In addition to complying with the specific provisions for the fire integrity of bulkheads and decks, the minimum fire integrity of all bulkheads and decks shall be in accordance with Table 20.1. The classification of the space use is defined in 4.2.2.

4.2.2 Classification of space use

For the purposes of classification of space use in accordance with fire hazard risks, the following grouping shall apply:

4.2.2.1 Areas of major fire hazard

"Areas of major fire hazard" referred to in Table 20.1 by A, include the following spaces:

- Machinery spaces
- Rocket silos or similar
- Ro-ro spaces
- Spaces containing dangerous goods
- Special category spaces
- Store-rooms containing flammable liquids
- Galleys
- Aircraft hangars, refuelling and maintenance facilities
- Trunks as part of above spaces

4.2.2.2 Areas of moderate fire hazard

"Areas of moderate fire hazard" referred to in Table 20.1 by B, include the following spaces:

- Auxiliary machinery spaces
- Accommodation containing sleeping berths
- Service spaces
- Trunks as part of above spaces

4.2.2.3 Areas of minor fire hazard

"Areas of minor fire hazard" referred to in Table 20.1 by C, include the following spaces:

- Auxiliary machinery spaces having little or no fire risk
- Cargo spaces
- Ammunition storage rooms, rooms for handling and storage of torpedoes, mines, aircraft missiles, etc.
- Tanks, voids and areas of little or no fire risk

- Fuel tank compartments
- Corridors in accommodation areas and stairway enclosures
- Accommodation other than defined in 4.2.2.2
- Trunks as part of the above spaces

4.2.2.4 Control stations

"Control stations" referred to in Table 20.1 by D, are the spaces as defined in A.2.2.8.

4.2.2.5 Evacuation stations and external escape routes

Evacuation stations and external escape routes referred to in Table 20.1 by E, include the following areas:

- External stairs and open decks used for escape routes
- Assembly stations, internal and external
- Open deck spaces forming boat and liferaft embarkation and lowering stations
- The ship's side to the waterline in the lightest seagoing condition, superstructure and deck-house sides situated below and adjacent to the liferaft's and evacuation system's embarkation areas

4.2.2.6 Open spaces

"Open spaces" referred to in Table 20.1 by F, include open spaces locations other than evacuation stations and external escape routes and control stations.

4.2.3 Fire-resisting divisions

4.2.3.1 The requirements below apply to all ships irrespective of construction material. The structural fire protection times for separating bulkheads and decks not bounding either main vertical zones or horizontal zones shall be in accordance with Table 20.1 and the structural fire protection times are all based on providing

protection for a period of 60 min. If any other lesser fire protection time is determined depending on the time needed for the evacuation of the ship, then the times given below in 4.2.3.5 and 4.2.3.6 may be amended pro rata. In no case shall the structural fire protection time be less than 30 min.

4.2.3.2 In using Table 20.1 it shall be noted that the title of each category is intended to be typical rather than restrictive. For determining the appropriate fire integrity standards to be applied to boundaries between adjacent spaces, where there is doubt as to their classification for the purpose of this Section, they shall be treated as spaces within the relevant category having the most stringent boundary requirement.

4.2.3.3 Areas of major and moderate fire hazard shall be enclosed by fire-resisting divisions complying with the requirements of A.2.1.6 except where the omission of any such division would not affect the safety of the ship. These requirements need not apply to those parts of the structure in contact with water at the lightweight condition, but due regard shall be given to the effect of temperature of hull in contact with water and heat transfer from any uninsulated structure in contact with water to insulated structure above the water.

4.2.3.4 In approving structural fire protection details, **BCS** will have regard to the risk of heat transmission intersections and terminal points of required barriers.

4.2.3.5 Fire-resisting bulkheads and decks shall be constructed to resist exposure to the standard fire test for a period of 30 min for areas of moderate fire hazard and 60 minutes for areas of major fire hazard except as provided in 4.2.3.1.

4.2.3.6 Main load-carrying structures within areas of major fire hazard and areas of moderate fire hazard and structures supporting control stations shall be arranged to distribute load such that there will be no collapse of the construction of the hull and superstructure when it is exposed to fire for the appropriate fire protection time. The load-carrying structure shall also comply with the requirements of 4.2.3.7 and 4.2.3.8.

4.2.3.7 If the structures specified in 4.2.3.6 are made of aluminium alloy, their insulation shall be such that the temperature of the core does not rise more than 200 °C above the ambient temperature in accordance with the times in 4.2.3.1 and 4.2.3.5.

4.2.3.8 If the structures specified in 4.2.3.6 are made of combustible material, their insulation shall be such that their temperatures will not rise to a level where deterioration of the construction will occur during the exposure to the standard fire test to such extent that the load-carrying capability, in accordance with the times in 4.2.3.1 and 4.2.3.5 will be impaired.

4.2.3.9 The construction of all doors and door frames in fire-resisting divisions, with the means of securing them when closed, shall provide resistance to fire as well as to the passage of smoke and flame equivalent to that of the bulkheads in which they are situated. Watertight doors of steel need not be insulated. The use of combustible materials in doors separating cabins from individual interior sanitary accommodation, such as showers, may be permitted. Also, where a fire-resisting division is penetrated by pipes, ducts, electrical cables etc. arrangements shall be made to ensure that the fire-resisting integrity of the division is not impaired, and necessary testing shall be carried out in accordance with the standard fire test.

4.2.3.10 Draught stops shall be placed at a distance acceptable to **BCS**.

5. Restricted use of combustible materials

Furniture and furnishings in accommodation, service spaces, etc. shall comply with the following standards unless hull, superstructures, structural bulkheads, decks and deckhouses are constructed of steel or equivalent material and all divisions, ceilings, linings and insulation are made from approved non-combustible materials:

- All case furniture is constructed entirely of approved non-combustible or fire-restricting materials, except that a combustible veneer with a calorific value not exceeding 45 MJ/m² may be used on the exposed surface of such articles.

- All other furniture such as chairs, tables, etc. is constructed with frames of approved non-combustible or fire-restricting materials.
- All draperies, curtains, other suspended textile materials have qualities of resistance to the propagation of flame in accordance with BCS approved procedures.
- All upholstered furniture and bedding components have qualities of resistance to the ignition and propagation of flame, this being determined in accordance with approved procedures.

6. Means of escape and arrangement

6.1 Above the bulkhead deck or the lowest open deck there shall be at least two means of escape from each main vertical zone or similarly restricted space or group of spaces at least one of which shall give access to a stairway forming a vertical escape or to doors to an open deck or a combination thereof.

6.2 Internal stairways connecting only two decks need only be enclosed at one deck by means of divisions and self-closing doors having the structural fire protection time as required in Table 20.1 for divisions separating those areas which each stairway serves.

6.3 Lift trunks shall be fitted such as to prevent the passage of smoke and flame from one deck to another and shall be provided with means of closing so as to permit the control of draught and smoke.

6.4 In accommodation, service spaces, control stations, corridors and stairways, air spaces behind ceilings, panelling or linings shall be suitably divided by close-fitting draught stops not more than 14 m apart.

7. Openings in fire-resisting divisions

7.1 Except for any hatches between cargo, special category, ro-ro, and store spaces and between such spaces and the weather deck, all openings shall be provided with permanently attached means of closing which shall be at least as effective for resisting fires as the divisions in which they are fitted.

7.2 It shall be possible for each door to be opened and closed from each side of the bulkhead by one person only.

7.3 Fire doors

7.3.1 Fire doors bounding major fire hazard areas and in main vertical zone bulkheads and stairway enclosures, other than power-operated watertight doors and those which are normally locked, shall be self-closing.

7.3.2 Doors required to be self-closing shall not be fitted with hold-back facilities. However, hold-back arrangements as well as power-operated drive facilities fitted with remote release devices of the fail-safe type may be utilized.

7.3.3 Doors fitted in boundary bulkheads of machinery spaces shall be reasonable gastight and self-closing.

7.3.4 In corridor bulkheads ventilation openings may be permitted in and under doors of cabins, lavatories, offices, pantries, lockers and small store rooms. Except, as permitted below, the openings shall be provided only in the lower half of the door. Where such an opening is under a door the total net area of any such opening or openings shall not exceed 0,05 m².

Alternatively, a non-combustible air balance duct routed between the cabin and the corridor, and located below the sanitary unit is permitted where the cross-sectional area of the duct does not exceed 0,05 m². Ventilation openings shall be fitted with a grille made of non-combustible material.

7.4 Outer boundaries facing open spaces

The requirements for integrity of fire-resisting divisions of the outer boundaries facing open spaces of a ship shall not apply to windows and side scuttles. Similarly, the requirements for integrity of fire-resisting divisions facing open spaces shall not apply to exterior doors in superstructures and deckhouses.

7.5 Doors in smoke-tight divisions

Doors in smoke-tight divisions shall be self-closing.

Doors which are normally kept open shall close automatically or by remote control from a continuously manned control station.

8. Ventilation

8.1 The main inlets and outlets of all ventilation systems shall be capable of being closed from outside the spaces being ventilated. In addition such openings to areas of major fire hazard shall be capable of being remotely closed from a continuously manned control station.

8.2 All ventilation fans shall be capable of being stopped from outside the spaces which they serve, and from outside the spaces in which they are installed. Ventilation fans serving areas of major fire hazard shall be capable of being remotely operated from a continuously manned control station. The means provided for stopping the power ventilation to the machinery space and those for stopping the ventilation of other spaces shall be clearly separated from each other.

8.3 In general, the ventilation fans shall be disposed that the ducts reaching the various spaces remain within the main vertical zone.

8.4 The ventilation of assembly stations shall be separated from areas of major fire hazard. Ventilation ducts for areas of major fire hazard shall not pass through other spaces and ventilation ducts of other spaces shall not pass through areas of major fire hazard, unless the ducts are of an approved 60 minutes structural fire protection standard. Ventilation outlets from areas of major fire hazard shall not terminate within a distance of 1 m from any control station, evacuation station or external escape route.

In addition, exhaust ducts from galley ranges shall be fitted with:

- A grease trap readily movable for cleaning unless an alternative approved grease removal system is fitted
- A fire damper located in the lower end of the duct which is automatically and remotely

operated, and in addition a remotely operated fire damper located in the upper end of the duct

- A fixed means for extinguishing a fire within the duct in accordance with Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9,K.
- Remote control arrangements for shutting off the exhaust fans and supply fans, for operating the fire dampers mentioned above and for operating the fire-extinguishing system, which shall be placed in a position close to the entrance to the galley. Where a multi-branch system is installed, means shall be provided to close all branches exhausting through the same main duct before an extinguishing medium is released into the system.
- Suitably located hatches for inspection and cleaning

8.5 Where a ventilation duct passes through a fire-resisting division, a fail safe automatic closing fire damper shall be fitted adjacent to the division if the duct has a free cross-sectional area exceeding 0,075 m² or a main vertical zone division is penetrated. The duct between the division and the damper- shall be of steel or other equivalent material and insulated to the same standard as required for the fire-resisting division. The fire damper may be omitted where ducts pass through spaces surrounded by fire-resisting divisions without serving those spaces providing that the duct has the same structural fire protection time as the division it penetrates. Where a ventilation duct passes through a smoke-tight division, a smoke damper shall not be fitted at the penetration unless the duct which passes through the space does not serve that space.

8.6 Where ventilation systems penetrate decks, the arrangements shall be such that the effectiveness of the deck in resisting fire is not thereby impaired and precautions should be taken to reduce the likelihood of smoke and hot gases passing from one deck to another.

Table 20.1 Structural fire protection times for separating bulkheads and decks [min]

One side other side		Classification of space use					
		A	B	C	D	E	F
Classi- fication of space use	A Areas of major fire hazard	60 (1),(2)	30 (1)	(3)	(1),(3),(4)	(3)	–
	B Areas of moderate fire hazard	60 (1),(2)	60 (1)	60 (1),(8)	60 (1)	60 (1)	60 (1),(7),(9)
	C Areas of minor fire hazard		(1),(2),(6),(10)	(3),(10)	(1),(3),(4)	(3)	–
	D Control stations		(1),(2),(6),(10)	(1),(6),(10)	60 (1)	(1),(6)	(3)
	E Evacuation stations and escape routes			(2),(3),(10)	(1),(3),(4)	(3)	(3)
	F Open spaces			(2),(3),(10)	30 (1),(8)	(3)	(3)

Explanation of the remarks:

The figures on either side of the diagonal line represent the required structural fire protection time for the protection system on the relevant side of the division. When steel construction is used and two different structural fire protection times are required for a division in the Table, only the greater one need to be applied.

- (1) The upper side of the decks of spaces protected by fixed fire-extinguishing systems need not be insulated.
- (2) Where adjacent spaces are in the same alphabetical category and a note 2 appears, a bulkhead or deck between such spaces need not be fitted if deemed unnecessary by national regulations. For example, a bulkhead need not be required between two store-rooms. A bulkhead is, however, required between a machinery space and a special category space even though both spaces are in the same category.
- (3) No structural fire protection requirements; however smoke-tight division made of non-combustible or fire-restricting material is required.
- (4) Control stations which are also auxiliary machinery spaces shall be provided with 30 min structural fire protection.
- (5) There are no special requirements for material or integrity of boundaries where only a dash appears in the Table.
- (6) The fire protection time is 0 min and the time for prevention of passage of smoke and flame is 30 min as determined by the first 30 min of the standard fire test.
- (7) Fire-resisting divisions need not comply with A.2.1.6.5.
- (8) Fire-resisting divisions adjacent to void spaces need not comply with A.2.1.6.5.
- (9) The fire protection time may be reduced to 0 min for those parts of open ro-ro spaces which are not essential parts of ship's main load-carrying structure, where the crew need not have access to them during any emergency.
- (10) Smoke tightness is not required if the divisions separate corridors, accommodation spaces or isolated lockers and small store-rooms in accommodation areas (lockers or store-rooms having areas less than 4m² and no flammable liquids inside) from each other.

8.7 All dampers fitted on fire-resisting or smoke-tight divisions shall also be capable of being manually closed from each accessible side of the division in which they are fitted, except of those dampers fitted on ducts serving spaces not normally manned such as stores and toilets that may be manually operated only from outside the served spaces. All dampers shall be capable of being remotely closed.

8.8 Duct material

Ducts shall be made of non-combustible or fire-restricting material. Short ducts, however, may be of combustible materials subject to the following conditions:

- Their cross section does not exceed 0,02 m².
- Their length does not exceed 2 m.
- They may only be used at the terminal end of the ventilation system.
- They shall not be situated less than 600 mm from an opening in a fire-resisting division.
- Their surfaces have low flame spread characteristics.

9. Fire detection system

9.1 Notwithstanding the provisions of Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, C., the subsequent requirements apply unless hull, superstructures, structural bulkheads, decks and deckhouses are constructed of steel or equivalent material and all divisions, ceilings, linings and insulation are made from approved non-combustible materials.

9.2 Areas of major and moderate fire hazard and other enclosed spaces not regularly occupied within accommodation and service space areas, such as cabins, store rooms, toilets, stairway enclosures, corridors and escape routes shall be provided with an approved automatic smoke detection system and manually operated call points complying with the requirements of Chapter 105 - Electrical Installations, Section 9 to indicate at the control station the location of

the outbreak of a fire in all normal operating conditions of the installations. Detectors operated by heat instead of smoke may be installed in galleys. Manually operated call points shall be installed throughout accommodation, corridors and stairway enclosures, service spaces and where necessary control stations. One manually operated call point shall be located at each exit from these spaces and from areas of major fire hazard.

10. Fixed sprinkler system

10.1 Accommodation where sleeping berths are provided, having a total deck area greater than 50 m² (including corridors serving such accommodation), shall be protected by an automatic sprinkler, fire detection and fire alarm system based on approved standards.

10.2 Plans of the system shall be displayed at each operating station. Suitable arrangements shall be made for the drainage of water discharged when the system is activated.

11. Protection of Special Category Spaces and Ro-Ro Spaces

11.1 Structural protection

11.1.1 Boundaries of special category spaces shall be insulated in accordance with Table 20.1. The standing deck of a special category space need only be insulated on the underside if required.

11.1.2 Indicators shall be provided on the navigating bridge or ship control station which should indicate when any door leading to or from the special category space or ro-ro space is closed.

11.1.3 Fire doors in boundaries of special category spaces leading to spaces below the vehicle deck shall be arranged with coamings of a height of at least 100 mm.

11.2 Further requirements

Further requirements apart from the structural fire protection are defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9.

12. Requirements for Flight Decks and Hangars**12.1 Flight deck structure**

12.1.1 In general, the construction of the flight deck shall be of steel or other equivalent material, see also Section 8. If the flight deck forms the deck head of a deckhouse or superstructure it shall be insulated according to an approved 60 minutes fire protection standard.

12.1.2 If **BCS** permits aluminium or other low melting point metal construction that is not made equivalent to steel, the following provisions shall be satisfied.

12.1.3 If the flight deck is cantilevered over the side of the ship after each fire on the ship or on the flight deck, the flight deck shall undergo a structural analysis to determine its suitability for further use.

12.2 If the flight deck is located above a ship's deckhouse or similar structure, the following conditions shall be satisfied:

- The deckhouse top and bulkheads under the flight deck shall have no openings
- Windows under the flight deck shall be provided with steel shutters

- After each fire on the flight deck or in close proximity, the flight deck shall undergo a structural analysis to determine its suitability for further use

12.3 Drainage facilities in way of flight decks shall be constructed of steel and shall lead directly over board, independent of any other system and shall be designed so that drainage does not fall onto any part of the ship.

12.4 Flight decks shall be provided with both, a main and an emergency means of escape and access for fire fighting and rescue personnel. These shall be located as far apart from each other as is practicable and preferably on opposite sides of the flight deck.

12.5 The different parts of the hangar deck have to be divided by bulkheads with big revolving or sliding doors, but at least with movable fire curtains. The details for such arrangements will be discussed and agreed for every particular case, see also the **BCS** Rules for Ship Operation Installations and Auxiliary Systems, Section 9.

12.6 Further requirements

All necessary requirements for carefully selected equipment and for fire fighting measures on the flight deck and in hangars as well as for aircraft refuelling are defined in Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, I. and in Section 8.

SECTION 21**RESIDUAL STRENGTH**

	Page
A. General	21-2
1. Definition	
2. Class Notation	
3. Damage stability	
4. Damaged structures	
B. Requirements for Residual Strength	21-2
1. Partial safety factors	
2. Plating	
3. Stiffeners and girders	
4. Proof of overall residual strength	
5. Materials	
C. Measures to Improve Residual Strength	21-4
1. General	
2. Longitudinal box girders	
3. Special stringers	
4. Reinforced bulkheads	

A. General

1. Definition

Residual strength is the remaining global strength capacity of the hull structure after damage due to military effects.

In general, the approval of the residual strength is not part of classification process.

On request, the buckling and yield capacities of the undamaged remaining components can be approved by **BCS**, if the character and extent of damage for

2. Class Notation

If the strength capacity of the remaining intact hull components is sufficient to allow the naval ship to perform tasks as defined by the Naval Authority, the Class Notation **RSM** for residual strength due to military effects can be assigned. See also Chapter 101 - Classification and Surveys (Naval Ship Rules), Section 2, C.

3. Damage stability

Ships with Class Notation **RSM** have also to proof satisfactory damage stability under the assumption of exactly the same conditions on which the residual strength calculations are based, see Section 2.

4. Damaged structures

The damaged structures have to be defined by the Naval Authority.

Note

*If the Naval Authority is not in the position to define the effects of the explosion of a missile or bullet in a watertight compartment or superstructure, **BCS** and its experienced partners would be able to evaluate on special request the resulting damage to the structure as well as to machinery systems and electrical installations.*

B. Requirements for Residual Strength

For ships with Class Notation **RSM** the following requirements for the remaining intact components are to be applied. These requirements are minimum requirements and may be extended by the Naval Authority or the shipyard.

1. Partial safety factors

For the requirements in this Section, the following Partial Safety Factors have to be applied:

	Local requirements (acc.to 1 and 2)	Overall residual strength (acc. to 3)
γ_m	1,1	1,2
γ_{fstat}	-	1,0
γ_{fdyn}	-	1,1

2. Plating

2.1 Plane plate fields

The plate thickness of structural members under compression shall not be less than:

$$t = c \cdot b \sqrt{\frac{R_m}{E} \cdot \gamma_m} + t_K \quad [\text{mm}]$$

$c = 0,78$ for plate panels with support at all sides

$= 1,62$ for plate panels with one unsupported side

b = Spacing of the loaded side of the plate [mm]

t_K = Corrosion addition [mm] according to Section 4, B.3.

2.2 Curved plate fields

The plate thickness of structural members under compression shall not be less than:

$$t = \frac{0,044 \cdot r \cdot R_m \cdot \gamma_m}{E} + t_K \quad [\text{mm}]$$

For large radii the thickness t between 2 stiffeners need not be more than the thickness according to 2.1

r = Radius of plate curvature [mm]

3. Stiffeners and girders

3.1 Lateral buckling

The following condition has to be met for structural members under compression:

$$\frac{I}{A} \geq c \cdot \frac{R_m}{E} \cdot \gamma_m \cdot \ell^2 \quad [\text{cm}^2]$$

I = Moment of inertia [cm⁴] of the stiffener including adjacent plate or of the column

A = Area [cm²] of the stiffener including adjacent plate or of the column

c = 0,022 for stiffeners or simply supported columns

= 0,011 for elastically restraint columns

ℓ = Unsupported span [m]

3.2 Secondary stiffeners

The length ℓ of stiffeners should not be larger than $12 \cdot h$, where h is the height of the stiffener.

3.3 Primary members acting as columns

The length ℓ of primary members forming buckling resistant columns should be the distance between two watertight bulkheads. Primary members not forming box girders have to be secured against torsional buckling. These members are to be carefully connected to their transverse supporting members.

4. Proof of overall residual strength

4.1 The bending moments and shear forces in damaged condition are to be applied to a cross section formed by those structures which are considered to remain intact in damaged condition, see Section 6, B.3.

All other parts of the hull cross section are assumed to be destroyed or lost. If more than one member/column is forming the residual hull cross section, effects of second order have to be considered.

4.2 For non-linear calculations (ultimate load/ultimate strength) the following conditions shall be satisfied:

- vertical bending and shear

$$|\gamma_{fstat} \cdot M_{SWf} + \gamma_{fdyn} \cdot M_{WVf}| \leq |M_{Uf} / \gamma_m|$$

$$|\gamma_{fstat} \cdot Q_{SWf} + \gamma_{fdyn} \cdot Q_{WVf}| \leq |Q_{Uf} / \gamma_m|$$

- horizontal bending and shear

$$|\gamma_{fdyn} \cdot M_{WHf}| \leq |M_{UHf} / \gamma_m|$$

$$|\gamma_{fdyn} \cdot Q_{WHf}| \leq |Q_{UHf} / \gamma_m|$$

M_{Uf} = Bending capacity [MNm] of the cross section formed by the members relevant for residual strength according to Section 6, D.3. around the horizontal axis in the hogging ($M_{Uf,H}$) and sagging ($M_{Uf,S}$) condition, respectively.

M_{UHf} = Bending capacity [MNm] of the cross section formed by the members relevant for residual strength according to Section 6, D.3. around the vertical axis.

Q_{Uf} = Shear capacity [MN] of the cross section formed by the members relevant for residual strength in vertical direction according to Section 6, D.3.

Q_{UHf} = Shear capacity [MN] of the cross section formed by the members relevant for residual strength in horizontal direction according to Section 6, D.3.

M_{SWf} = Vertical still water bending moment [MNm] in damaged condition according to Section 6.

Q_{SWf} = Vertical still water shear force [MN] in damaged condition according to Section 6.

M_{WVf} = Vertical wave bending moment [MNm] in damaged condition according to Section 6.

Q_{WVf} = Vertical wave shear force [MN] in damaged condition according to Section 6.

M_{WHf} = Horizontal wave bending moment [MNm] in damaged condition according to Section 6.

Q_{WHf} = Horizontal wave shear force [MN] in damaged condition according to Section 6.

5. Materials

5.1 Materials of elements which are relevant for residual strength are not to be of lower class than III as defined in Section 3, Table 3.3.

5.2 If strength members relevant for residual strength are made of aluminium, these members shall be insulated with a material ensuring a fire protection time of at least 60 minutes, see also Section 20.

C. Measures to Improve Residual Strength

1. General

Herein some possible measures to improve residual strength are described. Depending on the type of naval ship additional or other measures may be applied.

These measures have to be agreed with the Naval Authority case by case.

2. Longitudinal box girders

It is recommended to provide several longitudinal box girders immediately below the weather deck and at the bottom of the hull, see details A, B and D in Figure 21.1. The box girders can be used as cable channels to safeguard power and communication.

3. Special stringers

Reinforced longitudinal stringers are recommended in the lower range of the side shell above the double bottom, see Figure 21.1, detail C.

4. Reinforced bulkheads

For limitation of blast effects due to inboard missile explosion and the related destruction area and improving the splinter protection for crew and equipment bulkheads with improved steadfastness are recommended.

Attention should be paid on sufficient rotational flexibility at the bulkhead boundaries in case of double plate bulkheads.

Penetrations for cables and pipes shall not impair the global strength of the bulkhead.




Figure 21.1 Example for longitudinal box girders and special stringers

SECTION 22

AMPHIBIOUS WARFARE SHIPS

	Page
A. General	22-2
1. Validity	
2. Scope	
B. Bow Doors and Inner Doors	22-2
1. General, definitions	
2. Strength criteria	
3. Design loads	
4. Scantlings of bow doors	
5. Scantlings of inner doors	
6. Securing and supporting of bow doors	
7. Arrangement of securing and locking devices	
8. Operating and maintenance manual	
C. Side Shell Doors and Stern Doors	22-8
1. General	
2. Arrangement	
3. Strength criteria	
4. Design loads	
5. Scantlings	
6. Securing and supporting of side shell and stern doors	
7. Arrangement of securing and locking devices	
8. Operating and maintenance manual	
D. Well Dock	22-10
1. Steel structure	
2. Water management	
3. Stability	
4. Dock outfit	
5. Operating and maintenance manual	
E. References to Further Requirements for Amphibious Warfare	22-13

A. General**1. Validity**

The requirements given in all other Sections apply unless stated otherwise in this Section.

2. Scope

The requirements in this Section may be applied to all types of amphibious warfare ships, like Amphibious Assault Ship (LHD), Dock Landing Ship (LSD), Tank Landing Ship (LST) and Infantry Landing Craft (LCI). The flight operation aspects of the two first types are treated in Section 23.

B. Bow Doors and Inner Doors**1. General, definitions****1.1 Applicability**

1.1.1 These requirements apply to the arrangement, strength and securing of bow doors and inner doors leading to a complete or longer forward enclosed superstructure.

1.1.2 For naval ships the side-opening type of bow door may be applied.

These doors are opened either by rotating outwards about a vertical axis through two or more hinges located near the outboard edges or by horizontal translation by means of linking arms arranged with pivoted attachments to the door and the ship. It is anticipated that side-opening bow doors are arranged in pairs.

1.1.3 Other types of bow doors will be specially considered in association with the applicable requirements of these Rules.

1.2 Arrangement

1.2.1 Bow doors are to be situated above the freeboard deck. A watertight recess in the freeboard deck located forward of the collision bulkhead and above the deepest waterline fitted for arrangement of ramps

or other related mechanical devices, may be regarded as a part of the freeboard deck for the purpose of this requirement.

1.2.2 An inner door is to be provided. The inner door is to be part of the collision bulkhead. The inner door needs not be fitted directly above the collision bulkhead below, provided it is located within the limits specified in Section 2, C.2.3 for the position of the collision bulkhead. A vehicle ramp may be arranged for this purpose, provided its position complies with Section 2, C.2.3. If this is not possible, a separate inner weathertight door is to be installed, as far as practicable within the limits specified for the position of the collision bulkhead.

1.2.3 Bow doors are to be so fitted as to ensure tightness consistent with operational conditions and to give effective protection to inner doors. Inner doors forming part of the collision bulkhead are to be weathertight over the full height of the space for military vehicles/cargo and arranged with fixed sealing supports on the aft side of the doors.

1.2.4 Bow doors and inner doors are to be so arranged as to preclude the possibility of the bow door causing structural damage to the inner door or to the collision bulkhead in the case of damage to or detachment of the bow door. If this is not possible, a separate inner weathertight door is to be installed, as indicated in 1.2.2.

1.2.5 The requirements for inner doors are based on the assumption that the vehicles are effectively lashed and secured against movement in stowed position.

1.3 Definitions**1.3.1 Securing device**

Securing device is a device used to keep the door closed by preventing it from rotating about its hinges.

1.3.2 Supporting device

Supporting device is a device used to transmit external or internal loads from the door to a securing device and from the securing device to the ship's structure, or a

device other than a securing device, such as a hinge, stopper or other fixed device, that transmits loads from the door to the ship's structure.

1.3.3 Locking device

Locking device is a device that locks a securing device in the closed position.

2. Strength criteria

2.1 Primary structure and securing and supporting devices

2.1.1 Scantlings of the primary members, securing and supporting devices of bow doors and inner doors are to be designed such as the shell structure defined in Section 7 using design loads defined in 3.

2.1.2 The buckling strength of primary members is to be verified according to Section 4, F.

2.1.3 For steel to steel bearings in securing and supporting devices, the nominal bearing pressure calculated by dividing the design force by the projected bearing area is not to exceed $0,8 \cdot R_{eH}$, where R_{eH} is the yield stress of the bearing material. For other bearing materials, the permissible bearing pressure is to be determined according to the manufacturer's specification.

2.1.4 The arrangement of securing and supporting devices is to be such that threaded bolts do not carry support forces. The maximum tension stress in way of threads of bolts not carrying support forces is not to exceed $0,5 \cdot R_{eH}$ [N/mm²].

3. Design loads

3.1 Bow doors

3.1.1 The external design pressure to be

considered for the scantlings of primary members of bow doors is the pressure p_{SL} specified in Section 5, C.2. The relevant flare and entry angles are defined in Figure 22.1.

3.1.2 The design external forces for determining scantlings of securing and supporting devices of bow doors are not to be less than:

$$F_x = p_{SL} \cdot A_x \text{ [kN]}$$

$$F_y = p_{SL} \cdot A_y \text{ [kN]}$$

$$F_z = p_{SL} \cdot A_z \text{ [kN]}$$

A_x = area [m²] of the transverse vertical projection of the door between the levels of the bottom of the door and the upper deck or between the bottom of the door and the top of the door, whichever is the lesser

A_y = area [m²] of the longitudinal vertical projection of the door between the levels of the bottom of the door and the upper deck or between the bottom of the door and the top of the door, whichever is the lesser




Figure 22.1 Definition of height and length of bow doors

A_z = area [m²] of the horizontal projection of the door between the levels of the bottom of the door and the upper deck or between the bottom of the door and the top of the door, whichever is the lesser

for A_x , A_y and A_z see also Figure 22.2.

h = height [m] of the door between the levels of the bottom of the door and the upper deck or between the bottom of the door and the top of the door, whichever is the lesser

ℓ = length [m] of the door at a height $h/2$ above the bottom of the door

3.1.3 For bow doors, including bulwark, of unusual form or proportions, e.g. ships with a rounded nose and large stem angles, the areas and angles used for determination of the design values of external forces may require to be specially considered.

3.1.4 For side-opening doors the closing moment M_z under external loads is to be taken as:

$$M_z = F_x \cdot a + F_y \cdot b \text{ [kNm]}$$

a = horizontal distance [m] from door pivot axle to the centroid of the transverse vertical projected area A_x of one leave of the door, as shown in Figure 22.2

b = horizontal distance from door pivot axle to the centroid of the longitudinal vertical projected area A_y of one leave of the door, as shown in Figure 22.2

3.1.5 Between the upper and the lower pivot an additional moment has to be absorbed:

$$M_y = F_z \cdot c - 10 \cdot W \cdot d \text{ [kNm]}$$

c = horizontal distance [m] from door pivot axle to the centroid of the horizontal projected area A_z of one leave of the door, as shown in Figure 22.2

W = mass of one door leave [t]

d = horizontal distance from the door pivot to the centre of gravity of leave mass [m], as shown in Figure 22.2




Figure 22.2 Areas, centres and forces at side-opening bow doors

3.2 Inner doors

3.2.1 The external design pressure p_e considered for the scantlings of primary members, securing and supporting devices and surrounding structure of inner doors is to be taken as the greater of the following:

$$p_e = 0,45 \cdot L1 \left[\text{kN/m}^2 \right] \text{ or } \\ = 10 \cdot h \left[\text{kN/m}^2 \right]$$

$$L1 = L \text{ [m]}, \text{ but } \leq 200 \text{ m}$$

h = distance [m] from the load point to the top of the cargo space

3.2.2 The design internal pressure p_i considered for the scantlings of securing devices of inner doors is not to be less than:

$$p_i = 25 \text{ kN/m}^2$$

4. Scantlings of bow doors

4.1 General

4.1.1 The strength of bow doors is to be commensurate with that of the surrounding structure.

4.1.2 Bow doors are to be adequately stiffened and means are to be provided to prevent lateral or vertical movement of the doors when closed.

4.2 Plating and secondary stiffeners

4.2.1 The thickness of the bow door plating is not to be less than the side shell thickness according to Section 7, using bow door stiffener spacing, but in no case less than the required minimum thickness of the plating according to Section 4, Table 4.3.

4.2.2 The section modulus of horizontal or vertical stiffeners is not to be less than that required for framing at the position of the door according to Section 7. Consideration is to be given, where necessary, to differences in fixity between ship's frames and bow doors stiffeners.

4.3 Primary structure

4.3.1 The bow door secondary stiffeners are to be supported by primary members constituting the main stiffening of the door.

4.3.2 The primary members of the bow door and the hull structure in way are to have sufficient stiffness to ensure integrity of the boundary support of the door.

4.3.3 Scantlings of the primary members are generally to be verified by direct calculations in association with the external design pressure as referenced in 3.1.1 and design procedure defined in

2.1.1. Normally, formulae for simple beam theory may be applied.

5. Scantlings of inner doors

5.1 General

5.1.1 For determining scantlings of the primary members the requirements of 4.3.3 apply in conjunction with the loads specified in 3.2.

5.1.2 Where inner doors also serve as vehicle ramps, the scantlings are not to be less than those required for vehicle decks as per Section 4, B.4.3.

5.1.3 The distribution of the forces acting on the securing and supporting devices is generally to be verified by direct calculations taking into account the flexibility of the structure and the actual position and stiffness of the supports.

6. Securing and supporting of bow doors

6.1 General

6.1.1 Bow doors are to be fitted with adequate means of securing and supporting so as to be commensurate with the strength and stiffness of the surrounding structure. The hull supporting structure in way of the bow doors is to be suitable for the same design loads and design stresses as the securing and supporting devices. Where packing is required, the packing material is to be of a comparatively soft type, and the supporting forces are to be carried by the steel structure only. Other types of packing may be considered. The maximum design clearance between securing and supporting devices is generally not to exceed 3 mm.

A means is to be provided for mechanically fixing the door in the open position.

6.1.2 Only the active supporting and securing devices having an effective stiffness in the relevant direction are to be included and considered to calculate the reaction forces acting on the devices. Small and/or flexible devices such as cleats intended to provide load compression of the packing material are not generally to be included in the calculations called for in 6.2.4.

The number of securing and supporting devices is generally to be the minimum practical whilst taking into account the redundancy requirements given in 6.2.5 and the available space for adequate support in the hull structure.

6.2 Scantlings

6.2.1 Securing and supporting devices are to be adequately designed so that they can withstand the reaction forces according to the design procedure defined in 2.1.1.

6.2.2 For side-opening doors the reaction forces applied on the effective securing and supporting devices assuming the door as a rigid body are determined for the following combination of external loads acting simultaneously together with the self weight of the door:

6.2.2.1 Case 1: F_x , F_y and F_z acting on both doors

6.2.2.2 Case 2: $0,7 \cdot F_x$ and $0,7 \cdot F_z$ acting on both doors and $0,7 \cdot F_y$ acting on each door separately.

The forces F_x , F_y and F_z are to be determined as indicated in 3.1.2 and applied at the centroid of the projected areas.

6.2.3 The support forces as determined according to 6.2.2 shall generally result in a zero moment about the transverse axis through the centroid of the area A_x .

6.2.4 The distribution of the reaction forces acting on the securing and supporting devices may require to be verified by direct calculations taking into account the flexibility of the hull structure and the actual position and stiffness of the supports. This is, for instance, the case when the bow door is supported statically undetermined.

6.2.5 The arrangement of securing and supporting devices in way of these securing devices is to be designed with redundancy so that in the event of failure of any single securing or supporting device the remaining devices are capable of withstanding the reaction forces without exceeding by more than 20 per cent the permissible stresses.

6.2.6 All load transmitting elements in the design load path, from door through securing and supporting devices into the ship structure, including welded connections, are to be of the same strength standard as required for the securing and supporting devices.

6.2.7 For side-opening doors, thrust bearings are to be provided in way of girder ends at the closing of the two leaves to prevent one leaf to shift towards the other one under effect of unsymmetrical pressure. An example for a thrust bearing is shown in Figure 22.3. Securing devices are to be provided so that each part of the thrust bearing can be kept secured on the other part. Any other arrangement serving the same purpose may be accepted.




Figure 22.3 Thrust bearing for doors

7. Arrangement of securing and locking devices

7.1 Systems for operation

7.1.1 Securing devices are to be simple to operate and easily accessible.

Securing devices are to be equipped with mechanical locking arrangement, e.g. self locking or separate arrangement, or to be of the gravity type. The opening and closing systems as well as securing and locking devices are to be interlocked in such a way that they can only operate in the proper sequence.

7.1.2 Bow doors and inner doors giving access to vehicle decks are to be provided with an arrangement for remote control, from a position above the free-board deck of:

- The closing and opening of the doors
- Associated securing and locking devices for every door

Indication of the open/closed position of every securing and locking device is to be provided at the remote control stations. The operating panels for operation of doors are to be inaccessible to unauthorized persons. A notice plate, giving instructions to the effect that all securing devices are to be closed and locked before leaving harbour, is to be placed at each operating panel and is to be supplemented by warning indicator lights.

7.1.3 Where hydraulic securing devices are applied, the system is to be mechanically lockable in closed position. This means that, in the event of loss of the hydraulic fluid, the securing devices remain locked.

The hydraulic system for securing and locking devices is to be isolated from other hydraulic circuits, when in closed position.

7.2 Systems for indication/monitoring

The requirements according 7.2.3 - 7.2.6 are optional and have to be agreed between Naval Authority and BCS.

7.2.1 Separate indicator lights are to be provided on the navigation bridge and on the operating panel to show that the bow door and inner door are closed and that their securing and locking devices are properly positioned. Deviations from the correct closing state are to be indicated by acoustic and visual alarms. The indication panel is to be provided with a lamp test function. It shall not be possible to turn off the indicator lights.

7.2.2 The indicator system is to be designed on the self-monitoring principle and is to be alarmed by visual and audible means if the door is not fully closed and not fully locked or if securing devices become open or locking devices become unsecured. The power supply for the indicator system is to be independent of the power supply for operating and closing doors. The sensors of the indicator system are to be protected from

water, icing and mechanical damages. Degree of protection: at least IP 56.

7.2.3 The indication panel on the navigation bridge is to be equipped with a selector switch "harbour/sea voyage", so arranged that alarm is given if the ship leaves harbour with the bow door or inner door not closed and with any of the securing devices not in the correct position.

7.2.4 A water leakage detection system with audible alarm and television surveillance is to be arranged to provide an indication to the navigation bridge and to the machinery control centre resp. damage control centre of leakage through the inner door.

7.2.5 For the space between the bow door and the inner door a television surveillance system is to be fitted with a monitor on the navigation bridge and in the machinery control centre resp. damage control centre. The system must monitor the position of doors and a sufficient number of their securing devices. Special consideration is to be given for lighting and contrasting colour of objects under surveillance.

7.2.6 A drainage system is to be arranged in the area between bow doors and ramp, as well as in the area between the ramp and inner door where fitted. The system is to be equipped with an acoustic alarm function to the navigation bridge for water level in these areas exceeding 0,5 m above the vehicle deck level.

7.2.7 For indication and monitoring systems see also Chapter 105 - Electrical Installations, Section 9, D.

8. Operating and maintenance manual

8.1 For all types of amphibious warfare ships with bow doors except of the Landing Ship Infantry (LSI) type with limited size the following procedures have to be applied.

8.2 An operating and maintenance manual for the bow door and inner door has to be provided on board and contain necessary information on:

- Description of the door system and design drawings

- Service conditions, e.g. service restrictions, emergency operations, acceptable clearances for supports
- Maintenance and function testing
- Register of inspections and repairs

This manual has to be presented at the periodical surveys to **BCS** for approval.

Note:

It is recommended that inspections of the door supporting and securing devices be carried out by the ship's staff at monthly intervals and/or following incidents that could result in damage, including heavy weather and/or contact in the region of the shell doors.

8.3 Documented operating procedures for closing and securing the bow door and inner doors are to be kept on board and posted at an appropriate place.

C. Side Shell Doors and Stern Doors

1. General

1.1 These requirements apply to side shell doors abaft the collision bulkhead and to stern doors leading into enclosed spaces.

The requirements for doors leading to spaces of limited size will be specified case by case by **BCS**, especially with regard to the provision of an operating and maintenance manual.

1.2 For the definition of securing, supporting and locking devices see B. 1.3.

2. Arrangement

2.1 Stern doors and side shell doors of landing ships, helicopter carriers, etc. may be either below or above the freeboard deck.

2.2 Side shell doors and stern doors are to be so fitted as to ensure tightness and structural

integrity commensurate with their location and the surrounding structure.

2.3 Where the sill of any side shell door is below the uppermost load line, the arrangement is to be specially considered. In case of ice strengthening see Section 13.

2.4 Doors should preferably open outwards.

3. Strength criteria

The requirements of B.2. apply.

4. Design loads

The design forces considered for the scantlings of primary members, securing and supporting devices of side shell doors and stern doors are to be not less than the greater of the following values:

4.1 Design forces for securing or supporting devices of doors opening inwards:

$$\text{external force: } F_e = A \cdot p_s + F_p \quad [\text{kN}]$$

$$\text{internal force: } F_i = F_o + 10 \cdot W \quad [\text{kN}]$$

4.2 Design forces for securing or supporting devices of doors opening outwards:

$$\text{external force: } F_e = A \cdot p_s \quad [\text{kN}]$$

$$\text{internal force: } F_i = F_o + 10 \cdot W + F_p \quad [\text{kN}]$$

4.3 Design forces for primary members: external force:

$$\text{external force: } F_e = A \cdot p_s \quad [\text{kN}]$$

$$\text{internal force: } F_i = F_o + 10 \cdot W \quad [\text{kN}]$$

A = Area of the door opening [m²]

W = Mass of the door [t]

F_p = Total packing force [kN], where the packing line pressure is normally not to be taken less than 5 N/mm

F_o = The greater of F_c or $5 \cdot A$ [kN]

F_c = Accidental force [kN] due to loosened cargo/vehicles etc., to be uniformly distributed over the area A and not to be taken less than 300 kN. For small doors such as bunker doors and pilot doors, the value of F_c may be appropriately reduced.

However, the value of F_c may be taken as zero, provided an additional structure such as an inner ramp is fitted, which is capable of protecting the door from accidental forces due to loosened cargo/vehicles.

p_s = External design pressure for the ship's side according to Section 5, C.1. is to be determined at the centre of gravity of the door opening with height h_G above base line [m]. $p_{s\text{dyn}}$ is not to be less than 25 [kN/m²]

h_G = height of centre of area [m].

5. Scantlings

5.1 General

The requirements of B.4.1 apply analogously with the following additions:

- Where doors also serve as vehicle ramps, the design of the hinges shall take into account the ship's angle of trim and heel which may result in uneven loading on the hinges.
- Shell door openings are to have well-rounded corners and adequate compensation is to be arranged with web frames and stringers or equivalent above and below.

5.2 Plating and secondary stiffeners

The requirements of B.4.2.1 and B.4.2.2 apply analogously with the following additions:

Where doors serve as vehicle ramps, plate thickness and stiffener scantlings are to comply with the requirements of Section 4, B.4.3.

5.3 Primary structure

The requirements of B.4.3 apply analogously taking into account the design loads specified in 4.

6. Securing and supporting of side shell and stern doors

6.1 General

The requirements of B.6.1.1 and B.6.1.2 apply analogously.

6.2 Scantlings

The requirements of B.6.2.1, B.6.2.4, B.6.2.5 and B.6.2.6 apply analogously taking into account the design loads specified in 4.

7. Arrangement of securing and locking devices

7.1 Systems for operation

7.1.1 The requirements of B.7.1.1 apply.

7.1.2 Doors which are located partly or totally below the freeboard deck with a clear opening area greater than 6 m² are to be provided with an arrangement for remote control, from a position above the freeboard deck according to B.7.1.2.

7.1.3 The requirements of B.7.1.3 apply.

7.2 Systems for indication/monitoring

7.2.1 The requirements of B.7.2.1, B.7.2.2 and B.7.2.3 apply analogously to doors leading directly to special category spaces or ro-ro spaces, as defined in Section 20, A.2.2, through which such spaces may be flooded.

7.2.2 As an option to be agreed between the Naval Authority and **BCS**, a water leakage system with audible alarm and television may be arranged to provide an navigation bridge and to the resp . damage control the doors.

8. Operating and maintenance manual

The requirements of B.8. apply analogously.

D. Well Dock

If for the ship types Landing Ship Dock Helicopter and Landing Ship Dock a well dock is provided at the rear part of the ship with the aim to harbour landing craft, the following requirements have to be met.

1. Steel structure

1.1 The complete dock must be enclosed by a watertight bottom and watertight walls up to the bulk-head deck.

1.2 Load cases

The following load cases have to be considered:

1.2.1 Seagoing condition

For this condition it is assumed that the stern door is closed and no water is in the dock. The following loads are acting on the steel structure:

- Static load from the weight of the landing craft on the bottom of the dock

- Dynamic load from the weight of the landing craft according to the vertical acceleration component a_z of the ship according to Section 5, B.
- If military vehicles/materials are transported instead of landing craft, loads on internal decks according to Section 5, G.
- Lashing forces for landing craft or vehicles created by the transverse and longitudinal acceleration components of the ship according to Section 5, B. acting on planned lashing points to be defined in the Operating Manual, see 6.

- External sea pressure according to Section 5, C.1.

1.2.2 Dock operation

For this condition it is assumed that the ship is trimmed (if applicable), the stern door is open and the dock filled with water. It has to be defined in the Operating Manual (see 6.) up to which maximum ship speed and seaway condition dock operations shall take place. The following loads are to be applied:

- Static load p_{stat} from the water filling according to Section 5, C.1. and dynamic load p_{dyn} from the water in the dock accelerated by the motions of the ship, see Section 5, B.
- Local impact forces especially to the side walls due to landing craft manoeuvres, the size of these forces have to be agreed between Naval Authority, shipyard and **BCS**. See also Section 7, F.
- Mooring loads from the landing craft afloat in the dock, the size of these forces have to be agreed between Naval Authority, shipyard and **BCS**.
- Dynamic loads due to motion/acceleration of the ship must be taken into account in case the stern door is hinged about a horizontal axis below the sea surface

1.3 Scantlings

1.3.1 The design of the ship and its landing craft shall ensure that point loads on the dock bottom do not occur.

1.3.2 The thickness of the dock bottom shall be increased by 2 mm if vehicles and/or material shall be transported and no ceiling system is provided, see 5.

1.3.3 The formulae defined in Section 7 and Section 4 have to be applied for determining the actual dimensions.

1.4 Stern door

For the stern door at the rear end of the dock the following design features are to be complied with:

1.4.1 Principally shall the stern door close the complete opening watertight.

1.4.2 If in exceptional cases the door does not close the complete opening watertight and at the upper range a limited area remains open, additional considerations and measures concerning buoyancy and stability have to be agreed with **BCS**

In any way shall the bilge system in the dock be able to remove quickly any splash water from the seaway, see Rules for Ship Operation Installations and Systems, Section 8, N.

1.4.3 The basic requirements defined in C. are valid in analogous way. In addition the loads defined in 1.2.2 have to be considered.

1.4.4 A leakage detection system is to be installed.

1.4.5 Open or closed and secured condition is to be indicated locally and at the bridge. The use of the door shall be authorised by the officer of the watch.

1.5 Access doors to internal ship spaces

For doors from the well dock to internal spaces of the ship, the following design features are to be complied with:

1.5.1 Doors below the equilibrium or intermediate water plane due to an assumed damage shall be watertight bulkhead doors according to Section 9, A. Their doorway sill height shall be 600 mm and they shall be closed at sea and/or if the dock is flooded.

Open or closed and secured condition is to be indicated locally and at the bridge. The use of these doors shall be authorised by the officer of the watch.

1.5.2 Doors above the equilibrium or intermediate water plane due to an assumed damage shall be weathertight doors with a sill height of at least 380 mm.

1.5.3 **BCS** may accept lesser heights of sills if alternative solutions with equivalent level of safety are provided and recognized. Such an alternative solution would be e.g. the arrangement of a lock of moderate size behind the outside door.

2. Water management

2.1 A system has to be provided to fill and empty the dock within the time defined in the building specification. For this operation two independent pumping systems have to be provided. The drain wells in the dock have to be arranged at the forward and rear end as well as on port and starboard in a way that the complete emptying of the dock also at extreme trim situations of the ship can be guaranteed. The system has to meet the requirements defined in Chapter 107 – Ship Operation Installations and Auxiliary Systems, Section 2, D.2. for a ballast system for special tasks.

The flooding system must automatically activate a visual and audible flooding alarm in the complete dock area at a reasonable time before flooding starts to enable all personnel to leave the bottom of the dock and to warn the personnel of the landing craft.

2.2 Depending on the level of the well deck in the ship, a ballast system to achieve a stern trim for undisturbed landing craft traffic through the open stern door has to be provided, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8, P.

3. Stability

Sufficient stability has to be proven for dock operations during intermediate stages of embarkation and disembarkation of landing craft, see Section 2.

4. Dock outfit

To enable a safe operation of the dock the following outfit has to be provided:

- Protection of the dock bottom by a ceiling system if the thickness of the bottom plating is not increased and the dock shall also be used for transport of vehicles and materials, see also Section 19, C.2.
- Protection of the side walls by a permanently mounted fender system which has to be effective for the different water levels in the dock
- A mooring system to secure the planned position of the landing craft within the dock in all operating conditions with and without water; this system has to be arranged at a side walkway of the dock or in recesses of the side walls and shall not interfere with the side shell of the landing craft
- A guide system to lead the landing craft in their planned position, if necessary
- An inclined ramp at the forward end of the dock shall be provided with a non-slip sheathing
- At least two ladders for escape from the well dock bottom are to be arranged as far as possible away from each other
- No electrical installations have to be provided below the waterline at the greatest draught and trim of the ship, the electrical installations above the waterline are to be considered as within protection areas, see Chapter 105 - Electrical Installations, Section 15

- Sufficient lighting to enable safe navigation and loading/unloading procedures in the dock has to be provided, see Chapter 105 - Electrical Installations, Section 11. For night operations an additional red light system is recommended

- Sufficient ventilation of the dock space with closed stern door has to be provided, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 11

5. Operating and maintenance manual

5.1 An operating and maintenance manual for trimming the ship, if applicable, operating the dock and for the doors enclosing it has to be provided on board and contain necessary information on:

- Definition of the maximum ship speed and maximum seaway condition for operation of the dock
- Necessary trimming measures for the ship, if applicable, before and after docking operations
- Description of dock and doors and design drawings
- Operational conditions, acceptable clearances, etc.
- Function and maintenance testing
- Register of inspection and repairs

The manual has to be submitted for approval.

5.2 Documented operating procedures for closing and securing the stern door are to be kept aboard and posted at an appropriate place

E. References to Further Requirements for Amphibious Warfare

Besides the requirements defined in this Section the following other elements of amphibious warfare ships are defined for:

- Ramps, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 3, G.
- Aircraft handling, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 13
- Special requirements concerning electrical equipment and installations, see Chapter 105 - Electrical Installations, Section 15.
- Cranes, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 3, B.
- Lifts, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 3, E.

SECTION 23

PROVISIONS FOR FLIGHT OPERATIONS

		Page
A.	General	23-2
	1. Scope	
	2. Class Notation	
	3. Documents for Approval	
B.	Flight Decks	23-3
	1. Basic requirements	
	2. Helicopter Winching Area	
	3. Helicopter Landing Deck	
	4. Take-Off and Landing Deck for Fixed Wing Aircraft	
	5. Flight Deck Equipment	
C.	Hangars	23-8
	1. Hangar Layout	
	2. Hangar Equipment	
D.	Provisions for Drones (UAV)	23-9
	1. General	
	2. Size of start and landing deck	
	3. Marking of the deck	
E.	References to Further Requirements for Flight Operations	23-10
	1. Strength of the decks	
	2. Treatment of fuels and oils	
	3. Fire fighting	
	4. Ventilation	
	5. Aircraft handling	

A. General

1. Scope

Additional requirements for flight operations, like special lighting systems, communication between ship and aircraft, electronic take-off and landing aids, flight control, etc. are not subject of Classification and have to be agreed directly between Naval Authority and shipyard.

The requirements given in Section 1-22 apply unless stated otherwise in this Section.

2. Class Notation

2.1 Ships which are in the position to enable starts and landings of a greater number of different aircraft may be assigned the Class Notation **FO**, see Chapter 101 - Classification and Surveys (Naval Ship), Section 2, C. Therefore in this Section the overall aspects for ships operating aircraft are summarized and references are given to other Rule Chapters and Sections, where the requirements for relevant equipment are defined.

2.2 Naval ships meeting the requirements for winching areas according to 3.3.1 and B.2. will be assigned the Class Notation **FO (HELIW)** which means "Equipped for Helicopter Winching Operations".

2.3 Naval ships meeting the requirements for helicopter landing areas according to A., B.3., B.4., B.5., C., E. (partly) will be assigned the Class Notation **FO (HELIL)** which means "Equipped with Helicopter Landing Deck".

2.4 Naval ships meeting the requirements for helicopter landing areas and helicopter refuelling according to 2.3 and **BCS** Rules for Ship

assigned the Class Notation **FO (HELILF)** which means

"Equipped with Helicopter Landing Deck and Refuelling Capabilities".

2.5 Naval ships meeting only requirements for operation of drones (unmanned aerial vehicles) according to D. will be assigned the Class Notation **FO (DRONE)** which means "Equipped with Drone Handling Capabilities".

3. Documents for Approval

3.1 General

The following data, documents and drawings are to be submitted to **BCS** for approval.

3.2 Aircraft specification

The types of aircraft to operate on the naval ship have to be specified by the Naval Authority. Normally the following parameters are needed:

- Type of aircraft
- Length and width of aircraft body
- Span of wings (folded and unfolded)
- Rotor diameter
- Maximum take-off weight
- Wheel or skid configuration including individual wheel pressures
- Special requirements for aircraft handling
- Further technical characteristics for refuelling, maintenance, etc.
- Starting and landing procedure

- Highest vertical rate of descent on the deck, e.g. because of single engine failure, etc.
- Lashing systems to be provided
- Data for winching operations, if applicable

Besides fixed wing aircraft primarily helicopters with one main rotor are considered in these Rules, for helicopters with two main rotors relevant requirements have to be specified in analogous way and agreed with the Naval Authority.

3.3 Documents and drawings for ship Infrastructure

3.3.1 Winching Area, if applicable

- Arrangement plan to show the location on the naval ship and overall size of the area
- Obstructions nearby and their height above winching area
- Plans showing the scantlings and details of the deck used as winching area

3.3.2 Aircraft landing deck, if applicable

- Arrangement plan to show the overall location and size of the deck, definition of the different deck zones (like landing, take-off, parking including planned parking mode, etc.)
- Plans showing the scantlings and details of the deck and its substructure
- Arrangement for securing of the aircraft to the deck including deck fittings and earthing
- Deck equipment, like sheathing, railings, access possibilities, etc.

3.3.3 Hangar, if applicable

- Lay out including access to the hangar from flight deck and to the superstructure of the ship
- Arrangement for securing of the aircraft to the deck including deck fittings and earthing
- Hangar equipment, like sheathing, hangar door, electrical equipment, cranes, heating and ventilation etc.
- Plans showing the scantlings and details of the deck and its substructure

3.3.4 Further shipside equipment

- Technical documentation on lighting, aviation fuel system, fire protection/fighting, etc.

B. Flight Decks

1. Basic requirements

In addition to the requirements of these Rules the national regulations defined by the Naval Authority, NATO standards, etc. have to be fulfilled.

2. Helicopter Winching Area

2.1 Task

An area defined for vertical replenishment and transfer of personnel shall only be used for the following duties:

- Transfer of personnel, injured or ill crew members, light supplies, mail, etc. using a winch in the upper part of the helicopter
- Replenishment of supplies, like provisions, ammunition, etc. from ship to ship, to/from land, using a net hanging on a (releasable) hook at the underside of the helicopter (VERTREP). In this case measures for a convenient material flow from the helicopter deck have to be established.

2.2 Positioning of the area

The area should, for operational effectiveness and safety, be located at the side, bow or stern of the ship so that a large part of the maneuvering zone can extend to outside the ship. The area should, if practicable, be positioned clear of accommodation spaces, have an adequate space and provide for safe access to the area from different directions.

The position of the operating area should enable the pilot of the helicopter hovering over the rotor clearance zone to have an unobstructed view of the ship and be in a position which will minimise the effect of air turbulence and flue gases.

2.3 Size of the area

If no other regulation is defined by the Naval Authority, the requirements of the NATO standard STANAG 1162 HOS may be applied. The replenishing/winching area for helicopter operations consists of three zones as shown in Fig. 23.1:

- Load Clearance Zone

A square area clear of all obstructions with a minimum side length of 6,2 m. This zone shall have a matt, anti-slip surface.
- Fuselage and Landing Gear Clearance Zone:

This zone reaches from board to board of the ship and extends in longitudinal direction of the ship 4,6 m fore and aft from the middle of the loading/unloading zone. Within this zone no obstructions shall be higher than 1,52 m for low hover operations respectively 4,60 m for high hover operations.
- Rotor clearance zone:

This zone reaches from board to board of the ship and extends in longitudinal direction of the ship with a length of 75 % of the rotor diameter of the biggest permissible helicopter forward and aft from the middle of the

loading/unloading zone. Within this zone no obstructions shall be higher than 4,60 m for low hover operations respectively 7,62 m for high hover operations

2.4 Marking of the area

To assist flight operations the winching area is to be marked clearly according to a recognized standard.

If the Naval Authority does not prescribe another solution, a marking of the VERTREP position according to STANAG 1162, Type 1 is recommended. It should consist of a boundary line and a rotor centre limit line, which shall be 0,3 m (1') wide lines in contrasting colour to the surrounding paint work of the ship, see Figure 23.1.

3. Helicopter Landing Deck

3.1 Positioning of a helicopter landing area

A helicopter landing area shall be located at the main deck or a higher deck and its position shall be appropriate for the usual military landing procedures. If the landing deck is situated at the stern of the naval ship with superstructures and/or deckhouses beforehand, the angle of possible approaches should be at least 90° at each side of the ship's longitudinal axis.

A location of permanently occupied spaces, like crew accommodation, messes and service spaces under the helicopter deck shall be avoided because of safety reasons. If this is not possible, then the landing deck has to be designed completely as a crash zone, see Section 5, G.3.2.

3.2 Size of a landing deck for one helicopter

3.2.1 The regulations for evaluating the size of the landing deck have to be defined by the Naval Authority. Normally five zones can be distinguished:

- Aiming circle:

The aiming circle is an area with a radius equal to the distance between the axis of the main rotor and the seating position of the pilot.

- Landing zone:

Its position is defined by the location of the landing gear to the axis of the main rotor, which is the centre of the aiming circle. The zone reaches from board to board of the ship. Obstructions should be avoided in this zone.

- Rotor clearance zone:

The length of the rotor clearance zone depends very much on the helicopter type, possible accuracy of helicopter control, etc. The width of this zone extends from board to board.

- Approach and take-off zone:

The approach and take-off zone is extending outside the rotor clearance zone. This zone shall allow approach and take-off manoeuvres within a horizontal range of 180°.

- Crash zone:

The landing zone and all areas outside the landing zone are to be considered as crash zone for the layout of the flight deck.

From the boundary of these zones to fixed superstructures of the ship (e.g. hangar), a safety distance of 1,0 m is recommended.

3.2.2 To assist flight operations and increase safety it is recommendable to clearly mark the ideal helicopter landing position according to the design on the flight deck. If this would be an aiming circle (see 3.2.1) and/or a fore and aft position line, an aft rotor centre limit line, etc. has to be decided according to the regulations of the Naval Authority.

3.3 Sonar hatch

If the helicopters used are provided with a sonar sensor below the helicopter fuselage, a sonar hatch has to be provided in the landing deck for maintenance services.

Normally such a flush deck hatch shall be sized to enable good working conditions. The hatch and its coamings to the landing deck are to meet the strength requirements of the landing deck zone in which it is located. The hatch and its cover shall be watertight and the closing mechanism shall be operated from below the landing deck. Means for at least draining the hatch manually from the flight deck have to be provided.

3.4 Deck for several helicopters

3.4.1 For ships designed for more than one helicopter operating at the same time and with a hangar or accommodation underneath the flight deck, the layout of the complete flight deck depends on the type of flight operations and parking mode defined by the Naval Authority:

- Longitudinal parking
- Angular parking ($\alpha = 45^\circ - 60^\circ$ to longitudinal axis of ship)

Attention has to be paid to:

- Minimum rotor tip clearance distance between two adjacent helicopters and in direction of the superstructures
- From the latter boundary to fixed superstructures of the ship (e.g. "island") a safety distance of 1,0 m is recommended
- The size of the flight deck has to allow safe access to the landed or parked helicopter fuselage from all directions to enable loading and unloading, refuelling, ammunition, fire fighting and some maintenance between the flights

3.4.2 From safety point of view it is recommendable to clearly mark the helicopter positions according to the design for landing/starting and parking on the flight deck. If this would be an aiming circle (see 3.2.1) or crossing axes (e.g. defining also the direction of angular parking) has to be decided according to the regulations of the Naval Authority.




Figure 23.1 Marking of a winching deck

4. Take-Off and Landing Deck for Fixed Wing Aircraft

- Parking zone

Normally the crash zone will be a part of the landing zone.

4.1 Deck areas

The deck area shall be clearly divided into the following zones which may be marked according to the regulations of the Naval Authority:

Note:

If no other values are defined by the Naval Authority, the following total loads may be assumed for the different zones:

- Landing zone
- Crash zone
- Take-off zone

- crash zone:

6 x maximum take-off weight of heaviest aircraft

- landing zone:

3 x maximum take-off weight of heaviest aircraft

- *parking zone, take-off zone:*

1,5 x maximum take-off weight of heaviest aircraft

4.2 Where the flight deck is also part of a weather or superstructure deck, the scantlings are not to be less than those required for decks in the same position.

4.3 If a ramp to assist the take-off of VTOL aircraft is provided at the forward part of the flight deck, this is considered as part of the flight deck.

5. Flight Deck Equipment

5.1 Flight deck sheathing

The flight deck has to meet the following special characteristics:

- Increased structural strength at starting and landing area
- Resistant against aircraft fuel, hydraulic and lubricating oils
- Resistant against dry fire extinguishing powder and foams
- Resistant against defrosting expedient and salt

For general requirements of the sheathing, see Section 19, C.1.1.

5.2 Aircraft fastenings

In the parking zone flush fastening pots to secure the aircraft have to be provided. It is recommended to follow a certain lattice image, to be agreed with the Naval Authority. For tie down forces see Section 5, G 3.2.3.

5.3 Aircraft handling

The devices for the handling of helicopters during landing in the seaway are defined in Chapter 107 -

Ship Operation Installations and Auxiliary Systems, Section 13.

Steam catapults for starting of fixed wing aircraft, landing wire and landing net systems are not part of the Classification. Classification does, however, include the effects of the forces transmitted by these devices into their foundations and the ship's hull on the relevant stress level. Mobile tractors for aircraft handling at the flight deck and in hangars may be series products for airports and are therefore also not subject to Classification.

5.4 Personnel safety measures

5.4.1 Two means of escape have to be provided from the flight deck. They shall be situated at the maximum possible distance from each other and must not start from the landing zone. See also Section 20, C 12.4

5.4.2 A railing to be turned down during helicopter operation or fixed railing at large decks has to be provided around the boundaries of the flight deck.

If hinged railings have to be mechanically/electrically/hydraulically driven, the movement to be controlled from a central point overlooking the entire flight deck (Flight Control Centre - FCC). In any way, the railing elements are to be movable manually.

If not otherwise prescribed by the Naval Authority, the design should meet the following parameters:

- height above deck (for hinged type):

1,2 m minimum
- turned down width:

1,5 m minimum with an inclination of 1 : 10, outer boundary slightly higher than flight deck (approx. 100 mm)

- fastening below flight deck:
0,3 m maximum
- recommended element length:
2,0-2,2 m
- closed, elastic protective net:
fire-retardant material, mesh size approx. 100 mm
- design load: 2kN/m²
- test load: 100 kg from 1 m height to the middle of the net of an element

5.5 Drainage

The flight deck has to be drained directly over board. It has to be avoided that any liquid can penetrate into deckhouses, superstructures or the ship's hull.

C. Hangars

1. Hangar Layout

1.1 There are the following types of hangars:

- Single hangar for one helicopter, arranged symmetrically or asymmetrically
- Double hangar for two helicopters with one integrated area and one or two hangar doors
- Two single hangars for one helicopter each, with or without a corridor in between
- Large area hangar for a large number of helicopters and/or fixed wing aircraft, normally below the flight deck.

1.2 The length and the width of the hangar is to be determined by the parking mode of the harboured aircraft (with folded rotor or wings) and by a save

passage for the crew at all sides of the aircraft as well as the space requirements for repair and maintenance activities. The height of the hangar depends on the height of the harboured aircraft and the normally larger service height necessary for repair and maintenance.

If the hangar is equipped with an overhead travelling crane, the steel structure of the hangar walls and/or roof has to be arranged and increased accordingly, see also E.5.5.

1.3 All operational loads to be determined for the hangar deck, like parking and maintenance of fixed wing aircraft and helicopters, movement of military vehicles and general cargo have to be considered for the design of the scantlings according to the requirements defined in Section 8.

1.4 If the length or width of the hangar deck exceeds 40 m respectively 48 m (if the walls are above watertight bulkheads) special considerations will be given to structural fire protection, see Section 20, C.12..

2. Hangar Equipment

2.1 Hangar sheathing

Normally the same sheathing to be used as for the flight deck, see B.5.1.

2.2 Aircraft and equipment fastening

The same flush fastening pots as in the flight deck will be foreseen in the hangar floor, see B.5.2.

Additionally high points for lashing against horizontal movements at the walls and other lash points on the ceiling to assist during special maintenance operations are to be provided.

All equipment and mobile devices have to be stowed and secured against movement of the ship in a seaway to avoid any danger of damage to material or personnel.

For tie down forces see Section 5, G 3.2.3.

2.3 Ambient conditions

For hangars including equipment and components contained therein the ambient conditions as defined in Section 1, Table 1.2 are valid. If the hangar door, heating and ventilation equipment is laid out to guarantee environmental conditions as defined for inside the ship/all spaces, equipment and components can be designed accordingly. If the environmental situation inside the hangar corresponds - at least part time – to that outside the ship, equipment and components have to be designed for these more severe conditions.

2.4 Electrical equipment

Sufficient lighting as for workshops to enable safe maintenance work on the aircraft is recommended.

For night operations an additional red light system is recommended, see Chapter 105 - Electrical Installations, Section 11.

Measures for earthing of the aircraft at the hangar as well as on the flight deck have to be provided.

For further special measures to be considered for the electrical design and installations, like explosion protected equipment, etc., see Chapter 105 - Electrical Installations.

2.5 Access to the hangar

2.5.1 Hangar contributing to buoyancy

If the superstructure of a helicopter hangar is to be included in buoyancy considerations due to assumed damage of the ship, the following is to be considered.

- The hangar door(s) to the flight deck shall be watertight.
- All doors from the hangar to the other spaces in the superstructure of the ship have to be weathertight with a height of the doorway sill of 600 mm above deck above deck in pos. 1 and 380 mm above decks in pos. 2.

- **BCS** may accept lesser heights of sills alternative solutions with equivalent level safety are provided and recognized. Such alternative solution would be e.g. arrangement of a lock of moderate size behind the hangar exit.

2.5.2 Hangar not contributing to buoyancy

- The hangar door(s) to the flight deck may be weathertight or unprotected.
- All doors from the hangar to the other spaces in the superstructure of the ship which are situated above the most unfavourable damage waterline (equilibrium or intermediate water plane) have to be weathertight with a height of the doorway sill of 600 mm above deck in pos. 1 and 380 mm above decks in pos. 2.
- All doors from the hangar to the other spaces in the superstructure of the ship which are situated below the most unfavourable damage waterline (equilibrium or intermediate water plane) have to be watertight with a height of the doorway sill of 600 mm above deck in pos. 1 and 380 mm above decks in pos. 2.
- **BCS** may accept lesser heights of sills alternative solutions with equivalent level safety are provided and recognized. Such alternative solution would be e.g. arrangement of a lock of moderate size (agreed by **BCS**) behind the hangar exit.

D. Provisions for Drones (UAV)

1. General

In principle the requirements for flight operations with drones (unmanned aerial vehicles – UAV) are analogues to the operation of light and very light helicopters.

But even more critical seems the securing of the drone on deck before starting and immediately after landing, if the ship and its deck are moving in the maximum allowable sea state. For bigger drones mechanical systems will become necessary. The proposed systems are to be fixed to the ship's hull and shall be submitted and agreed with **BCS**.

The transfer to the drone hangar and vice versa is specified in **BCS** Rules for Ship Operation and Auxiliary Systems, Section 13, C.

2. Size of start and landing deck

The size of the start and landing deck may be limited, but depends very much on the D-value of the drone and the accuracy of the flight control of the drones to be used. Therefore the size has to be defined by the Naval Authority.

3. Marking of the deck

The marking on the starting and landing deck may be limited to an aiming circle or crossed lines to fix the starting/landing position.

E. References to Further Requirements for Flight Operations

For the flight operations on naval ships also the requirements according to the following references are to be considered in the Classification process.

1. Strength of the decks

1.1 For loads on decks involved in flight operations see Section 5, G.

1.2 For dimensioning of decks involved in flight operations see Section 8, F.

2. Treatment of fuels and oils

2.1 For storage of aviation fuel, see Chapter 107 Ship Operation Installations and Auxiliary Systems, Section 7, D.

2.2 For storage of lubrication and hydraulic oils, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 7, C.

2.3 For equipment for re- and defuelling of aircraft, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 8, H.

3. Fire fighting

3.1 For fire extinguishing equipment, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, D.

3.2 For foam fire extinguishing systems, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, G.

3.3 For fire extinguishing systems for flight decks and hangars, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, I.

3.4 For portable and mobile fire extinguishers, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 9, M.

3.5 For structural fire protection, see Section 20.

4. Ventilation

For ventilation, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 11, C, 2.13.

5. Aircraft handling

5.1 For helicopter handling systems, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 13, B.

5.2 For drone handling systems, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 13, C.

5.3 For hangar doors, see Chapter 107 - Ship Operation Installations and Auxiliary Systems, Section 13, D.

5.4 For flight deck lifts, see Chapter 107 – Ship Operation Installations and Auxiliary Systems, Section 13, E.

5.5 For cranes in hangars, see Chapter 107 – Ship Operation Installations and Auxiliary Systems, Section 13, B.